

---

---

# VIEWERS' REPORT

—IN—

DITCH PROCEEDINGS.

---

---

"D"

Rathbun Ditch  
No 14

---

Specifications

---

---

No. 680.— Pioneer Press Co., St. Paul, Minn.

Filed August 12<sup>th</sup> 1891  
W. M. Putnam  
County Auditor

EXHIBIT 2 OF VIEWERS' REPORT IN DITCH PROCEEDINGS.

Showing Time and Manner in which same must be done. Ditch No. ....

SECTION	TIME WITHIN WHICH WORK MUST BE DONE	MANNER IN WHICH WORK MUST BE DONE	MATERIALS USED	COST OF MATERIALS AND WORK
Stake No. <u>1</u> to Stake No. <u>200</u>	Sept <del>July</del> 1 <sup>st</sup> 1892	<p>Earth from ditch to be thrown in old ditch whenever shrub hends are cut off and old ditch is within eight feet of new, at all other points to be thrown back at least two feet -</p> <p>When there is stiff sod - sod may be laid upside down and flush with edge of ditch and balance thrown beyond it</p>		\$ 3.00
		<p>Bridge at station 1411 to be taken up, and replaced after ditch is dry using <del>same</del> material now in bridge</p> <p>Stakes are set on right bank of ditch except from 155+74 on left side to 160.32</p> <p>Stakes on cuts 160.32 to 176+42</p>		