EXHIBIT 2.

VIEWERS' REPORT

—IN—

DITCH PROCEEDINGS.

Ditch No 28

No. 680.—Pioneer Press Co., St. Paul, Minn.

Office of County Auditor,
County of Aitkin, Minn.,
Filed Feb. 19, 1898.
G. W. Pittman,
Co. Auditor.

EXHIBIT 2 OF VIEWERS' REPORT IN DITCH PROCEEDINGS.

Showing Time and Manner in which same must be done. Ditch No. 28

SECTION	TIME WITHIN WHICH WORK MUST BE DONE	MANNER IN WHICH WORK MUST BE DONE	MATERIALS USED	COST OF MATERIALS AND WORK
Main Ditch Stake No. 0 TO Stake No. 119	Nov 1st 1898	Earth taken from Ditch to be thrown at least one foot from Edge of same From 4.47 to Sta 12 and from Sta 90 to 117 main line ~~take~~ Earth to be thrown to the left and from 12.25 to 14.26 Branch 6 also to be thrown to the left to make room —		
Cell Branches No 0 to 7	Same date	Bridges At Sta 41 Branch No 3 & at Sta 8 Branch No 6 to be made of 10 plank Each 3"x12"x16' the same to be laid on stringers from to Each bridge made of Tamarac or oak not less than 8 in diam and 10 ft long — Each bridge to have two bank sills of same size and length of stringers Plank to be spiked down to stringers Stakes are set on ~~right~~ left Edge of ditch		Estimated Cost of Each Bridge $7.00