Repair Ditch 28

F. C. Richardson	$47,733.66
Fulton & Nelson	48,814.83
John Kohler	50,000.00
United Dredging Co	49,506.47

323 Stations of 6 foot Bottom Average
Depth 6 ft 79,373 cu. yds of excavation
Estimated at $19,959.90 - Clearing and culverts
estimated at $719. Suitable for dry land machine

355 Stations of 3 foot Bottom Average Depth 5 foot
53,319 cu. yds of excavation estimated at $ 15,995.70
Clearing and Culverts estimated at 1154.00 - Suitable
for dry land machine and hand work.
Total Estimated Cost $38,828.60

Located 3 miles East of Cedar Minn.

K. C. RICHARDSON

DRAINAGE CONTRACTOR AND ENGINEER

ANOKA, MINN.

August 24th, 1920.

County Auditor, Anoka County Minn.

I hereby agree to construct County Ditch No. 28 for the following prices:

Main ditch and all branches with 6 ft. bottom for the sum of 3 1/4 per cu. yd.

All other branches for the sum of 37¢ per cu. yd.

All clearing for the sum of $ 1400.00

All Culverts for the sum of $ 2000.00

K. C. Richardson

I am to be awarded job in two contracts to be decided on between Engineer & Contractor at a later date. The idea being to seperate the so called land work from the machine work.

K. C. Richardson

Ditch No.

PROPOSAL FOR DITCHING

TO

Filed this _____ *day*

of _____ *19* _____

County Auditor.

MILLER-DAVIS COMPANY MINNEAPOLIS

Form 2724—Proposal For Ditching Contract. Miller-Davis Company, Mfg. Stationers, Minneapolis, Minn

Anoka ~~Aug 24~~ Minn. Aug 24 1920

To the County Auditor of _____ **County, Minnesota.**

SIR: I *do hereby agree to do all the work, furnish all teams and implements of every nature and description necessary to fully complete all that part of* _____ *Ditch No.* 28 *as shall be awarded to the undersigned, in a first class and workmanlike manner and in strict accordance with the plans and specifications for said ditch on file in the office of the County Auditor of* Anoka *County, Minnesota, for* 30 percent above the estimate of the engineer in charge *per cubic yard, and will agree to fully complete said ditch by the time fixed in said specifications.* or $50000 for the whole job

Repair

And will agree to enter into contract within five days from the date of your acceptance of this proposal and will furnish such sureties for the faithful performance of the work as shall be required by the County Auditor of said Anoka *County.*

Should any default be made on my part in carrying out the conditions of this proposition and in entering into contract and furnishing the required sureties, the sum of Thirty percent above the engineers estimate *Dollars, which I have this* or $50000 for the whole job *day deposited with my bid shall be forever forfeited to the County of* Anoka

Fifty Thousand Dollars for all equation Culverts and Clearing

John Kohler

this bid is for the whole job or none

Postoffice Frazee Minn

Ditch No.

PROPOSAL FOR DITCHING

TO

Filed this _____ *day*

of _____ *19*_____

County Auditor.

MILLER-DAVIS COMPANY MINNEAPOLIS

Form 2724—Proposal For Ditching Contract. Miller-Davis Company, Mfg. Stationers, Minneapolis, Minn

Anoka County, *Minn.* August 24th. *19* 20.

To the County Auditor of Anoka **County, Minnesota.**

SIR: We *do hereby agree to do all the work, furnish all teams and implements of every nature and description necessary to fully complete all that part of* Main Ditch and Branches *Ditch No.* 28 *as shall be awarded to the undersigned, in a first class and workmanlike manner and in strict accordance with the plans and specifications for said ditch on file in the office of the County Auditor of* Anoka *County, Minnesota, for* ~~32¢ per cu.yd. for six~~ foot bottom ditch and 37¢ per cu.yd. for 3 ft. ditch clearing and culverts *per cubic yard, and will agree to fully complete said ditch by the time fixed in said specifications.* 3,687.44

And will agree to enter into contract within five days from the date of your acceptance of this proposal and will furnish such sureties for the faithful performance of the work as shall be required by the County Auditor of said Anoka *County.*

Should any default be made on my part in carrying out the conditions of this proposition and in entering into contract and furnishing the required sureties, the sum of $3,000.00 Three thousand *Dollars, which I have this day deposited with my bid shall be forever forfeited to the County of* Anoka

Fulton & Nelson

By Peter Nelson

Postoffice

Completed November 21st. 1921.
Lump Sum according to plans
for clearing and culverts.

Ditch No.

PROPOSAL FOR DITCHING

TO

Filed this *day*

of *19*

County Auditor.

MILLER-DAVIS COMPANY MINNEAPOLIS

Form 2724—Proposal For Ditching Contract. Miller-Davis Company, Mfg. Stationers, Minneapolis, Minn

Anoka Minn. Aug 24 1920

To the County Auditor of Anoka County, Minnesota.

SIR: We *do hereby agree to do all the work, furnish all teams and implements of every nature and description necessary to fully complete all that part of* Co *Ditch No.* 28 *as shall be awarded to the undersigned, in a first class and workmanlike manner and in strict accordance with the plans and specifications for said ditch on file in the office of the County Auditor of* Anoka *County, Minnesota, for* 27½ above Eng Est ~~*per cubic yard,*~~ *and will agree to fully complete said ditch by the time fixed in said specifications.*

And will agree to enter into contract within five days from the date of your acceptance of this proposal and will furnish such sureties for the faithful performance of the work as shall be required by the County Auditor of said Anoka *County.*

Should any default be made on my part in carrying out the conditions of this proposition and in entering into contract and furnishing the required sureties, the sum of $5000 Five Thousand & no/100 *Dollars, which I have this day deposited with my bid shall be forever forfeited to the County of* Anoka

United Dredging Co

Per H Arpin Pres

Postoffice Grand Rapids, Wis