

EXHIBIT 2

---

---

**ENGINEER'S REPORT**  
**IN**  
**DITCH PROCEEDINGS**

---

---

# EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Repairs County Ditch No. 31

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section	(7) Estimated Cost, per Section	
				in old Ditch	To be Removed	\$	CTS.		\$	CTS.
Between Stake No. 16 and Stake No. 17	2.7	2.0	7.4	20.4	32.2	12				3 86
Between Stake No. 18 and Stake No. 19	3.0		8.6	17.8	43.7		5 24			
Between Stake No. 20 and Stake No. 21	3.3		8.6	17.8	47.0		5 64			
Between Stake No. 22 and Stake No. 23	2.8		7.6	17.0	41.5		4 98			
Between Stake No. 24 and Stake No. 25	2.8		7.6	17.8	31.8		3 82			
Between Stake No. 26 and Stake No. 27	2.9		7.8	17.8	34.8		4 18			
Between Stake No. 28 and Stake No. 29	2.4		6.8	19.6	27.4		3 29			
Between Stake No. 30 and Stake No. 31	2.6		7.2	18.5	23.4		2 81			
Between Stake No. 32 and Stake No. 33	2.3		6.6	13.3	28.6		3 43			
Between Stake No. 34 and Stake No. 35	2.3		6.6	13.3	23.4		2 81			
Between Stake No. 36 and Stake No. 37	1.8		5.6	13.3	18.6		2 23			
Between Stake No. 38 and Stake No. 39	2.1		6.2	16.7	12.9		1 55			
Between Stake No. 40 and Stake No. 41	2.2		6.4	17.8	16.3		1 96			
Between Stake No. 42 and Stake No. 43	2.1		6.2	23.3	10.8		1 30			
Between Stake No. 44 and Stake No. 45	1.9		5.8	24.4	5.2		62			
Between Stake No. 46 and Stake No. 47	1.8		5.6	21.1	6.3		76			
Between Stake No. 48 and Stake No. 49	1.8		5.6	17.8	6.4		77			
Between Stake No. 50 and Stake No. 51	1.7	5.4	16.7	8.5	1 02					
Between Stake No. 52 and Stake No. 53	1.8	5.6	18.9	6.3	76					

425.1

\$ 51.03

Total Estimated Cost of Whole Work, \$ .....

# EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Redburn County Ditch No. 31

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section	(7) Estimated Cost per Section	
				cu. yds. in old Ditch	cu. yds. to be Removed	\$	CTS.		\$	CTS.
Between Stake No. 36 and Stake No. 37	1.8	2.0	5.6	20.0	16.7	12				2 00
Between Stake No. 38 and Stake No. 39	2.8		10.2	43.3	28.2					3 38
Between Stake No. 40 and Stake No. 41	4.1		11.2	65.0	39.3					4 72
Between Stake No. 42 and Stake No. 43	4.6		8.0	40.0	41.6					4 99
Between Stake No. 44 and Stake No. 45	3.0		9.4	31.1	37.1					4 45
Between Stake No. 46 and Stake No. 47	3.7		8.6	31.1	40.4					4 85
Between Stake No. 48 and Stake No. 49	3.3		10.0	51.1	27.1					3 25
Between Stake No. 50 and Stake No. 51	4.0		10.4	60.0	32.6					3 91
Between Stake No. 52 and Stake No. 53	4.2		10.4	75.0	21.4					2 57
Between Stake No. 54 and Stake No. 55	4.2		15.8	133.7	23.9					2 87
	6.9		11.2	72.2	65.3					7 84
	4.6		8.6	21.5	67.4					8 09
	3.3		8.4	20.0	44.8					5 38
	3.2		7.0	17.8	34.8					4 18
	2.5		8.8	20.0	35.6					4 27
	3.4		8.8	19.6	48.6					5 83
	3.4		8.8	19.6	48.6					5 83
	2.5		7.0	14.1	41.5					4 98
	2.6		7.2	12.6	31.8					3 82

126.7

\$87.21

Total Estimated Cost of Whole Work, \$.....

# EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Repairs County Ditch No. 31

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section	(7) Estimated Cost per Section							
				Cu. Yds. in old Ditch	Cu. Yds. to be Removed	\$	CTS.		\$	CTS.						
Between Stake No. 55 and Stake No. 56	2.6 2.0	2.0	7.2 6.0	10.4	26.3	12				315						
Between Stake No. 57 and Stake No. 58	2.0 1.9		6.0 5.8	8.9	20.7						20.7	222				
Between Stake No. 59 and Stake No. 60	2.0 1.7		6.0 5.4	12.2	17.4						15.2	209				
Between Stake No. 61 and Stake No. 62	1.6 2.5		5.2 7.0	8.3	15.0						20.8	182				
Between Stake No. 63 and Stake No. 64	4.1 5.4		10.2 12.8	75.9	8.9						9.1	180				
Between Stake No. 65 and Stake No. 66	7.1 6.4		16.2 14.8	180.7	9.4						7.4	250				
Between Stake No. 67 and Stake No. 68	6.2 5.6		14.4 13.2	161.1	4.6						3.7	107				
Between Stake No. 69 and Stake No. 70	4.9 5.7		11.7 13.4	118.0	2.9						0.9	109				
Between Stake No. 71 and Stake No. 72	1.8 2.6		5.6 7.2	23.7	44.5						19.3	112				
Between Stake No. 73 and Stake No. 74	2.2 2.3		6.4 6.6	18.5	20.8						18.9	89				
																55
																44
																35
																11
																534
																232
																250
																226

284.3

34.10

Total Estimated Cost of Whole Work, \$ .....

# EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Repairs County Ditch No. 31

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section		(7) Estimated Cost, per Section, Excavation
				cu. yds.	cu. yds.	\$	CTS.	\$	CTS.	\$
Between Stake No. 74 and Stake No. 75	2.3	2.0	6.6	in old Ditch	To be Removed		12			294
Between Stake No. 76 and Stake No. 77	2.4	"	6.8	14.8	24.5					253
Between Stake No. 77 and Stake No. 77+50	2.2	"	6.4	15.6	21.1					284
Between Stake No. 77+50 and Stake No. 77	2.5	"	7.0	15.6	23.7					258
Between Stake No. 77+50 and Stake No. 77+50	2.5	"	7.0	20.4	21.5					\$1089
Between Stake No. 77+50 and Stake No. 77+50					90.8					
Between Stake No. 77+50 and Stake No. 77+50										
Between Stake No. 77+50 and Stake No. 77+50										
Between Stake No. 77+50 and Stake No. 77+50										
Between Stake No. 77+50 and Stake No. 77+50										
Between Stake No. 77+50 and Stake No. 77+50										
Between Stake No. 77+50 and Stake No. 77+50										
Between Stake No. 77+50 and Stake No. 77+50										

Total Estimated Cost of Whole Work, \$.....

# EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Repairs County Ditch No. 31

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section	(7) Estimated Cost per Section	
				Cu. Yds. in old Ditch	Cu. Yds. to be Removed	\$	CTS.		\$	CTS.
Between Stake No. 0 and Stake No. 1	1.6	2.0	5.2	9.1	14.2	12				170
Between Stake No. 2 and Stake No. 3	1.8		5.6	9.4	15.8					190
Between Stake No. 4 and Stake No. 5	2.0		6.0	10.5	16.9					203
Between Stake No. 6 and Stake No. 7	1.6		5.2	10.0	15.2					182
Between Stake No. 7 and Stake No. 7+85	2.0		6.0	10.0	15.2					182
Between Stake No. 6 and Stake No. 7	2.2		6.4	11.7	20.2					242
Between Stake No. 7 and Stake No. 7+85	1.8		5.6	11.1	18.5					222
Between Stake No. 7+85 and Stake No. 7+85	2.2		6.4	9.4	15.8					190
Between Stake No. 7+85 and Stake No. 7+85					131.8					\$1581

Total Estimated Cost of Whole Work, \$ .....



EXHIBIT 3.

---

---

# VIEWERS' REPORT

IN

## DITCH PROCEEDINGS.

---

---

*Engineer's*  
Exhibit 3 of ~~VIEWERS~~ Report in Ditch Proceedings.

*Statement of Actual Time Engaged and Compensation Charged and Expenses Incurred.*

WORK DONE AND SPECIFICATION OF EXPENSE CHARGES.	NO. OF DAYS EMPLOYED	AMOUNT CHARGED PER DAY	TOTAL AMOUNT CHARGED	OTHER EXPENSES INCURRED
<i>Wayne S. Ridgely, Engineer</i>	10	5 00	50 00	
<i>H. E. Richardson Asst Engr.</i>	10	5 00	50 00	
<i>Ross Catter Rodman</i>	6	2 00	12 00	
<i>Keith Caldwell Steamman</i>	6	2 00	12 00	
<i>Linney Board</i>	6		17 00	
<i>Railroad fare</i>			8 96	
<i>Hotel</i>			1 35	
<i>Bond</i>			10 00	
<i>Total =</i>			<u>\$176.31</u>	