

EXHIBIT 2.

---

# Engineer's Report

IN

## Ditch Proceedings.

---

*Filed April 11<sup>th</sup> 1904*  
*Selden M<sup>c</sup>Gaffey*  
*C. Audubon*

*P. M. O.*

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch N<sup>o</sup> 1.

SECTION		(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD \$ CTS.		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION \$ CTS.		(7) TOTAL ESTIMATED COST PER SECTION \$ CTS.	
Between Stake No.	0	2.0	2.0	6.0							
and Stake No.	1				30						
Between Stake No.	1	2.0	"	6.0							
and Stake No.	2				39						
Between Stake No.	2	2.8	"	7.6							
and Stake No.	3				41						
Between Stake No.	3	2.2	"	6.4							
and Stake No.	4				44						
Between Stake No.	4	3.0	"	8.0							
and Stake No.	5				78						
Between Stake No.	5	4.4	"	10.8							
and Stake No.	6				102						
Between Stake No.	6	4.3	"	10.6							
and Stake No.	7				91						
Between Stake No.	7	3.8	"	9.6							
and Stake No.	8				81						
Between Stake No.	8	3.8	"	9.6							
and Stake No.	9				60						
Between Stake No.	9	2.5	"	7.0							
and Stake No.	10				46						
								Total Estimated Cost of Whole Work, \$-----			

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch #1

SECTION		(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD \$ CTS.		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION \$ CTS.		(7) TOTAL ESTIMATED COST PER SECTION \$ CTS.	
Between Stake No.	10	2.8	2.0	7.6							
and Stake No.	11				55						
Between Stake No.	11	3.1	"	8.2							
and Stake No.	12				60						
Between Stake No.	12	3.2	"	8.4							
and Stake No.	13				58						
Between Stake No.	13	2.9	"	7.8							
and Stake No.	14				41						
Between Stake No.	14	2.1	"	6.2							
and Stake No.	15				38						
Between Stake No.	15	2.6	"	7.2							
and Stake No.	16				57						
Between Stake No.	16	3.5	"	9.0							
and Stake No.	17				71						
Between Stake No.	17	3.5	"	9.0							
and Stake No.	18				65						
Between Stake No.	18	3.1	"	8.2							
and Stake No.	19				60						
Between Stake No.	19	3.2	"	8.4							
and Stake No.	20				59						
								Total Estimated Cost of Whole Work, \$-----			

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch No 1

SECTION		(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD \$ CTS.		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION \$ CTS.			(7) TOTAL ESTIMATED COST PER SECTION \$ CTS.	
Between Stake No.	20	3.2	2.0	8.04	57							
and Stake No.	21											
Between Stake No.	21	3.1	"	8.2	60							
and Stake No.	22											
Between Stake No.	22	3.2	"	8.4	70							
and Stake No.	23											
Between Stake No.	23	3.7	"	9.4	70							
and Stake No.	24											
Between Stake No.	24	3.2	"	8.4	57							
and Stake No.	25											
Between Stake No.	25	2.9	"	7.8	51							
and Stake No.	26											
Between Stake No.	26	2.8	"	7.6	47							
and Stake No.	27											
Between Stake No.	27	2.6	"	7.2	52							
and Stake No.	28											
Between Stake No.	28	3.1	"	8.2	68							
and Stake No.	29											
Between Stake No.	29	3.7	"	9.4	81							
and Stake No.	30											
Total Estimated Cost of Whole Work, \$												

# EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch No 1.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION			(7) TOTAL ESTIMATED COST PER SECTION	
					\$	CTS.		\$	CTS.	\$	CTS.
Between Stake No. 30 and Stake No. 31	3.9	2.0	9.8	99							
Between Stake No. 31 and Stake No. 32	4.6	2.0	11.2	111							
Between Stake No. 32 and Stake No. 33	4.5	"	11.0	125							
Between Stake No. 33 and Stake No. 34	5.3	"	12.6	99							
Between Stake No. 34 and Stake No. 35	3.2	"	8.4	65							
Between Stake No. 35 and Stake No. 36	3.4	"	8.8	75							
Between Stake No. 36 and Stake No. 37	3.8	"	9.6	93							
Between Stake No. 37 and Stake No. 38	4.4	"	10.8	99							
Between Stake No. 38 and Stake No. 39	4.1	"	10.2	115							
Between Stake No. 39 and Stake No. 40	5.2	"	12.4	85							
							Total Estimated Cost of Whole Work, \$				

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch N<sup>o</sup> 1 Concluded

SECTION		(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD \$ CTS.		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION \$ CTS.		(7) TOTAL ESTIMATED COST PER SECTION \$ CTS.	
Between Stake No.	40	2.6	2.0	7.2							
and Stake No.	41				41						
Between Stake No.	41	2.4	"	6.8							
and Stake No.	42	2.6	"	7.2	41						
Between Stake No.					2837		\$ 08.		\$ 226 96		
and Stake No.											
Between Stake No.											
and Stake No.											
Between Stake No.											
and Stake No.											
Between Stake No.											
and Stake No.											
Between Stake No.											
and Stake No.											
Between Stake No.											
and Stake No.											
Total Estimated Cost of Whole Work, \$											