

EXHIBIT 2.

Engineer's Report

IN

Ditch Proceedings.

Filed April 11th 1904
Selden M. Guppy
Co. Auditor

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch No 8.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION		(7) TOTAL ESTIMATED COST PER SECTION	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 0 and Stake No. 1	1.8	2.0	5.6	29						
Between Stake No. 1 and Stake No. 2	2.1	"	6.2	34						
Between Stake No. 2 and Stake No. 3	2.3	"	6.6	34						
Between Stake No. 3 and Stake No. 4	2.1	"	6.2	31						
Between Stake No. 4 and Stake No. 5	2.0	"	6.0	26						
Between Stake No. 5 and Stake No. 6	1.7	"	5.4	20						
Between Stake No. 6 and Stake No. 7	1.4	"	4.8	22						
Between Stake No. 7 and Stake No. 7+67	1.9	"	5.8	21						
Between Stake No. 7+67 and Stake No. 7+73	2.3	"	6.6	4						
Between Stake No. 7+73 and Stake No. 7+81	4.1	5.0	5.0	7						

Total Estimated Cost of Whole Work, \$-----

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch No 8.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD \$ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION \$ CTS.	(7) TOTAL ESTIMATED COST PER SECTION \$ CTS.
Between Stake No. 7+81 and Stake No. 7+86	4.1	5.0	5.0	3		Bridges built and enlarged \$15 00	
Between Stake No. 7+86 and Stake No. 8	1.9	2.0	5.8	2			
Between Stake No. 8 and Stake No. 9	0.3	"	2.6	8			
Between Stake No. 9 and Stake No. 10	1.2	"	4.4	17			
Between Stake No. 10 and Stake No. 11	1.6	"	5.2	30			
Between Stake No. 11 and Stake No. 12	2.4	"	6.8	288		} #08 Sta. 0 to Sta 11. Sand Cut. Sta. 11 to Sta. 13	\$ 23 04
Between Stake No. 12 and Stake No. 12+15	4.1	"	10.2	64			
Between Stake No. 12+15 and Stake No. 13	6.1	4	14.2	20			
Between Stake No. 13 and Stake No. 14	2.3	" 8.6	6.6	166		\$15 Sta. 11 to Sta. 13	\$ 24 90
Between Stake No. 14 and Stake No. 15	1.8	3.0	6.6	31			
				38			

Total Estimated Cost of Whole Work, \$-----

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch No 8

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION		(7) TOTAL ESTIMATED COST PER SECTION		
					\$	CTS.	\$	CTS.	\$	CTS.	
Between Stake No. 15 and Stake No. 16	2.3	3.0	7.6	48							
Between Stake No. 16 and Stake No. 17	2.5	"	8.0	41							
Between Stake No. 17 and Stake No. 18	1.8	"	6.6	41							
Between Stake No. 18 and Stake No. 19	2.5	"	8.0	51							
Between Stake No. 19 and Stake No. 20	2.5	"	8.0	53							
Between Stake No. 20 and Stake No. 21	2.6	"	8.2	55							
Between Stake No. 21 and Stake No. 22	2.7	"	8.4	59							
Between Stake No. 22 and Stake No. 23	2.8	"	8.6	60							
Between Stake No. 23 and Stake No. 24	2.8	"	8.6	60							
Between Stake No. 24 and Stake No. 25	2.8	"	8.6	60							
<i>Total Estimated Cost of Whole Work, \$</i>											

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch No. 8.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION		(7) TOTAL ESTIMATED COST PER SECTION		
					\$	CTS.	\$	CTS.	\$	CTS.	
Between Stake No. 25 and Stake No. 26	2.8	3.0	8.6	60							
Between Stake No. 26 and Stake No. 27	2.8	"	8.6	60							
Between Stake No. 27 and Stake No. 28	2.8	"	8.6	62							
Between Stake No. 28 and Stake No. 29	2.9	"	8.8	63							
Between Stake No. 29 and Stake No. 30	2.9	"	8.8	63							
Between Stake No. 30 and Stake No. 31	2.9	"	8.8	67							
Between Stake No. 31 and Stake No. 32	3.1	"	9.2	73							
Between Stake No. 32 and Stake No. 33	3.3	"	9.6	75							
Between Stake No. 33 and Stake No. 34	3.2	"	9.4	72							
Between Stake No. 34 and Stake No. 35	3.1	"	9.2	75							
<i>Total Estimated Cost of Whole Work, \$</i>											

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch N^o 8.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION				(7) TOTAL ESTIMATED COST PER SECTION	
					\$	CTS.	\$	CTS.	\$	CTS.		
Between Stake No. 35 and Stake No. 36	3.4	3.0	9.8	86								
Between Stake No. 36 and Stake No. 37	3.7	"	10.4	88								
Between Stake No. 37 and Stake No. 38	3.5	"	10.0	81								
Between Stake No. 38 and Stake No. 39	3.3	"	9.6	81								
Between Stake No. 39 and Stake No. 40	3.5	"	10.0	88								
Between Stake No. 40 and Stake No. 41	3.7	"	10.4	92								
Between Stake No. 41 and Stake No. 42	3.7	"	10.4	94								
Between Stake No. 42 and Stake No. 43	3.8	"	10.6	98								
Between Stake No. 43 and Stake No. 44	3.9	"	10.8	102								
Between Stake No. 44 and Stake No. 45	4.0	"	11.0	106								
<i>Total Estimated Cost of Whole Work, \$</i>							-----					

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Branch No 8 loud...

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD		(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION		(7) TOTAL ESTIMATED COST PER SECTION	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 45 and Stake No. 46	4.1	3.0	11.2	110						
Between Stake No. 46 and Stake No. 47	4.2	"	11.4	110						
Between Stake No. 47 and Stake No. 48	4.1	"	11.2	106						
Between Stake No. 48 and Stake No. 48+56	4.0 4.4	" "	11.0 11.8	65						
Between Stake No. 48+56 and Stake No. 48+56				2574			\$08	Sta. 13 to Sta 48+56	\$20592	
Between Stake No. 48+56 and Stake No. 48+56										
Between Stake No. 48+56 and Stake No. 48+56										
Between Stake No. 48+56 and Stake No. 48+56										
Between Stake No. 48+56 and Stake No. 48+56										
Between Stake No. 48+56 and Stake No. 48+56										
Between Stake No. 48+56 and Stake No. 48+56										
Total Estimated Cost of Whole Work, \$									268	86