For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 77	4.3	4.0	12.6				
and Stake No. 78				133			
Between Stake No. 78	4.3	5.0	13.6	4912	09	Sta. 40 to Sta. 78 $442 08	
and Stake No. 79				154			
Between Stake No. 79	4.5	5.0	14.0				
and Stake No. 80				164			
Between Stake No. 80	4.7	"	14.4	318	10	Sta 78 to Sta 80 31 80	
and Stake No. 81				178			
Between Stake No. 81	5.0	"	15.0				
and Stake No. 82				233			
Between Stake No. 82	6.5	"	18.0			Sand cut, Brush + Trees.	
and Stake No. 83				230			
Between Stake No. 83	4.9	"	14.8				
and Stake No. 84				154			
Between Stake No. 84	3.9	"	12.8	795	20	Sta 80 to Sta 84 159 00	
and Stake No. 85				142			
Between Stake No. 85	4.4	"	13.8		10	Sta 84 to Sta. 87. 46.80	
and Stake No. 86				154			
Between Stake No. 86	4.4	"	13.8				
and Stake No. 87				172			
				468			

*Total Estimated Cost of Whole Work, $*_____

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 87	5.1	5.0	15.2				
and Stake No. 88				224			
Between Stake No. 88	6.2	"	17.4				
and Stake No. 89				254			
Between Stake No. 89	6.1	"	17.2				
and Stake No. 90				262	Sand Cut, Brush & Trees		
Between Stake No. 90	6.5	"	18.0				
and Stake No. 91				250			
Between Stake No. 91	5.7	"	16.4				
and Stake No. 92				186			
Between Stake No. 92	4.3	"	13.6	1176	20	Sta 87 to Sta 92	# 235 20
and Stake No. 93				139			
Between Stake No. 93	3.9	"	12.8				
and Stake No. 94				139			
Between Stake No. 94	4.3	"	13.6				
and Stake No. 95				157			
Between Stake No. 95	4.6	"	14.2				
and Stake No. 96				149			
Between Stake No. 96	4.0	"	13.0				
and Stake No. 97				129			

*Total Estimated Cost of Whole Work, $*_____

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 97	3.8	5.0	12.6				
and Stake No. 98				129			
Between Stake No. 98	4.0	"	13.0				
and Stake No. 99				134			
Between Stake No. 99	4.0	"	13.0				
and Stake No. 100				137			
Between Stake No. 100	4.1	"	13.2				
and Stake No. 101				142			
Between Stake No. 101	4.2	"	13.4				
and Stake No. 102				142			
Between Stake No. 102	4.1	"	13.2				
and Stake No. 103				139			
Between Stake No. 103	4.1	"	13.2				
and Stake No. 104				137			
Between Stake No. 104	4.0	"	13.0				
and Stake No. 105				134			
Between Stake No. 105	4.0	"	13.0				
and Stake No. 106				134			
Between Stake No. 106	4.0	"	13.0				
and Stake No. 107				139			
						Total Estimated Cost of Whole Work, $	

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 107	4.2	5.0	13.4				
and Stake No. 108				144			
Between Stake No. 108	4.2	"	13.4				
and Stake No. 109				139			
Between Stake No. 109	4.0	"	13.0				
and Stake No. 110				139			
Between Stake No. 110	4.2	"	13.4				
and Stake No. 111				139			
Between Stake No. 111	4.0	"	13.0				
and Stake No. 112				139			
Between Stake No. 112	4.2	"	13.4				
and Stake No. 113				147			
Between Stake No. 113	4.3	"	13.6				
and Stake No. 114				142			
Between Stake No. 114	4.0	"	13.0				
and Stake No. 115				137			
Between Stake No. 115	4.1	"	13.2				
and Stake No. 116				129			
Between Stake No. 116	3.7	"	12.4				
and Stake No. 117				127			
						Total Estimated Cost of Whole Work, $	

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 117	4.0	5.0	13.0				
and Stake No. 118				134			
Between Stake No. 118	4.0	5.0	13.0				
and Stake No. 119				137			
Between Stake No. 119	4.1	"	13.2				
and Stake No. 120				147			
Between Stake No. 120	4.4	"	13.8				
and Stake No. 121				144			
Between Stake No. 121	4.0	"	13.0				
and Stake No. 122				147			
Between Stake No. 122	4.5	"	14.0				
and Stake No. 123				147			
Between Stake No. 123	4.0	"	13.0				
and Stake No. 124				134			
Between Stake No. 124	4.0	"	13.0				
and Stake No. 125				139			
Between Stake No. 125	4.2	"	13.4				
and Stake No. 126				149			
Between Stake No. 126	4.4	"	13.8				
and Stake No. 127				155			
						Total Estimated Cost of Whole Work, $	

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 127	4.4	5.0	13.8				
and Stake No. 128				149			
Between Stake No. 128	4.2	"	13.4				
and Stake No. 129				149			
Between Stake No. 129	4.4	"	13.8				
and Stake No. 130				149			
Between Stake No. 130	4.2	"	13.4				
and Stake No. 131				139			
Between Stake No. 131	4.0	"	13.0				
and Stake No. 132				139			
Between Stake No. 132	4.2	5.0	13.4				
and Stake No. 133				134			
Between Stake No. 133	3.8	"	12.6				
and Stake No. 134				127			
Between Stake No. 134	3.9	"	12.8				
and Stake No. 135				132			
Between Stake No. 135	4.0	"	13.0				
and Stake No. 136				144			
Between Stake No. 136	4.4	6.0	14.8	6157	10	Sta. 92 to Sta. 136 — $ 615 70	
and Stake No. 137				204			

*Total Estimated Cost of Whole Work, $*_____

No. 2562—Engineer's Report in Ditch Proceedings.

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 137	5.6	6.0	17.2				
and Stake No. 138				264			
Between Stake No. 138	6.3	"	18.6				
and Stake No. 139				229			
Between Stake No. 139	4.5	"	15.0				
and Stake No. 140				184			
Between Stake No. 140	4.8	"	15.6				
and Stake No. 141				181			
Between Stake No. 141	4.4	"	14.8				
and Stake No. 142				181			
Between Stake No. 142	4.8	"	15.6				
and Stake No. 143				173			
Between Stake No. 143	4.1	"	14.2				
and Stake No. 144				187			
Between Stake No. 144	5.3	"	16.6				
and Stake No. 145				187			
Between Stake No. 145	4.1	"	14.2				
and Stake No. 146				154			
Between Stake No. 146	4.1	"	14.2				
and Stake No. 147				160			
						Total Estimated Cost of Whole Work, $	

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 147	4.3	6.0	14.6				
and Stake No. 148				163			
Between Stake No. 148	4.2	"	14.4				
and Stake No. 149				157			
Between Stake No. 149	4.1	"	14.2				
and Stake No. 150				160			
Between Stake No. 150	4.3	"	14.6				
and Stake No. 151				165			
Between Stake No. 151	4.3	"	14.6				
and Stake No. 152				165			
Between Stake No. 152	4.3	"	14.6				
and Stake No. 153				168			
Between Stake No. 153	4.4	"	14.8				
and Stake No. 154				168			
Between Stake No. 154	4.3	"	14.6				
and Stake No. 155				168			
Between Stake No. 155	4.4	"	14.8				
and Stake No. 156				179			
Between Stake No. 156	4.7	"	15.4				
and Stake No. 157				179			
						Total Estimated Cost of Whole Work, $	

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 157	4.4	6.0	14.8				
and Stake No. 158				173			
Between Stake No. 158	4.5	"	15.0				
and Stake No. 159				170			
Between Stake No. 159	4.3	"	14.6				
and Stake No. 160				170			
Between Stake No. 160	4.5	"	15.0				
and Stake No. 161				173			
Between Stake No. 161	4.4	"	14.8				
and Stake No. 162				163			
Between Stake No. 162	4.1	"	14.2				
and Stake No. 163				163			
Between Stake No. 163	4.4	"	14.8				
and Stake No. 164				163			
Between Stake No. 164	4.1	"	14.2				
and Stake No. 165				157			
Between Stake No. 165	4.2	"	14.4				
and Stake No. 166				165			
Between Stake No. 166	4.4	"	14.8				
and Stake No. 167				175			
						Total Estimated Cost of Whole Work, $	

For sale by Miller-Davis Printing Co., Mfg. Stationers, Minneapolis.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 41 Main Ditch

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) ESTIMATED COST PER CUBIC YARD $ CTS.	(6) CHARACTER OF OTHER EXPENSES, INCLUDING PRELIMINARY EXPENSES AND EXPENSES OF INSPECTING WORK UNTIL COMPLETED, WITH TOTAL PER SECTION $ CTS.	(7) TOTAL ESTIMATED COST PER SECTION $ CTS.
Between Stake No. 167	4.6	6.0	15.2				
and Stake No. 168				179			
Between Stake No. 168	4.5	"	15.0				
and Stake No. 169				175			
Between Stake No. 169	4.5	"	15.0				
and Stake No. 170				173			
Between Stake No. 170	4.4	"	14.8				
and Stake No. 171				181			
Between Stake No. 171	4.8	"	15.6				
and Stake No. 172				181			
Between Stake No. 172	4.6	"	14.8				
and Stake No. 173				173			
Between Stake No. 173	4.5	"	15.0				
and Stake No. 174				181			
Between Stake No. 174	4.7	"	15.4				
and Stake No. 175				181			
Between Stake No. 175	4.5	"	15.0				
and Stake No. 176				175			
Between Stake No. 176	4.5	"	15.0				
and Stake No. 177				165			
						Total Estimated Cost of Whole Work, $	