

VIEWERS' REPORT

—IN—

DITCH PROCEEDINGS.

*Clare Ditch
No 24*

No. 686.—Pioneer Press Co., St. Paul, Minn.

*Filed October 13th 1894
J. M. Portman
County Auditor*

*Estimate Clare Ditch
No 24*

<i>Contractors on per Statement</i>	<i>\$ 3146.69</i>
<i>Bridges at Old 99</i>	<i>577.60</i>
<i>" " " 150</i>	<i>15000</i>
<i>Locating Expenses</i>	<i>88.00</i>
<i>Shovels free</i>	<i>7.00</i>
<i>Articles "</i>	<i>25.00</i>
<i>Repairs "</i>	<i>2.00</i>
<i>Printing "</i>	<i>2.00</i>
<i>Total =</i>	<i><u>\$ 3361.29</u></i>

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No.

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. 20	2.8	4 ft	7.5	52.2	8
and Stake No. 21	2.3	"	8.0	23	8
22	2.4	"	8.8	3.5	8
23	2.3	"	8.6	3.5	8
24	2.5	"	9.0	3.5	8
25	2.6	"	9.2	3.6	8
26	2.8	"	9.6	3.9	8
27	3.2	"	10.4	4.7	8
28	3.3	"	10.6	5.0	8
29	3.2	"	10.4	5.0	8
30	3.0	"	10.0	6.4	8
31	3.3	"	10.6	8.3	8
32	3.1	"	10.2	8.5	8
33	3.1	"	10.2	8.2	8
34	3.1	"	10.2	8.2	8
35	3.1	"	10.2	8.2	8
36	3.3	"	10.6	8.5	8
37	3.3	"	10.6	8.9	8
38	3.4	"	10.8	9.1	8
39	3.4	"	10.8	9.3	8
			Total =	178.8	
					Totals

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No.....

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. 40	3.4	4 ft	10.8	1730	8
and Stake No. 41	4.2	"	12.4	105	8
42	4.8	"	13.6	130	8
43	4.7	"	13.4	142	8
44	4.7	"	13.4	139	8
45	4.4	"	12.8	132	8
46	3.6	"	11.2	107	8
47	3.8	"	11.6	94	8
48	4.7	"	13.4	120	8
49	4.0	"	12.0	123	8
50	4.4	"	12.8	116	8
51	4.2	"	12.4	120	8
52	4.8	"	13.6	130	8
53	4.5	"	13.0	137	8
54	4.5	"	13.0	130	8
55	4.5	"	13.0	130	8
56	4.5	"	13.0	130	8
57	4.4	"	12.8	127	8
58	4.6	"	13.2	130	8
59	4.6	"	13.2	135	8
			Total = 7200		
					Totals

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No.

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. 60	4.7	4 ft	13.4	149	10
and Stake No. 61	4.9	"	13.8	156	10
62	5.0	"	14.0	163	10
63	5.8	"	15.6	188	10
64	5.3	"	14.6	197	10
65	6.2	"	16.4	208	10
66	6.3	"	16.6	237	10
67	6.3	"	16.6	240	10
68	6.1	"	16.2	234	10
69	4.8	"	13.6	192	10
70	6.3	"	16.6	193	10
71	5.6	"	15.2	220	10
72	5.0	"	14.0	183	10
73	6.6	"	17.2	211	10
74	5.5	"	15.0	226	10
75	5.0	"	14.0	180	10
76	5.2	"	14.4	172	10
77	5.6	"	15.2	188	10
78	6.6	"	17.2	228	10
79	6.0	"	16.0	240	10
			Totals =	5205	

Totals

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No.....

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. <u>80</u>	5.6	4 ft	15.6	205	12
and Stake No. <u>81</u>	5.8	"	15.6	205	12
<u>82</u>	5.7	"	15.4	208	12
<u>83</u>	6.3	"	16.6	222	12
<u>84</u>	6.6	"	17.2	250	12
<u>85</u>	6.2	"	16.4	247	12
<u>86</u>	6.1	"	16.2	231	12
<u>87</u>	6.4	"	16.8	237	12
<u>88</u>	6.3	"	16.6	247	12
<u>89</u>	6.5	"	17.0	247	12
<u>90</u>	6.3	"	16.6	247	12
<u>91</u>	6.9	"	17.8	259	12
<u>92</u>	7.6	"	19.2	301	12
<u>93</u>	6.9	"	17.8	301	12
<u>94</u>	7.4	"	18.8	295	12
<u>95</u>	7.2	"	18.4	305	12
<u>96</u>	7.1	"	18.2	292	12
<u>97</u>	6.7	"	17.4	278	12
<u>98</u>	6.9	"	17.8	272	12
<u>99</u>	7.0	"	18.0	282	12
Total =				1334 1/2	
					Totals

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No.....

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	ESTIMATED COST PER CUBIC YARD	
Between Stake No. 100	6.5	4 ft	17.0	13341	12 1/2	Stake from Sta 103 to 120 are set for middle of ditch and cut from also for middle of ditch—
and Stake No. 101	7.0	"	18.0	234	12 1/2	
102	7.6	"	19.2	306	12 1/2	
103	7.5	"	19.0	285	12 1/2	
104	7.7	"	19.4	288	12 1/2	
105	12.7	"	32.0	594	12 1/2	
106	13.6	"	34.2	913	12 1/2	
107	13.7	"	37.6	1078	12 1/2	
108	12.4	"	32.4	963	12 1/2	
109	8.2	"	20.4	609	12 1/2	
110	10.3	"	24.6	457	12 1/2	
111	13.1	"	30.2	687	12 1/2	
112	14.3	"	32.6	900	12 1/2	
113	14.2	"	32.4	963	12 1/2	
114	13.1	"	30.2	843	12 1/2	
115	12.2	"	28.4	782	12 1/2	
116	8.3	"	20.6	556	12 1/2	
117	10.6	"	25.2	476	12 1/2	
118	16.2	"	36.4	893	12 1/2	
119	11.0	"	26.0	911	12 1/2	
			Total =	26363		Totals

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No.

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. 120	4.9	4 ft	13.8	26363	8
and Stake No. 121	3.2	"	10.4	436	8
122	2.7	"	9.4	123	8
123	2.5	"	9.0	76	8
124	2.8	"	9.6	84	8
125	2.4	"	8.8	65	8
126	2.4	"	8.8	64	8
127	1.9	"	7.8	57	8
128	1.4	"	6.8	49	5
129	1.2	"	6.4	35	8
130	2.0	"	8.0	26	8
131	2.0	"	8.0	34	8
132	2.1	"	8.2	44	8
133	1.9	"	7.8	46	8
134	2.2	"	8.4	44	8
135	2.5	"	9.0	46	8
136	2.8	"	9.6	55	8
137	2.4	"	8.8	65	8
138	2.2	"	8.4	64	8
139	3.4	"	10.8	54	8
				72	8
			Total =	27872	
					Totals

