
VIEWERS' REPORT

—IN—

DITCH PROCEEDINGS.

Ditch 25

No. 680.—Pioneer Press Co., St. Paul, Minn.

Filed April 6th 1895
J. W. Putnam
County Auditor

EXHIBIT 2 OF VIEWERS' REPORT IN DITCH PROCEEDINGS.

Showing Time and Manner in which same must be done. Ditch No. 25

SECTION	TIME WITHIN WHICH WORK MUST BE DONE	MANNER IN WHICH WORK MUST BE DONE	MATERIALS USED	COST OF MATERIALS AND WORK
Stake No. <u>0</u> TO Stake No. <u>167</u> Main Line	June 1 st 1896	Earth from ditch to be rounded at least two feet from edge of dam - all angles to be rounded off with easy curves - Bridge at 164+50 to be made of 3 good stringers 10 inches in diameter 14 feet long with 14 plank 3" x 12" x 16 feet long Stakes are set on right bank of ditch -		
Sta 0 to Sta 75 Branch	June 1 st 1896	Dam as above When applicable Box drain at Sta 62 to be made 20 ft long 2 ft wide and 2 feet deep in clear - to be made of 3" x 12" plank top & bottom plank to be 2 1/2 feet long laid across ditch, ^{single spiked} side plank to be laid so as to break joints - no joints to be lapped less than five feet Shuts - showing side of drain		

6	67
---	----