

EXHIBIT *B*

Ditch no 29
VIEWERS' REPORT

—IN—
DITCH PROCEEDINGS.

No. 686.—Pioneer Press Co., St. Paul, Minn.

*Filed March 3, 1898,
G. W. Putnam,
C. Auditor.*

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. *29 Branch No 3*

| SECTION | DEPTH OF CUT | WIDTH OF CUT AT BOTTOM | WIDTH OF CUT AT TOP | NO. OF CUBIC YARDS REMOVED | ESTIMATED COST PER CUBIC YARD |
|-----------------------------|--------------|------------------------|---------------------|----------------------------|--|
| Between Stake No. <i>40</i> | <i>2.6</i> | <i>2 ft</i> | <i>4.6</i> | <i>32</i> | <i>All dirt (6) Cont'd beyond Estimated Branch No 3 1744 yds @ \$6 = \$10464</i> |
| and Stake No. <i>41</i> | <i>2.2</i> | | <i>4.2</i> | <i>28</i> | |
| <i>42</i> | <i>2.4</i> | <i>"</i> | <i>4.4</i> | <i>27</i> | |
| <i>43</i> | <i>2.3</i> | <i>"</i> | <i>4.3</i> | <i>28</i> | |
| <i>44</i> | <i>2.2</i> | <i>"</i> | <i>4.2</i> | <i>26</i> | |
| <i>45</i> | <i>2.3</i> | <i>"</i> | <i>4.3</i> | <i>26</i> | |
| <i>46</i> | <i>2.5</i> | <i>"</i> | <i>4.5</i> | <i>26</i> | |
| <i>47</i> | <i>2.4</i> | <i>"</i> | <i>4.4</i> | <i>21</i> | |
| <i>48</i> | <i>2.4</i> | <i>"</i> | <i>4.4</i> | <i>19</i> | |
| <i>49</i> | <i>2.4</i> | <i>"</i> | <i>4.4</i> | <i>19</i> | |
| <i>50</i> | <i>2.5</i> | <i>"</i> | <i>4.5</i> | <i>18</i> | |
| <i>51</i> | <i>2.5</i> | <i>"</i> | <i>4.5</i> | <i>30</i> | |
| <i>52</i> | <i>2.5</i> | <i>"</i> | <i>4.5</i> | <i>30</i> | |
| <i>53</i> | <i>2.8</i> | <i>"</i> | <i>4.8</i> | <i>33</i> | |
| <i>54</i> | <i>2.4</i> | <i>"</i> | <i>4.4</i> | <i>32</i> | |
| <i>720</i> | <i>2.3</i> | <i>"</i> | <i>4.3</i> | <i>6</i> | |
| | | | | <i>4018</i> | |
| <i>Totals</i> | | | | | |

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. *29* Branch No *4*

| SECTION | DEPTH OF CUT | WIDTH OF CUT AT BOTTOM | WIDTH OF CUT AT TOP | NO. OF CUBIC YARDS REMOVED | ESTIMATED COST PER CUBIC YARD |
|----------------------------|--------------|------------------------|---------------------|----------------------------|----------------------------------|
| Between Stake No. <i>0</i> | <i>2.0</i> | <i>2 ft</i> | <i>4.0</i> | <i>22</i> | <i>All dirt (6) cut for soil</i> |
| and Stake No. <i>1</i> | <i>1.9</i> | | <i>3.9</i> | <i>22</i> | |
| <i>2</i> | <i>1.9</i> | " | <i>3.9</i> | <i>21</i> | |
| <i>3</i> | <i>1.9</i> | " | <i>3.9</i> | <i>21</i> | |
| <i>4</i> | <i>1.9</i> | " | <i>3.9</i> | <i>21</i> | |
| <i>5</i> | <i>2.0</i> | " | <i>4.0</i> | <i>22</i> | |
| <i>6</i> | <i>1.9</i> | " | <i>3.9</i> | <i>22</i> | |
| <i>7</i> | <i>2.0</i> | " | <i>4.0</i> | <i>22</i> | |
| <i>8</i> | <i>2.1</i> | " | <i>4.1</i> | <i>23</i> | |
| <i>9</i> | <i>1.8</i> | " | <i>3.9</i> | <i>22</i> | |
| <i>10</i> | <i>1.8</i> | " | <i>3.8</i> | <i>19</i> | |
| <i>11</i> | <i>2.0</i> | " | <i>4.0</i> | <i>22</i> | |
| <i>12</i> | <i>1.9</i> | " | <i>3.9</i> | <i>22</i> | |
| <i>13</i> | <i>1.8</i> | " | <i>3.8</i> | <i>20</i> | |
| <i>14</i> | <i>1.9</i> | " | <i>3.9</i> | <i>20</i> | |
| <i>15</i> | <i>1.9</i> | " | <i>3.9</i> | <i>21</i> | |
| <i>16</i> | <i>2.1</i> | " | <i>4.1</i> | <i>22</i> | |
| <i>17</i> | <i>2.1</i> | " | <i>4.1</i> | <i>24</i> | |
| <i>18</i> | <i>2.1</i> | " | <i>4.1</i> | <i>24</i> | |
| <i>19</i> | <i>1.5</i> | " | <i>3.5</i> | <i>19</i> | |
| | | | | <i>409</i> | |
| | | | | <i>4</i> | |
| | | | | | Totals |

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. *29 Branch No 4*

| SECTION | DEPTH OF CUT | WIDTH OF CUT AT BOTTOM | WIDTH OF CUT AT TOP | NO. OF CUBIC YARDS REMOVED | ESTIMATED COST PER CUBIC YARD |
|-----------------------------|--------------|------------------------|---------------------|----------------------------|-------------------------------|
| Between Stake No. <i>20</i> | <i>1.5</i> | <i>20 ft</i> | <i>3.5</i> | <i>15</i> | <i>Add. dir. Costs per yd</i> |
| and Stake No. <i>21</i> | <i>1.4</i> | | <i>3.4</i> | <i>15</i> | |
| <i>22</i> | <i>2.3</i> | <i>"</i> | <i>4.3</i> | <i>20</i> | |
| <i>23</i> | <i>1.6</i> | <i>"</i> | <i>3.6</i> | <i>22</i> | |
| <i>24</i> | <i>0.8</i> | <i>"</i> | <i>2.8</i> | <i>12</i> | |
| <i>25</i> | <i>1.2</i> | <i>"</i> | <i>3.2</i> | <i>9</i> | |
| <i>26</i> | <i>2.1</i> | <i>"</i> | <i>4.1</i> | <i>17</i> | |
| <i>27</i> | <i>1.8</i> | <i>"</i> | <i>3.8</i> | <i>22</i> | |
| <i>28</i> | <i>2.3</i> | <i>"</i> | <i>4.3</i> | <i>23</i> | |
| <i>29</i> | <i>1.3</i> | <i>"</i> | <i>3.3</i> | <i>19</i> | |
| <i>30</i> | <i>1.8</i> | <i>"</i> | <i>3.8</i> | <i>16</i> | |
| <i>31</i> | <i>2.8</i> | <i>"</i> | <i>4.8</i> | <i>30</i> | |
| <i>32</i> | <i>2.9</i> | <i>"</i> | <i>4.9</i> | <i>20</i> | |
| <i>33</i> | <i>2.6</i> | <i>"</i> | <i>4.6</i> | <i>23</i> | |
| <i>34</i> | <i>2.6</i> | <i>"</i> | <i>4.6</i> | <i>23</i> | |
| <i>35</i> | <i>2.8</i> | <i>"</i> | <i>4.8</i> | <i>21</i> | |
| <i>36</i> | <i>2.7</i> | <i>"</i> | <i>4.7</i> | <i>21</i> | |
| <i>37</i> | <i>2.8</i> | <i>"</i> | <i>4.8</i> | <i>31</i> | |
| <i>38</i> | <i>2.7</i> | <i>"</i> | <i>4.7</i> | <i>34</i> | |
| <i>39</i> | <i>2.9</i> | <i>"</i> | <i>4.9</i> | <i>35</i> | |
| | | | | <i>428</i> | |
| | | | | <i>6</i> | |
| | | | | | Totals |

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, *Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 29 Branch No. 4*

| SECTION | DEPTH OF CUT | WIDTH OF CUT AT BOTTOM | WIDTH OF CUT AT TOP | NO. OF CUBIC YARDS REMOVED | ESTIMATED COST PER CUBIC YARD |
|-----------------------------|-----------------------|------------------------|---------------------|----------------------------|---|
| Between Stake No. <i>40</i> | <i>2.7</i> | <i>Lft</i> | <i>4.7</i> | <i>35</i> | <i>All. for (6) Cuts per ft</i> |
| and Stake No. <i>41</i> | <i>2.9</i> | | <i>4.9</i> | <i>35</i> | |
| <i>42</i> | <i>2.9</i> | <i>"</i> | <i>4.9</i> | <i>37</i> | |
| <i>43</i> | <i>2.8</i> | <i>"</i> | <i>4.8</i> | <i>36</i> | |
| <i>44</i> | <i>3.0</i> | <i>"</i> | <i>5.0</i> | <i>37</i> | |
| <i>45</i> | <i>3.1</i> | <i>"</i> | <i>5.1</i> | <i>46</i> | |
| <i>46</i> | <i>3.1</i> | <i>"</i> | <i>5.1</i> | <i>41</i> | |
| <i>47</i> | <i>3.3</i> | <i>"</i> | <i>5.3</i> | <i>43</i> | |
| <i>48</i> | <i>3.2</i> | <i>"</i> | <i>5.2</i> | <i>44</i> | |
| <i>49</i> | <i>3.0</i> | <i>"</i> | <i>5.0</i> | <i>41</i> | |
| <i>50</i> | <i>3.1</i> | <i>"</i> | <i>5.1</i> | <i>40</i> | |
| <i>51</i> | <i>3.3</i> | <i>"</i> | <i>5.3</i> | <i>43</i> | |
| <i>52</i> | <i>3.5</i> | <i>"</i> | <i>5.5</i> | <i>47</i> | <i>Estimated Branch No. 4</i> <i>1400 yds. @ 6 = 84.00</i> <i>Bridge on Culvert = 8.00</i> <i>Totals = \$92.00</i> |
| <i>53</i> | <i>3.5</i> | <i>"</i> | <i>5.5</i> | <i>49</i> | |
| | | | | <i>568</i> | |
| | <i>1400 yds @ 6 =</i> | | <i>84.00</i> | | |
| | <i>Bridge</i> | | | | |
| | | | | | <i>Totals</i> |

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. *29* Branch No *5*

| SECTION | DEPTH OF CUT | WIDTH OF CUT AT BOTTOM | WIDTH OF CUT AT TOP | NO. OF CUBIC YARDS REMOVED | ESTIMATED COST PER CUBIC YARD |
|----------------------------|--------------|------------------------|---------------------|----------------------------|-------------------------------|
| Between Stake No. <i>0</i> | <i>2.2</i> | <i>2 ft</i> | <i>4.2</i> | | |
| and Stake No. <i>1</i> | <i>2.6</i> | | <i>4.6</i> | <i>28</i> | |
| <i>2</i> | <i>2.5</i> | " | <i>4.5</i> | <i>31</i> | |
| <i>3</i> | <i>2.6</i> | " | <i>4.6</i> | <i>31</i> | |
| <i>4</i> | <i>2.6</i> | " | <i>4.6</i> | <i>32</i> | |
| <i>5</i> | <i>2.7</i> | " | <i>4.7</i> | <i>33</i> | |
| <i>6</i> | <i>1.0</i> | " | <i>3.0</i> | <i>20</i> | |
| <i>7</i> | <i>0.0</i> | " | <i>0 0</i> | <i>4</i> | |
| <i>8</i> | <i>0.0</i> | " | | | |
| <i>9</i> | <i>0.0</i> | " | <i>Luman Lake</i> | | |
| <i>10</i> | <i>0.0</i> | " | | | |
| <i>11</i> | <i>0.0</i> | " | | | |
| <i>12</i> | <i>0.0</i> | " | <i>0 0</i> | | |
| <i>13</i> | <i>1.5</i> | " | <i>3.5</i> | <i>3</i> | |
| <i>14</i> | <i>1.5</i> | " | <i>3.5</i> | <i>15</i> | |
| <i>15</i> | <i>2.3</i> | " | <i>4.3</i> | <i>21</i> | |
| <i>16</i> | <i>2.5</i> | " | <i>4.5</i> | <i>28</i> | |
| <i>17</i> | <i>2.3</i> | " | <i>4.3</i> | <i>28</i> | |
| <i>18</i> | <i>2.3</i> | " | <i>4.3</i> | <i>27</i> | |
| <i>19</i> | <i>2.4</i> | " | <i>4.4</i> | <i>28</i> | |
| | | | | <i>329</i> | |
| | | | | <i>5</i> | |
| | | | | | <i>Totals</i> |

All dirt (6) cut per yard

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 29 Branch No 5

| SECTION | DEPTH OF CUT | WIDTH OF CUT AT BOTTOM | WIDTH OF CUT AT TOP | NO. OF CUBIC YARDS REMOVED | ESTIMATED COST PER CUBIC YARD |
|-----------------------------|--------------|------------------------|---------------------|----------------------------|--|
| Between Stake No. <u>20</u> | <u>2.3</u> | <u>28</u> | <u>4.3</u> | <u>28</u> | 437 Minus 9/ Cubic x Six (6) Cents per yd Note Stake 0 to 35 Six (6) Cents per yd " " 35 " 67 Minus (9) Cents per yd " " 67 " 84 x 65 Six Cents per yd |
| and Stake No. <u>21</u> | <u>2.4</u> | <u>28</u> | <u>4.4</u> | <u>28</u> | |
| <u>22</u> | <u>2.5</u> | <u>29</u> | <u>4.5</u> | <u>29</u> | |
| <u>23</u> | <u>2.5</u> | <u>30</u> | <u>4.5</u> | <u>30</u> | |
| <u>24</u> | <u>2.5</u> | <u>30</u> | <u>4.5</u> | <u>30</u> | |
| <u>25</u> | <u>2.6</u> | <u>31</u> | <u>4.6</u> | <u>31</u> | |
| <u>26</u> | <u>2.6</u> | <u>32</u> | <u>4.6</u> | <u>32</u> | |
| <u>27</u> | <u>2.6</u> | <u>32</u> | <u>4.6</u> | <u>32</u> | |
| <u>28</u> | <u>2.7</u> | <u>33</u> | <u>4.7</u> | <u>33</u> | |
| <u>29</u> | <u>2.5</u> | <u>34</u> | <u>4.5</u> | <u>32</u> | |
| <u>30</u> | <u>2.6</u> | <u>35</u> | <u>4.6</u> | <u>31</u> | |
| <u>31</u> | <u>2.6</u> | <u>32</u> | <u>4.6</u> | <u>32</u> | |
| <u>32</u> | <u>2.9</u> | <u>33</u> | <u>4.9</u> | <u>34</u> | |
| <u>33</u> | <u>2.7</u> | <u>35</u> | <u>4.7</u> | <u>35</u> | |
| <u>34</u> | <u>2.2</u> | <u>29</u> | <u>4.2</u> | <u>29</u> | |
| <u>35</u> | <u>2.4</u> | | <u>4.4</u> | <u>27</u> | |
| <u>36</u> | <u>2.7</u> | | <u>4.7</u> | <u>37</u> | |
| <u>37</u> | <u>2.3</u> | | <u>4.3</u> | <u>30</u> | |
| <u>38</u> | <u>2.7</u> | | <u>4.7</u> | <u>30</u> | |
| <u>39</u> | <u>2.8</u> | | <u>4.8</u> | <u>34</u> | |
| | | | | <u>187</u> | |
| Totals | | | | | |