

VIEWERS' REPORT

—IN—

DITCH PROCEEDINGS.

Ditch 31

No. 680.—Pioneer Press Co., St. Paul, Minn.

Office of County Auditor
Anoka County, Minn.
Filed April 30, 1897
S. B. Paulianus.
Co. Auditor.
to

[Faint, illegible handwritten text, likely bleed-through from the reverse side of the page.]

EXHIBIT 2 OF VIEWERS' REPORT IN DITCH PROCEEDINGS.

Showing Time and Manner in which same must be done. Ditch No. 31

All of main ditches and branches
from Sta 0 to outlets of each -

All to be completed on or before December
1st 1898

All Earth taken from ditch to be thrown at least three
feet from edge of ditch -
Bridges will be put in on work as follows -
Bridge with 8 planks each 3" x 12" x 6" at Sta 13.50 main line
South - Sta 26.50 main line north - End at Sta 27.15 Branch
No 1 End one with 10 planks same dimensions at Sta 27
Branch No 2 - These Bridges to have each two bank piles
and four stringers made of round live oak or Laminar
not less than 10 inches in diameter and not less than
10 ft long - Planks to be well spiked on stringers with
6ⁱⁿ spikes - Stakes are set for right hand edge of
ditch looking down stream -

SECTION	TIME WITHIN WHICH WORK MUST BE DONE	MANNER IN WHICH WORK MUST BE DONE	MATERIALS USED	COST OF MATERIALS AND WORK
---------	-------------------------------------	-----------------------------------	----------------	----------------------------

Stake No. TO Stake No.