

EXHIBIT 1.

---

# VIEWERS' REPORT

—IN—

DITCH PROCEEDINGS.

---

*Ditch No 32*

*Project No 1*

*Cost = \$150.66*

---

No. 686.—Pioneer Press Co., St. Paul, Minn.

*Filed July 11<sup>th</sup> 1898*

*J. M. Putnam  
County Auditor*

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. *32 Branch No 1*

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. <i>0</i>	<i>2.5</i>		<i>5.7</i>		✓
and Stake No. <i>1</i>	<i>2.7</i>	<i>Diff</i>	<i>6.0</i>	<i>38</i>	✓
<i>2</i>	<i>2.6</i>	"	<i>5.9</i>	<i>39</i>	✓
<i>3</i>	<i>2.8</i>	"	<i>6.2</i>	<i>40</i>	✓
<i>4</i>	<i>2.9</i>	"	<i>6.3</i>	<i>43</i>	✓
<i>5</i>	<i>2.5</i>	"	<i>5.7</i>	<i>40</i>	✓
<i>6</i>	<i>2.8</i>	"	<i>6.2</i>	<i>39</i>	✓
<i>7</i>	<i>2.8</i>	"	<i>6.2</i>	<i>43</i>	✓
<i>8</i>	<i>2.6</i>	"	<i>5.9</i>	<i>40</i>	✓
<i>9</i>	<i>2.6</i>	"	<i>5.9</i>	<i>38</i>	✓
<i>10</i>	<i>2.4</i>	"	<i>5.6</i>	<i>36</i>	✓
<i>11</i>	<i>2.8</i>	"	<i>6.2</i>	<i>38</i>	✓
<i>12</i>	<i>2.7</i>	"	<i>6.0</i>	<i>41</i>	✓
<i>13</i>	<i>2.6</i>	"	<i>5.9</i>	<i>39</i>	✓
<i>14</i>	<i>2.5</i>	"	<i>5.7</i>	<i>37</i>	✓
<i>15</i>	<i>2.5</i>	"	<i>5.7</i>	<i>36</i>	✓
<i>16</i>	<i>2.6</i>	"	<i>5.9</i>	<i>37</i>	✓
<i>17</i>	<i>2.5</i>	"	<i>5.7</i>	<i>37</i>	✓
<i>18</i>	<i>2.7</i>	"	<i>6.0</i>	<i>38</i>	✓
<i>19</i>	<i>2.8</i>	"	<i>6.2</i>	<i>41</i>	✓
				<i>757 0</i>	
				<i>10</i>	
					<i>Totals</i>

All @ Six (6) Cent per yd

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. *32 Branch No 1*

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. <i>20</i>	<i>2.7</i>	<i>2 ft</i>	<i>6.0</i>	<i>40</i>	✓
and Stake No. <i>1</i>	<i>2.8</i>		<i>6.2</i>	<i>40</i>	✓
<i>2</i>	<i>2.5</i>	<i>"</i>	<i>5.7</i>	<i>39</i>	✓
<i>3</i>	<i>2.4</i>		<i>5.6</i>	<i>35</i>	✓
<i>4</i>	<i>2.7</i>	<i>"</i>	<i>6.0</i>	<i>37</i>	✓
<i>5</i>	<i>2.0</i>		<i>5.0</i>	<i>33</i>	✓
<i>6</i>	<i>2.4</i>	<i>"</i>	<i>5.6</i>	<i>30</i>	✓
<i>7</i>	<i>2.1</i>		<i>5.1</i>	<i>31</i>	✓
<i>8</i>	<i>1.9</i>	<i>"</i>	<i>4.8</i>	<i>26</i>	✓
<i>450</i>	<i>3.1</i>		<i>6.6</i>	<i>38</i>	✓
<i>30</i>	<i>2.3</i>	<i>"</i>	<i>5.4</i>	<i>27</i>	✓
<i>1</i>	<i>1.8</i>		<i>4.7</i>	<i>25</i>	✓
<i>2</i>	<i>2.0</i>	<i>"</i>	<i>5.0</i>	<i>25</i>	✓
<i>3</i>	<i>1.9</i>		<i>4.8</i>	<i>25</i>	✓
<i>4</i>	<i>1.1</i>	<i>"</i>	<i>3.6</i>	<i>17</i>	✓
<i>5</i>	<i>2.1</i>		<i>5.1</i>	<i>19</i>	✓
<i>6</i>	<i>3.0</i>	<i>"</i>	<i>6.5</i>	<i>37</i>	✓
<i>7</i>	<i>2.5</i>		<i>5.7</i>	<i>41</i>	✓
<i>8</i>	<i>2.2</i>	<i>"</i>	<i>5.3</i>	<i>33</i>	✓
	<i>2.3</i>		<i>5.4</i>	<i>31</i>	✓
				<i>604</i>	
				<i>6</i>	
					Totals

*All dirt (.6) cost per yd*

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 32 Branch 1

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. <u>39</u>	<u>1.6</u>	<u>2 ft</u>	<u>4.4</u>	<u>25</u>	✓
and Stake No. <u>40</u>	<u>1.7</u>		<u>4.5</u>	<u>20</u>	✓
<u>1</u>	<u>1.9</u>		<u>4.8</u>	<u>23</u>	✓
<u>2</u>	<u>1.9</u>		<u>4.8</u>	<u>25</u>	✓
<u>3</u>	<u>1.9</u>		<u>4.8</u>	<u>25</u>	✓
<u>4</u>	<u>1.9</u>		<u>4.8</u>	<u>25</u>	✓
<u>5</u>	<u>2.2</u>		<u>5.3</u>	<u>27</u>	✓
<u>6</u>	<u>2.2</u>		<u>5.3</u>	<u>30</u>	✓
<u>7</u>	<u>2.1</u>		<u>5.1</u>	<u>29</u>	✓
<u>8</u>	<u>2.4</u>		<u>5.6</u>	<u>31</u>	✓
<u>9</u>	<u>2.5</u>		<u>5.7</u>	<u>35</u>	✓
<u>10</u>	<u>2.3</u>		<u>5.4</u>	<u>34</u>	✓
<u>11</u>	<u>2.0</u>		<u>5.0</u>	<u>29</u>	✓
<u>12</u>	<u>2.1</u>		<u>5.7</u>	<u>27</u>	✓
<u>13</u>	<u>2.1</u>	<u>5.1</u>	<u>28</u>	✓	
<u>14</u>	<u>2.0</u>	<u>5.0</u>	<u>27</u>	✓	
<u>15</u>	<u>2.2</u>	<u>5.3</u>	<u>28</u>	✓	
<u>16</u>	<u>2.0</u>	<u>5.0</u>	<u>28</u>	✓	
<u>17</u>	<u>2.3</u>	<u>5.4</u>	<u>29</u>	✓	
<u>18</u>	<u>2.6</u>	<u>6.0</u>	<u>35</u>	✓	
			<u>560</u>	<u>14</u>	
					<i>Totals</i>

All dirt carried away

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 32 Branch No 1

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. <u>59</u>	<u>2.4</u>	<u>2 ft</u>	<u>5.6</u>	<u>36</u>	✓
and Stake No. <u>+70</u>	<u>3.0</u>		<u>6.5</u>	<u>40</u>	✓
<u>60</u>	<u>2.3</u>		<u>5.4</u>	<u>39</u>	✓
<u>1</u>	<u>1.9</u>		<u>4.8</u>	<u>28</u>	✓
<u>2</u>	<u>1.8</u>		<u>4.7</u>	<u>24</u>	✓
<u>3</u>	<u>1.8</u>		<u>4.7</u>	<u>23</u>	✓
<u>4</u>	<u>1.8</u>		<u>4.7</u>	<u>23</u>	✓
<u>5</u>	<u>1.9</u>		<u>4.8</u>	<u>24</u>	✓
<u>6</u>	<u>1.9</u>		<u>4.8</u>	<u>25</u>	✓
<u>7</u>	<u>2.6</u>		<u>5.9</u>	<u>31</u>	✓
<u>8</u>	<u>2.6</u>	<u>5.9</u>	<u>38</u>	✓	
<u>9</u>	<u>2.4</u>	<u>5.6</u>	<u>36</u>	✓	
<u>70</u>	<u>2.4</u>	<u>3 ft</u>	<u>5.6</u>	<u>34</u>	✓
<u>1</u>	<u>1.9</u>		<u>5.8</u>	<u>32</u>	✓
<u>2</u>	<u>2.6</u>		<u>6.9</u>	<u>39</u>	✓
<u>3</u>	<u>2.7</u>		<u>7.0</u>	<u>51</u>	✓
<u>4</u>	<u>2.1</u>		<u>6.1</u>	<u>14</u>	✓
<u>5</u>	<u>2.5</u>		<u>6.7</u>	<u>11</u>	✓
<u>6</u>	<u>1.8</u>		<u>5.7</u>	<u>10</u>	✓
<u>7</u>	<u>2.0</u>		<u>6.0</u>	<u>5</u>	✓
				<u>527</u>	
				<u>8</u>	
					Totals

All dirt to be carried for you.

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 32 Branch no 1

SECTION	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD	
Between Stake No. <u>78</u>	<u>1.9</u>	<u>3 ft</u>	<u>5.8</u>	<u>for clearing out old ditch</u>	✓	
and Stake No. <u>9</u>	<u>1.9</u>		<u>5.8</u>			
<u>80</u>	<u>2.0</u>	"	<u>6.0</u>			✓
<u>1</u>	<u>1.6</u>		<u>5.4</u>			✓
<u>2</u>	<u>2.7</u>	"	<u>7.0</u>			✓
<u>3</u>	<u>2.2</u>		<u>6.3</u>			✓
<u>4</u>	<u>2.4</u>	"	<u>6.6</u>			✓
<u>5</u>	<u>2.8</u>		<u>7.2</u>			✓
<u>6</u>	<u>3.7</u>	"	<u>8.5</u>			✓
<u>7</u>	<u>3.5</u>		<u>8.2</u>			✓
<u>8</u>	<u>2.9</u>	"	<u>7.3</u>	✓		
<u>9</u>	<u>2.4</u>		<u>6.6</u>	✓		
<u>0</u>	<u>2.8</u>	"	<u>7.2</u>	✓		
<u>1</u>	<u>2.6</u>		<u>6.9</u>	✓		
<u>2</u>	<u>2.6</u>	"	<u>6.9</u>	✓		
<u>7</u>	<u>2.6</u>		<u>6.9</u>	✓		
				<u>82</u>	<u>4 1/2</u>	
					<u>All Soil (6) Cured for ya</u>	
					<u>Estimate Branch no 1</u>	
					<u>2511 yds Excavation @ 6 = 15066</u>	
					<u>Totals</u>	