

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Rapids County Ditch No. 35 Branch No. 2

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard	(6) Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section	(7) Total Estimated Cost Per Section			
				yds deducted	yds to be removed	\$ 15 CTS	\$	CTS	\$	CTS	
Between Stake No. 0 and Stake No. 1	5.0	2	17.0				Clearing.				
Between Stake No. 2 and Stake No. 3	4.6	"	15.8	12	142	21 30		100	22	30	
Between Stake No. 4 and Stake No. 5	4.1	"	14.3	19	119	17 85		100	18	85	
Between Stake No. 6 and Stake No. 7	4.6	"	15.8	17	121	18 15		100	19	15	
Between Stake No. 8 and Stake No. 9	4.0	"	14.0	13	122	18 30		100	19	30	
Between Stake No. 10 and Stake No. 11	4.2	"	14.6	10	114	17 10		100	18	10	
Between Stake No. 12 and Stake No. 13	5.5	"	18.5	12	157	23 55		100	24	55	
Between Stake No. 14 and Stake No. 15	3.7	"	13.1	21	135	20 25		100	21	25	
Between Stake No. 16 and Stake No. 17	6.2	"	20.6	10	171	25 65		100	26	65	
Between Stake No. 18 and Stake No. 19	3.2	"	11.6	28	142	21 30		100	22	30	
Between Stake No. 20 and Stake No. 21	3.2	"	11.6	9	72	10 80		100	11	80	
Between Stake No. 22 and Stake No. 23	3.6	"	12.8	10	80	12 00		100	13	00	
Between Stake No. 24 and Stake No. 25	3.3	"	11.9	14	78	11 70		100	12	70	
Between Stake No. 26 and Stake No. 27	3.2	"	11.6	15	68	10 30		100	11	30	
Between Stake No. 28 and Stake No. 29	3.5	"	12.5	15	72	10 80		100	11	80	
Between Stake No. 30 and Stake No. 31	2.1	"	8.3	19	48	7 20		100	8	20	
Between Stake No. 32 and Stake No. 33	2.1	"	8.3	7	33	4 95		100	5	95	
Between Stake No. 34 and Stake No. 35	2.7	"	10.1	7	44	6 60		100	7	60	
Between Stake No. 36 and Stake No. 37	2.5	"	9.5	13	41	6 15		100	7	15	
Between Stake No. 38 and Stake No. 39	3.6	"	12.8	9	64	9 60		100	10	60	
				270	1823	\$ 273.45		\$19.00	\$292.45		

Total Estimated Cost of Whole Work.....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in *Reparo County* Ditch No. *35* Branch No. *2*

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard  \$ 15 CTS.	(6) Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		(7) Total Estimated Cost Per Section		
				yds deducted	yds to be removed		\$	CTS	\$	CTS.	
<i>Between Stake No. 19</i>	<i>19</i>		<i>12.8</i>								
<i>and Stake No. 20</i>	<i>3.7</i>	<i>2.0</i>	<i>13.1</i>	<i>17</i>	<i>84</i>	<i>12 60</i>		<i>100</i>	<i>13</i>	<i>60</i>	
<i>Between Stake No. 21</i>	<i>3.8</i>	"	<i>13.4</i>	<i>19</i>	<i>87</i>	<i>13 05</i>		<i>100</i>	<i>14</i>	<i>05</i>	
<i>and Stake No. 22</i>	<i>3.5</i>	"	<i>12.5</i>	<i>20</i>	<i>81</i>	<i>12 15</i>		<i>100</i>	<i>13</i>	<i>15</i>	
<i>Between Stake No. 23</i>	<i>3.2</i>	"	<i>11.6</i>	<i>18</i>	<i>69</i>	<i>10 35</i>		<i>100</i>	<i>11</i>	<i>35</i>	
<i>and Stake No. 24</i>	<i>2.8</i>	"	<i>10.4</i>	<i>16</i>	<i>57</i>	<i>8 55</i>		<i>100</i>	<i>9</i>	<i>55</i>	
<i>Between Stake No. 25</i>	<i>2.8</i>	"	<i>10.4</i>	<i>10</i>	<i>54</i>	<i>8 10</i>		<i>100</i>	<i>9</i>	<i>10</i>	
<i>and Stake No. 26</i>	<i>3.1</i>	"	<i>11.3</i>	<i>11</i>	<i>59</i>	<i>8 85</i>		<i>100</i>	<i>9</i>	<i>85</i>	
<i>Between Stake No. 27</i>	<i>3.3</i>	"	<i>11.9</i>	<i>13</i>	<i>68</i>	<i>10 20</i>		<i>100</i>	<i>11</i>	<i>20</i>	
<i>and Stake No. 28</i>	<i>3.0</i>	"	<i>11.0</i>	<i>16</i>	<i>62</i>	<i>9 45</i>		<i>100</i>	<i>10</i>	<i>45</i>	
<i>Between Stake No. 29</i>	<i>3.1</i>	"	<i>11.3</i>	<i>14</i>	<i>60</i>	<i>9 00</i>		<i>100</i>	<i>10</i>	<i>00</i>	
<i>and Stake No. 30</i>	<i>2.7</i>	"	<i>10.1</i>	<i>13</i>	<i>56</i>	<i>8 40</i>		<i>100</i>	<i>9</i>	<i>40</i>	
<i>Between Stake No. 31</i>	<i>3.2</i>	"	<i>11.6</i>		<i>71</i>	<i>10 65</i>		<i>100</i>	<i>11</i>	<i>65</i>	
<i>and Stake No. 32</i>	<i>2.1</i>	"	<i>8.3</i>		<i>60</i>	<i>9 00</i>		<i>100</i>	<i>10</i>	<i>00</i>	
<i>Between Stake No. 33</i>	<i>3.3</i>	"	<i>11.9</i>		<i>59</i>	<i>8 85</i>		<i>100</i>	<i>9</i>	<i>85</i>	
<i>and Stake No. 34</i>	<i>4.1</i>	"	<i>14.3</i>		<i>104</i>	<i>15 60</i>		<i>100</i>	<i>16</i>	<i>60</i>	
<i>Between Stake No. 35</i>	<i>4.1</i>	"	<i>14.3</i>		<i>124</i>	<i>18 60</i>		<i>100</i>	<i>19</i>	<i>60</i>	
<i>and Stake No. 36</i>	<i>4.1</i>	"	<i>14.3</i>		<i>124</i>	<i>18 60</i>		<i>100</i>	<i>19</i>	<i>60</i>	
<i>Between Stake No. 37</i>	<i>3.3</i>	"	<i>11.9</i>		<i>104</i>	<i>15 60</i>		<i>100</i>	<i>16</i>	<i>60</i>	
<i>and Stake No. 38</i>	<i>3.7</i>	"	<i>13.1</i>		<i>94</i>	<i>14 10</i>		<i>100</i>	<i>15</i>	<i>10</i>	
				<i>167 1478</i>		<i>\$221.70</i>		<i>\$1900</i>		<i>\$240.70</i>	

Total Estimated Cost of Whole Work.....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in *Repairs Co.* Ditch No. *35* Branch No. *2*

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard  \$ 15 CTS.		(6) Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section  \$ CTS		(7) Total Estimated Cost Per Section  \$ CTS.	
	<i>Between Stake No. 38</i>	<i>3.7</i>	<i>2.0</i>	<i>13.1</i>		<i>Cost of</i>				
<i>and Stake No. 39</i>	<i>2.8</i>	<i>"</i>	<i>10.4</i>	<i>84</i>	<i>Excavation</i>	<i>12 60</i>	<i>Clearing</i>	<i>100</i>	<i>13 60</i>	
<i>Between Stake No. 40</i>	<i>2.0</i>	<i>"</i>	<i>8.0</i>	<i>51</i>	<i>per Sta.</i>	<i>7 65</i>	<i>"</i>	<i>100</i>	<i>8 65</i>	
<i>and Stake No. 41</i>	<i>2.0</i>	<i>"</i>	<i>6.0</i>	<i>33</i>		<i>4 95</i>	<i>"</i>	<i>100</i>	<i>5 95</i>	
<i>Between Stake No. 42</i>	<i>1.6</i>	<i>"</i>	<i>5.2</i>	<i>26</i>		<i>3 90</i>	<i>"</i>	<i>100</i>	<i>4 90</i>	
<i>and Stake No. 43</i>	<i>2.2</i>	<i>"</i>	<i>6.4</i>	<i>26</i>		<i>3 90</i>	<i>"</i>	<i>100</i>	<i>4 90</i>	
<i>Between Stake No. 44</i>	<i>2.4</i>	<i>"</i>	<i>6.8</i>	<i>37</i>		<i>5 55</i>	<i>"</i>	<i>100</i>	<i>6 55</i>	
<i>and Stake No. 45</i>	<i>2.0</i>	<i>"</i>	<i>6.0</i>	<i>34</i>		<i>5 10</i>	<i>"</i>	<i>100</i>	<i>6 10</i>	
<i>Between Stake No.</i>										
<i>and Stake No.</i>										
<i>Between Stake No.</i>										
<i>and Stake No.</i>										
<i>Between Stake No.</i>										
<i>and Stake No.</i>										
<i>Between Stake No.</i>										
<i>and Stake No.</i>										
<i>Between Stake No.</i>										
<i>and Stake No.</i>										
<i>Between Stake No.</i>										
<i>and Stake No.</i>										
				<i>291</i>		<i>43.65</i>		<i>\$7.00</i>	<i>\$50.65</i>	

*Total Estimated Cost of Whole Work* .....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in \_\_\_\_\_ Ditch No. \_\_\_\_\_

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		(7) Total Estimated Cost Per Section	
					\$	CTS.			\$	CTS.
<i>Between Stake No. and Stake No.</i>		<i>Summary of Branch No. 2</i>					<i>Estimate No. 1.</i>			
		<i>Sheet No 1</i>		<i>1823</i>	<i>273</i>	<i>45</i>	<i>Clearing</i>	<i>19 00</i>	<i>292</i>	<i>45</i>
<i>Between Stake No. and Stake No.</i>		<i>" "</i>	<i>2</i>	<i>1478</i>	<i>221</i>	<i>70</i>	<i>"</i>	<i>19 00</i>	<i>240</i>	<i>70</i>
<i>Between Stake No. and Stake No.</i>		<i>" "</i>	<i>3</i>	<i>291</i>	<i>423</i>	<i>65</i>	<i>"</i>	<i>7 00</i>	<i>506</i>	<i>65</i>
<i>Between Stake No. and Stake No.</i>										
<i>Between Stake No. and Stake No.</i>										
<i>Between Stake No. and Stake No.</i>										
<i>Between Stake No. and Stake No.</i>										
<i>Between Stake No. and Stake No.</i>										
<i>Between Stake No. and Stake No.</i>										
<i>Between Stake No. and Stake No.</i>										
<i>Between Stake No. and Stake No.</i>				<i>3592</i>	<i>538</i>	<i>80</i>		<i>45 00</i>	<i>583</i>	<i>80</i>

*Total Estimated Cost of Whole Work* \_\_\_\_\_