

Summary  
of

Branch No. 3

	No. of yds	Cost of Excav.	Cost of Clearing	Total Cost
Sheet No. 1	890	133.50	14.00	147.50
" No. 2	333	49.95		49.95

1223      \$ 183.45      \$ 14.00      \$ 197.45

31

30

29

28

27

26

25

24

23

22

21

20

19

18

17

16

15

14

13

12

11

10

9

8

7

6

5

4

3

2

1

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in <sup>Repairs</sup> County \_\_\_\_\_ Ditch No. 337

SECTION	(1)	(2)	(3)	(4)		(5)	(6)		(7)			
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	Cu yds. to be DEDUCTED	Cu yds. TO BE EXCAV.	Estimated Cost Per Cubic Yard \$ / 100 CTS Per Sta.	Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		\$	CTS	\$	CTS
Between Stake No. 0	2.7	2.0'	7.4									
and Stake No. 1	2.6	"	7.2		46	690	clearing	100			790	
Between Stake No. 2	2.6	"	7.2		44	660	"	100			770	
and Stake No. 3	2.1	"	6.2		38	570	"	100			670	
Between Stake No. 4	2.3	"	6.6		36	540	"	100			640	
and Stake No. 5	2.5	"	7.0		39	585	"	100			685	
Between Stake No. 6	3.5	1 1/2' : 1' Slope	12.5		68	1020	"	100			1120	
and Stake No. 7	4.4	"	15.2	19	98	1470	"	100			1570	
Between Stake No. 8	3.8	"	13.4	20	104	1560	"	100			1660	
and Stake No. 9	3.5	1 1/2' : 1' "	12.5	17	84	1260	"	100			1360	
Between Stake No. 10	2.4	1 : 1' "	6.8	12	55	825	"	100			925	
and Stake No. 11	2.0	"	6.0		34	510	"	100			610	
Between Stake No. 12	2.3	"	6.6		33	495	"	100			595	
and Stake No. 13	1.9	"	5.8		32	480	"	100			580	
Between Stake No. 14	2.1	"	6.2		30	450	"	100			550	
and Stake No. 15	1.5	"	5.0		26	390						
Between Stake No. 16	2.2	"	6.4		27	405						
and Stake No. 17	2.1	"	6.2		34	510						
Between Stake No. 18	1.9	"	5.8		30	450						
and Stake No. 19	2.3	"	6.6		32	480						
				68	890	133.50			14.00		\$147.50	

Total Estimated Cost of Whole Work \_\_\_\_\_

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in \_\_\_\_\_ Ditch No. \_\_\_\_\_

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard \$ 15 CTS	(6) Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section	(7) Total Estimated Cost Per Section	
				Deducted	Execd.			\$	CTS.
		<i>1:1 Slope</i>				<i>Per Sta.</i>			
<i>Between Stake No. 20</i>	<i>14</i>	<i>2.0'</i>	<i>4.8</i>		<i>27</i>	<i>4 05</i>			
<i>and Stake No. 21</i>	<i>14</i>	<i>"</i>	<i>4.8</i>		<i>18</i>	<i>2 70</i>			
<i>Between Stake No. 22</i>	<i>17</i>	<i>"</i>	<i>5.4</i>		<i>21</i>	<i>3 15</i>			
<i>and Stake No. 23</i>	<i>15</i>	<i>"</i>	<i>5.0</i>		<i>21</i>	<i>3 15</i>			
<i>Between Stake No. 24</i>	<i>16</i>	<i>"</i>	<i>5.2</i>		<i>21</i>	<i>3 15</i>			
<i>and Stake No. 25</i>	<i>1.8</i>	<i>"</i>	<i>5.6</i>		<i>23</i>	<i>3 45</i>			
<i>Between Stake No. 26</i>	<i>14</i>	<i>"</i>	<i>4.8</i>		<i>21</i>	<i>3 15</i>			
<i>and Stake No. 27</i>	<i>16</i>	<i>"</i>	<i>5.2</i>		<i>20</i>	<i>3 00</i>			
<i>Between Stake No. 28</i>	<i>14</i>	<i>"</i>	<i>4.8</i>		<i>20</i>	<i>3 00</i>			
<i>and Stake No. 29</i>	<i>17</i>	<i>"</i>	<i>5.4</i>		<i>21</i>	<i>3 15</i>			
<i>Between Stake No. 30</i>	<i>19</i>	<i>"</i>	<i>5.8</i>		<i>26</i>	<i>2 90</i>			
<i>and Stake No. 31</i>	<i>1.9</i>	<i>"</i>	<i>5.8</i>		<i>27</i>	<i>4 05</i>			
<i>Between Stake No. 32</i>	<i>15</i>	<i>"</i>	<i>5.0</i>		<i>24</i>	<i>3 60</i>			
<i>and Stake No. 33</i>	<i>16</i>	<i>"</i>	<i>5.2</i>		<i>21</i>	<i>3 15</i>			
<i>Between Stake No. 34</i>	<i>17</i>	<i>"</i>	<i>5.4</i>		<i>22</i>	<i>3 30</i>			
<i>and Stake No.</i>									
<i>Between Stake No.</i>									
<i>and Stake No.</i>									
<i>Between Stake No.</i>									
<i>and Stake No.</i>									
				<i>333</i>		<i>49.95</i>			

*Total Estimated Cost of Whole Work* \_\_\_\_\_