
ENGINEER'S REPORT

IN

DITCH PROCEEDINGS.

*Filed July 21st 1902
Selden M. Gaffey
Co. auditor*

Exhibit 2 of Engineer's Report in Ditch Proceedings.

Showing Time and Manner in which same must be done. Ditch No. 39—

SECTION	TIME WITHIN WHICH WORK MUST BE DONE	MANNER IN WHICH WORK MUST BE DONE	MATERIALS USED	COST OF MATERIALS AND WORK
Stake No. 0 TO Stake No. 27	Nearly all cleaning out old ditch. work to be finished by June 1 st 1903			
Stake No. 27 TO Stake No. 130	New ditch from 1 st 1903 roadbed and spread evenly over June 1 st 1903 road bed. Water to be within June 1 st 31 ft from road limits.	Ditch along Central Ave Road will be excavated and earth thrown on the road road bed. Water to be within June 1 st 31 ft from road limits.		
Stake No. 130 TO Stake No. 179H16	Cleaning out old ditch from 1 st 1903			
Stake No. 158+20 TO Stake No. 170+50	A bridge to be made laid on mud sills at least ten (10) feet long with one foot side at least Eight (8) inches. String stringers at least 14 ft. long connected on one side at least four 14 - 2 inch planks 12 inch wide and 10 ft. long No. 1 common lumber reasonably spaced			\$14 00
Stake No. 170+50 TO Stake No. 179H16	Bridge same as above Mud sills 14 feet long Seven stringers 3" plank to cross bridge 14 ft by 10 ft.			\$16 00
Stake No. 179H16 TO Stake No. 170+50	Bridge same as above at Stake 158+20			\$14 00
Stake No. 170+50 TO Stake No. 179H16	Bridge same as at 170+50			\$16 00