

Notice to Ditch Contractors.

Sealed bids will be received at the office of the County Auditor of Anoka County Minn for the widening and deepening of County Ditch No. 41 at — o'clock of July — 1947

This job involves the excavation of 35775 cubic yards or 2175.7 rods on the main ditch, 4803 cubic yards or 127.2 rods on branch No. 4

This job also includes the furnishing and placing of 70 feet of 36 inch ~~culvert pipe~~ ~~iron culvert pipe~~ and 86 feet of 48 inch iron, ^{arched} culvert pipe. 50 feet of the 48 inch pipe is to be jacked thru Trunk Highway No 65 at Sta 209+57

The contractors bid will include the removal of and disposal of trees and debris which may hinder the free flow of water and may be bin. in at a lump sum or by tree unit. Specifications for all work are on file at the County auditors office. It must be noted by the

contractor that all waste banks must²
be leveled to a slope of not less than
4 to 1 and all such work shall be
included the price bid by the yard
or road.

All bids must be accompanied by
a certified check for not less than
10 % of the total bid.

The auditor reserves the right to
reject any ^{or} ~~and~~ all bids.

121-1-1-1-1