

NOTICE TO DITCH CONTRACTORS

Sealed bids will be received at the office of the County Auditor of Anoka County, Minnesota for the widening and deepening of Downy Ditch No. 41 at 11 o'clock, August 4, 1947.


This job involves the excavation of 35,775 cubic yards or 2175.7 rods on the main ditch and 4803 cubic yards or 127.2 rods on Branch No. 4.

This job also includes the furnishing and placing of 70 feet of 36 inch and 86 feet of 48 inch iron arched culvert pipe. Fifty feet of the 48 inch pipe is to be jacked thru Trunk Highway No. 65 at Station 209 + 57.

The contractor bid will include the removal of and disposal of trees and debris which may hinder the free flow of water and may be bid in at a lump sum or by tree unit. Specifications for all work are on file at the County Auditor's office. It must be noted by the contractor that all waste banks must be leveled to a slope of not less than 4 to 1 and all such work shall be included in the price bid by the yard or road.

All bids must be accompanied by a certified check for not less than 10% of the total bid.

Bid envelope to be marked "Bid on Ditch No. 41".


H. A. Carlson, County Auditor
Anoka County, Minnesota