

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Repairs Ditch No. 41

SECTION	(1)	(2)	(3)	(4)		(5)	(6)		(7)		
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	Cuyds. TO BE DEDUCTED	Cuyds. TO BE EXCAVATED	Estimated Cost Per Cubic Yard	Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		\$	CTS.	
Between Stake No. 0	8.0	3.0'	19.0								
and Stake No. 1	6.0		15.0	100	163	32	60			32	60
Between Stake No. 2	5.4		13.4	105	79	15	80			15	80
and Stake No. 3	4.8		12.6	99	54	10	80			10	80
Between Stake No. 4	4.1		11.2	94	25	5	00			5	00
and Stake No. 5	3.4		9.8	84	10	2	00			2	00
Between Stake No. 6	3.3		9.6	72	5	1	00			1	00
and Stake No. 7	3.3		9.6	72	5	1	00			1	00
Between Stake No. 8	3.1		9.2	66	7	1	40			1	40
and Stake No. 9	3.2		9.4	49	25	5	00			5	00
Between Stake No. 10	3.2		9.4	51	22	4	40			4	40
and Stake No. 11	3.1		9.2	67	5	1	00			1	00
Between Stake No. 12	3.0		9.0	63	5	1	00			1	00
and Stake No. 13	2.8		8.6	58	5	1	00			1	00
Between Stake No. 14	2.8		8.6	55	5	1	00			1	00
and Stake No. 15	2.1		7.2	45	5	1	00			1	00
Between Stake No. 16	2.6		8.2	41	5	1	00			1	00
and Stake No. 17	2.8		8.6	51	6	1	20			1	20
Between Stake No. 18	2.6		8.2	51	6	1	20			1	20
and Stake No. 19	2.5		8.0	44	8	1	60			1	60
				1268	445	89.00				89.00	

Total Estimated Cost of Whole Work.....

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Repairs Ditch No. 41

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yard \$ 20 CTS	(6) Character of Other Expenses, including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section \$ CTS	(7) Total Estimated Cost Per Section \$ CTS	
				<i>Cu Yds. To Be Deducted</i>	<i>Cu Yds. To Be Excav.</i>			\$	CTS.
Between Stake No. 20	2.6	3.0'	8.2	40	12	240			240
and Stake No. 21	2.2		7.4	32	16	320			320
Between Stake No. 22	2.6		8.2	30	18	360			360
and Stake No. 23	2.3		7.6	31	18	360			360
Between Stake No. 24	2.4		7.8	30	16	320			320
and Stake No. 25	2.3		7.6	30	16	320			320
Between Stake No. 26	2.5		8.0	32	15	300			300
and Stake No. 27	2.8		8.6	30	25	500			500
Between Stake No. 28	2.7		8.4	28	30	600			600
and Stake No. 29	2.5		8.0	30	23	460			460
Between Stake No. 30	2.5		8.0	28	22	440			440
and Stake No. 31	2.9		10.8	34	24	680			680
Between Stake No. 32	2.6		8.2	36	23	660			660
and Stake No. 33	2.3		7.6	20	29	580			580
Between Stake No. and Stake No.									
Between Stake No. and Stake No.									
Between Stake No. and Stake No.									
Between Stake No. and Stake No.									
				431	307	6140			6140

Total Estimated Cost of Whole Work.....

