

Approximate present location of County Ditch No. 41

In Anoka County

Beginning in the present County Ditch, 784 feet south and 330 feet west of the north quarter corner of section 17, township 31 north, range 23 west; thence run southeasterly to a point distant 873 feet south and 65 feet west of said north quarter corner; thence east 115 feet; thence run northeasterly to a point distant 804 feet south and 275 feet east of the north quarter corner of said section 17.

Proposed location of County Ditch No. 41

Beginning in the present County Ditch, 784 feet south and 330 feet west of the north quarter corner of section 17, township 31 north, range 23 west; thence run southeasterly to a point distant 873 feet south and 65 feet west of said north quarter corner; thence east 115 feet; thence run northeasterly to a point distant 804 feet south and 275 feet east of the north quarter corner of said section 17.

### SUPPLEMENTAL AGREEMENT

Contractor Jay W. Craig Co.	Project DF 005-2 (16)	State Project No. 1-16-17, 1959
Address 1814 N. E. California	Project Location On 65, 0.7 Mi. No. of 10 to 2.9 Sta. No. of 10	

Contract number 9867 is amended as follows:

A complete set of this Agreement, with copies, shall be prepared by the Project Engineer who will obtain the contractor's signature to all copies and forward to the District Engineer for approval. All copies will then be forwarded to the Central Office for approval and distribution.

- WHEREAS, the plans provide for the placing of a culvert on the North bound Roadway at Engineers Station 539+18, and
- WHEREAS, said structural plate culvert is to be connected to a 48"x90" concrete box culvert in place on the South bound Roadway, and
- WHEREAS, in the interim existing between the original survey and actual construction, said 48"x90" concrete box culvert has deteriorated structurally necessitating its replacement

NOW, THEREFORE, IT IS HEREBY AGREED AS FOLLOWS:

1. A sectional concrete pipe shall be substituted for the structural plate culvert and shall be extended beneath the South bound Roadway.
2. The 48"x90" concrete box culvert shall be demolished and removed subject to the provisions of Specification 1410.
3. The backfill of the former ditch servicing the 48" box culvert will be obtained from adjacent cuts within the balance.
4. The sectional concrete culvert shall be installed on the North bound Lane plus all work up to and including the bituminous plant mix base construction shall be accomplished prior to any work on the South bound Lane to permit a detour of traffic to the North bound Lane.
5. A by-pass each side of the construction area shall be constructed to

Index	Item	Class	Quarter	Fund	Dept. Ident.
Amount Requested \$				Dated APR. 27 19 59	
Original Contract				Approved by Project Engineer	
Prev. Additions				Dated	19
Total to Date \$				Accepted by Comptroller	
Percentage—Increase—decrease				By	
				%	

Approved as to form and execution

APPROVED:  
Commissioner of Administration

Dated 19

District Engineer

Assistant Attorney General

By

Dated 19

Approved by Ag. Sec. 19

Dated

RESOLUTION

BE IT RESOLVED, That approval is hereby given the Minnesota Department of Highways to remove the structure presently in place at the crossing of T.H. 65 and County ditch #41 and to replace the structure with a culvert of adequate capacity.

SEAL

AUDITOR'S CERTIFICATION

STATE OF MINNESOTA )  
                          ) ss  
COUNTY OF ANOKA     )

I, Kenneth W. Campbell, County Auditor of Anoka County, Minnesota, hereby certify that I have compared the foregoing copy of resolution of the County Board of said County with the original record thereof on file in the office of the County Auditor of Anoka County, Minnesota, as stated in the minutes of the proceedings of said board at a meeting duly held on February 21, 1958, and that the same is a true and correct copy of said original record and of the whole thereof, and that said resolution was duly adopted by said board at said meeting.

Witness my hand and seal this 12th day of MAY, 1959.

\_\_\_\_\_  
Kenneth W. Campbell  
Anoka County Auditor