

EXHIBIT 2

ENGINEER'S REPORT
-IN-
DITCH PROCEEDINGS

JOHN D. MORGAN }
ARTHUR E. MORGAN } Engineers

Filed April 23, 1906.
Arthur H. Caswell
Co Auditor

ENGINEER

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Ditch No. 43 County of Arizoa As Amended.

Journal-Press Co., Printers and Binders, St. Cloud—10956

Morgan & Morgan Form, 1000, 2-26-06

REMARKS	STATION	Elevation of Surface		Elevation of Bottom		Cut		Width at Top		Width at Bottom		Area of Cross Section		Cubic Yards in Section Preceding		Estimated Cost per Cubic Yard		Total Estimated Cost of Section Preceding		Record of Bench Marks					
		FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	YARDS	100ths	Dollars	Cents	Dollars	Cents						
	21	76	15	73	90	2	30	5	30	3	00	9	50	3	530	12	1/2	4	41						
	22	76	10	73	80	2	30	5	30	"	"	9	50	3	530	"	"	4	41						
	23	76	10	73	70	2	40	5	40	"	"	10	10	3	630	"	"	4	54						
	24	75	95	73	60	2	40	5	40	"	"	10	10	3	740	"	"	4	65						
	25	76	05	73	50	2	60	5	60	"	"	11	20	3	940	"	"	4	92						
	26	75	85	73	40	2	50	5	50	"	"	10	60	4	040	"	"	5	05						
	27	75	70	73	30	2	40	5	40	"	"	10	10	3	830	"	"	4	79						
	28	75	70	73	20	2	50	5	50	"	"	10	60	3	830	"	"	4	79						
	29	75	70	73	10	2	60	5	60	"	"	11	20	4	040	"	"	5	05						
	30	75	70	73	00	2	70	5	70	"	"	11	70	4	240	"	"	5	30						
	31	75	80	72	90	2	90	5	90	"	"	12	90	4	560	"	"	5	70						
	32	76	05	72	80	3	30	6	30	"	"	15	30	5	220	"	"	6	52						
	33	76	15	72	70	3	50	6	50	"	"	16	60	5	910	"	"	7	39						
	34	75	70	72	60	3	10	6	10	"	"	14	10	5	690	"	"	7	11						
	35	75	40	72	50	2	90	5	90	"	"	12	90	5	000	"	"	6	25						
	36	75	30	72	40	2	90	5	90	"	"	12	90	4	780	"	"	5	98						
	37	75	30	72	30	3	00	6	00	"	"	13	50	4	890	"	"	6	11						
	38	75	40	72	20	3	20	6	20	"	"	14	70	5	220	"	"	6	53						
	39	75	20	72	10	3	10	6	10	"	"	14	10	5	330	"	"	6	66						
	40	76	05	72	00	4	10	7	10	"	"	20	70	6	440	"	"	8	05						
														9	13			11	4						
														<i>Amount brought forward</i>				11	4						
														<i>Total</i>				2	0			2	5		

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Ditch No. 43 County of 43

Journal-Press Co., Printers and Binders, St. Cloud—10956

Morgan & Morgan Form, 1000, 2-26-06

REMARKS	STATION	Elevation of Surface		Elevation of Bottom		Cut		Width at Top		Width at Bottom		Area of Cross Section		Cubic Yards in Section Preceding		Estimated Cost per Cubic Yard		Total Estimated Cost of Section Preceding		Record of Bench Marks
		FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	YARDS	100ths	Dollars	Cents	Dollars	Cents	
	81 ^a	70	21	67	70	2	50	5	50	3	00	10	60	24	40	12	½	4	30	
	82 ^a	70	71	67	65	3	10	6	10	"	"	14	10	45	70	"	"	5	71	
	83 ^a	71	71	67	60	4	10	7	10	"	"	20	70	64	40	"	"	8	05	
	84 ^a	73	61	67	55	6	10	9	10	"	"	36	90	106	70	"	"	13	84	
	85 ^a	72	71	67	50	5	20	8	20	"	"	29	10	122	20	"	"	15	28	
	86 ^a	76	21	67	45	8	80	14	80	"	"	65	10	174	40	"	"	21	80	
	87 ^a	77	00	67	40	9	60	12	60	"	"	74	90	259	30	"	"	32	41	
	88	74	61	67	35	7	30	10	30	"	"	48	50	228	50	"	"	28	56	
	84	71	30	67	30	4	00	7	00	"	"	20	00	126	90	"	"	15	86	
	85	70	00	67	25	2	80	5	80	"	"	12	30	59	80	"	"	7	48	
	86	70	30	67	20	3	10	6	10	"	"	14	10	48	90	"	"	6	11	
	87	68	50	67	15	1	40	4	40	"	"	5	20	35	70	"	"	4	46	
	88	68	50	67	10	1	40	4	40	"	"	5	20	19	30	"	"	2	41	
	89	68	80	67	05	1	80	4	80	"	"	7	00	22	60	"	"	2	82	
	90	69	50	67	00	2	50	5	50	"	"	10	60	32	60	"	"	4	08	
														1381	40			172	67	
														4706	40			588	30	
														6087	80			760	97	

Amount brought forward

Total

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Ditch No. 43 County of Anoka *As Amended.*

Journal-Press Co., Printers and Binders, St. Cloud—10956

Morgan & Morgan Form, 1000, 2-26-06

REMARKS	STATION	Elevation of Surface		Elevation of Bottom		Cut		Width at Top		Width at Bottom		Area of Cross Section		Cubic Yards in Section Preceding		Estimated Cost per Cubic Yard		Total Estimated Cost of Section Preceding		Record of Bench Marks	
		FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	YARDS	100ths	Dollars	Cents	Dollars	Cents		
	91	73	10	66	90	6	20													20	70
	92	73	70	66	80	6	90													25	00
	93	73	90	66	70	7	20													26	00
	94	75	43	66	60	8	80													28	00
	95	75	10	66	50	8	60													29	40
	96	71	80	66	40	5	40													26	00
	97	68	50	66	80	2	20													20	00
	98	69	30	66	20	3	10													20	00
	99	70	80	66	10	4	70													20	00
	100	71	80	66	00	5	80													22	50
	101	71	60	65	90	5	70													23	50
	102	72	30	65	80	6	50													24	20
	103	73	60	65	70	7	90													26	40
	104	74	90	65	60	8	30													29	20
	105	73	70	65	50	8	20													29	60
	106	74	30	65	40	8	90													29	00
	107	73	40	65	80	8	10													29	00
	108	73	07	65	20	7	90													28	00
	109	72	30	65	10	7	20													27	00
	110	72	80	65	00	7	80													27	00
																				510	50

To be laid with 12-inch drainage tile, according to specifications.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Ditch No. 43 County of Anoka. *As Amended.*

Journal-Press Co., Printers and Binders, St. Cloud—10956

Morgan & Morgan Form, 1000, 2-26-06

REMARKS	STATION	Elevation of Surface		Elevation of Bottom		Cut		Width at Top		Width at Bottom		Area of Cross Section		Cubic Yards in Section Preceding		Estimated Cost per Cubic Yard		Total Estimated Cost of Section Preceding		Record of Bench Marks		
		FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	FEET	100ths	YARDS	100ths	Dollars	Cents	Dollars	Cents			
	111	72	60	64	20	7	70													27	60	
	112	71	50	64	80	6	70													26	40	
	113	71	15	64	70	6	50													25	20	
	114	71	00	64	60	6	40													24	80	
	115	71	80	64	50	7	30													25	60	
	116	70	90	64	40	6	50													25	80	
	117	71	55	64	30	7	30													25	80	
	118	72	15	64	20	8	00													27	20	
	119	71	78	64	10	7	70													27	60	
	120	71	64	64	00	7	60													27	30	
	121	71	25	63	90	7	40													27	00	
	122	71	05	63	80	7	30													26	70	
	123	71	20	63	70	7	50													26	80	
	124	71	15	63	60	7	60													27	10	
	125	71	37	63	50	7	90													27	50	
	126	70	97	63	40	7	60													27	50	
	127	69	37	63	80	6	10													25	70	
	128	69	42	63	20	6	20													24	30	
	129	67	67	63	10	4	60													22	80	
	129+50	60	70	63	00	0														10	00	
																				5	08	70
																				5	10	50
																				10	19	20
																				76	09	7
																				178	01	7

To be laid with 12-inch drainage tile according to specifications.

Total cost of Tile in Open Ditch. 1019 20
 " " " Ditch 760 97
 1780 17

129 50