

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. 45

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yards		(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section				(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.		
XXXXXX Stake No. 0	3.0 ft.	2.0 ft.	8.0 ft.									
and Stake No. 1	2.3 ft.	2.0 ft.	6.6 ft.	46.48		11	\$ 5.11			4.90	\$ 10.01	
Between Stake No. 2	2.4 ft.	2.0 ft.	6.8 ft.	38.33		11	4.22			4.90	9.12	
and Stake No. 3	2.5 ft.	2.0 ft.	7.0 ft.	40.86		11	4.49			4.90	9.39	
Between Stake No. 4	2.7 ft.	2.0 ft.	7.4	44.16		11	4.86			4.90	9.76	
and Stake No. 5	2.7 ft.	2.0 ft.	7.4 ft.	46.14		11	5.08			4.90	9.98	
Between Stake No. 6	2.8 ft.	2.0 ft.	7.6 ft.	48.24		11	5.31			4.90	10.21	
and Stake No. 7	3.0 ft.	2.0 ft.	8.0 ft.	53.17		11	5.85			4.90	10.75	
Between Stake No. 8	3.2 ft.	2.0 ft.	8.4 ft.	59.26		11	6.52			4.90	11.42	
and Stake No. 9	3.4 ft.	2.0 ft.	8.8 ft.	66.07		11	7.27			4.90	12.17	
Between Stake No. 10	2.8 ft.	2.0 ft.	7.6 ft.	60.37		11	6.64			4.90	11.54	
and Stake No. 11	2.8 ft.	2.0 ft.	7.6 ft.	50.12		11	5.51			4.90	10.41	
Between Stake No. 12	2.9 ft.	2.0 ft.	7.8 ft.	50.89		11	5.60			4.90	10.50	
and Stake No. 13	3.0 ft.	2.0 ft.	8.0 ft.	54.54		11	6.00			4.90	10.90	
Between Stake No. 14	3.0 ft.	2.0 ft.	8.0 ft.	56.73		11	6.24			4.90	11.14	
and Stake No. 15	3.4 ft.	2.0 ft.	8.8 ft.	62.22		11	6.84			4.90	11.74	
Between Stake No. 16	4.0 ft.	2.0 ft.	10.0 ft.	73.20		11	8.05			4.90	12.95	
and Stake No. 17	4.7 ft.	2.0 ft.	11.4 ft.	102.96		11	11.32			4.90	16.22	
Between Stake No. 18	5.2 ft.	2.0 ft.	12.4 ft.	189.70		11	20.87			4.90	25.77	
XXXXXXXXXX and Stake No.			Totals.	1143.44			\$125.78			\$88.20	\$ 213.89	

Total Estimated Cost of Whole Work, \$-----

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Anoka County Ditch No. 45

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total per Section		(7) Total Estimated Cost per Section		
					\$	CTS.	\$	CTS.	\$	CTS.	
<i>Between Stake No.</i> 19	4.7 ft.	2.0 ft.	11.4 ft.	128.60		11	\$ 14.15		4	90	\$ 19 05
XXXX <i>and Stake No.</i> 20.	4.8 ft.	2.0 ft.	11.6 ft.	118.30		11	13.01		4	90	17.91
XXXX <i>Stake No.</i> 21.	5.4 ft.	2.0 ft.	12.8 ft.	124.14		11	13.65		4	90	18.56
XXXX <i>and Stake No.</i> 22.	5.4 ft.	2.0 ft.	12.8 ft.	138.17		12	16.66		4	90	21.56
XXXX <i>Between Stake No.</i> 23.	4.8 ft.	2.0 ft.	11.6 ft.	133.51		12	16.02		4	90	20.92
XXXX <i>and Stake No.</i> 24.	4.7 ft.	2.0 ft.	11.4 ft.	118.33		12	14.20		4	90	19.10
XXXX <i>Between Stake No.</i> 25.	4.7 ft.	2.0 ft.	11.4 ft.	117.25		12	14.07		4	90	18.97
XXXX <i>and Stake No.</i> 26.	4.8 ft.	2.0 ft.	11.8 ft.	120.44		12	14.44		4	90	19.34
XXXX <i>Between Stake No.</i> 27.	4.9 ft.	2.0 ft.	11.8 ft.	123.67		12	14.84		4	90	19.74
XXXX <i>and Stake No.</i> 28.	5.2 ft.	2.0 ft.	12.4 ft.	131.48		12	15.78		4	90	20.68
XXXX <i>Between Stake No.</i> 29.	4.9 ft.	2.0 ft.	11.8 ft.	131.10		12	15.73		4	90	20.63
XXXX <i>and Stake No.</i> 30.	5.2 ft.	2.0 ft.	12.4 ft.	131.66		12	15.80		4	90	20.70
XXXX <i>Between Stake No.</i> 31.	5.0 ft.	2.0 ft.	12.0 ft.	132.77		12	15.93		4	90	20.83
XXXX <i>and Stake No.</i> 32.	5.0 ft.	2.0 ft.	12.0 ft.	129.17		12	15.50		4	90	20.40
XXXX <i>Between Stake No.</i> 33.	4.9 ft.	2.0 ft.	11.8 ft.	128.06		11	14.09		4	90	18.99
XXXX <i>and Stake No.</i> 34.	4.8 ft.	2.0 ft.	11.6 ft.	124.78		11	13.72		4	90	18.63
XXXX <i>Between Stake No.</i> 35.	5.0 ft.	2.0 ft.	12.0 ft.	126.77		11	13.94		4	90	18.84
XXXX <i>and Stake No.</i> 36.	4.9 ft.	2.0 ft.	11.8 ft.	127.95		11	14.07		4	90	18.97
XXXX <i>Between Stake No.</i> 37.	5.0 ft.	2.0 ft.	12.2 ft.	128.95		11	14.18		4	90	19.08
XXXX <i>and Stake No.</i>											
Totals.				2415.10			\$ 279.78		\$ 93.10		\$ 372.90

Total Estimated Cost of Whole Work, \$-----

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. -- 45 --

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)			
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yards	Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section	Total Estimated Cost per Section	\$	CTS.	\$	CTS.	
					\$	CTS.	\$	CTS.	\$	CTS.		
Between Stake No. 38.	5.5 ft.	2.0 ft.	13.4 ft.	141.77		15	\$ 21.27		\$ 4	90	\$ 26	17
and Stake No. 39.	4.7 ft.	2.0 ft.	11.4 ft.	133.33		15	20.00		4	90	24	90
Between Stake No. 40.	4.7 ft.	2.0 ft.	11.5 ft.	117.25		15	17.57		4	90	22	49
and Stake No. 41.	2.1 ft.	2.0 ft.	6.2 ft.	75.30		11	8.28		4	90	13	18
Between Stake No. 42.	2.4 ft.	2.0 ft.	6.8 ft.	35.48		11	3.90		4	90	8	80
and Stake No. 43.	2.7 ft.	2.0 ft.	7.4 ft.	43.02		11	4.73		4	90	9	63
Between Stake No. 44.	3.0 ft.	2.0 ft.	8.0 ft.	51.29		11	5.64		4	90	10	54
and Stake No. 45.	2.8 ft.	2.0 ft.	7.6 ft.	53.63		11	5.79		4	90	10	69
Between Stake No. 46.	3.2 ft.	2.0 ft.	8.4 ft.	55.63		11	6.12		4	90	11	02
and Stake No. 47.	3.0 ft.	2.0 ft.	8.0 ft.	58.58		11	6.45		4	90	11	35
Between Stake No. 48.	2.3 ft.	2.0 ft.	6.6 ft.	46.11		11	5.07		4	90	9	97
and Stake No. 49.	2.6 ft.	2.0 ft.	7.2 ft.	40.44		11	4.44		4	90	9	34
Between Stake No. 50.	3.0 ft.	2.0 ft.	8.0 ft.	49.89		11	5.49		4	90	10	39
and Stake No. 51.	3.3 ft.	2.0 ft.	8.6 ft.	60.18		11	6.62		4	90	11	52
Between Stake No. 52.	3.6 ft.	2.0 ft.	9.2 ft.	69.77		11	7.68		4	90	12	58
and Stake No. 53.	3.8 ft.	2.0 ft.	9.6 ft.	78.18		11	8.60		4	90	13	50
Between Stake No. 54.	3.9 ft.	2.0 ft.	9.8 ft.	83.40		11	9.17		4	90	14	07
and Stake No. 55.	4.0 ft.	2.0 ft.	10.0 ft.	87.04		11	9.57		4	90	14	47
Between Stake No. 56.	4.1 ft.	2.0 ft.	10.2 ft.	90.74		11	9.98		4	90	14	88
and Stake No.				1379.05			\$ 166.39		\$ 93	10	\$ 259	49

Total Estimated Cost of Whole Work, \$-----

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. 45

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yards	(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section		(7) Total Estimated Cost per Section	
					\$ CTS.	\$	CTS.	\$	CTS.
<i>Between Stake No. 57.</i>	4.3 ft.	2.0 ft.	10.6 ft.	96.48	11	\$ 10.62		4 90	15 52
XXXX Stake No. 58.	4.4 ft.	2.0 ft.	10.8 ft.	102.40	11	11.26		4 99	16.16
Between Stake No. 59.	4.5 ft.	2.0 ft.	11.0 ft.	106.30	11	11.69		4 99	16.59
XXXX Stake No. 60.	4.6 ft.	2.0 ft.	11.2 ft.	110.18	11	12.12		4 90	17 02
Between Stake No. 61.	4.7 ft.	2.0 ft.	11.4 ft.	114.44	11	12.58		4 90	17 48
XXXX Stake No. 62.	5.4 ft.	2.0 ft.	12.8 ft.	132.40	11	14.56		4 90	19 46
Between Stake No. 63.	5.6 ft.	2.0 ft.	13.2 ft.	152.96	12	18.35		4 90	23.25
XXXX Stake No. 64.	6.1 ft.	2.0 ft.	14.2 ft.	178.18	12	21.38		4 90	26.28
Between Stake No. 65.	6.6 ft.		15.2 ft.	196.37	12	23.56		4 90	28.46
XXXX Stake No. 66.	8.0 ft.	12"	No. 2 Sewer Pipe.			45.00		4 90	49.90
Between Stake No. 67.	8.0 ft.	12"	No. 2 Sewer Pipe.			45.00		4 90	49.90
XXXX Stake No. 68.	8.00 ft.	12"	No. 2. Sewer Pipe.			45.00		4 90	49.90
Between Stake No. 69.	9.00 ft.	12"	No. 2. Sewer Pipe.			45.00		4 90	49.90
XXXX Stake No. 70.	10.0 ft.	12"	No. 2 Sewer Pipe.			48.00		4 90	52.90
Between Stake No. 71.	10.7 ft.	12"	No. 2 Sewer Pipe.			63.50		4 90	68 40
XXXX Stake No. 72.	11.0 ft.	12"	No. 2. Sewer Pipe.			75 10		4 90	80 00
Between Stake No. 73.	12.1 ft.	12"	No. 2. Sewer Pipe.			79.00		4 90	83.90
XXXX Stake No. 74.	12.1 ft.	12"	No. 2. Sewer Pipe.			82.30		4 90	87 20
Between Stake No. 75.	14.8 ft.	12"	No. 2. Sewer Pipe.			<u>96.50</u>		4 90	<u>101 40</u>
XXXXXXXXXXXX	5	Totals.		1189.71		\$ 760.52		\$ 93 10	\$ 853 62

Total Estimated Cost of Whole Work, \$.....

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. 45

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yards		(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section		(7) Total Estimated Cost per Section		
					\$	CTS.			\$	CTS.	
Between Stake No. 76.	15.7 ft.	12"	No. 2. Sewer Pipe.				\$ 114.40		4	90	\$ 119 30
and Stake No. 77.	16.2 ft.	12"	No. 2. Sewer Pipe.				120.70		4	90	125.60
Between Stake No. 78.	9.7 ft.	12"	No. 2. Sewer Pipe.				58.00		4	90	62.90
and Stake No. 79.	10.0 ft.	12"	No. 2. Sewer Pipe.				58.60		4	90	63.50
Between Stake No. 80.	10.4 ft.	12"	No. 2. Sewer Pipe.				60.40		4	90	65.30
and Stake No. 81.	9.8 ft.	12"	No. 2. Sewer Pipe.				58.00		4	90	62.90
Between Stake No. 82.	10.1 ft.	12"	No. 2. Sewer Pipe.				58.00		4	90	62.90
and Stake No. 83.	10.3 ft.	12"	No. 2. Sewer Pipe.				58.75		4	90	63.65
Between Stake No. 84.	9.9 ft.	12"	No. 2. Sewer Pipe.				58.00		4	90	62.90
and Stake No. 85.	9.8 ft.	12"	No. 2. Sewer Pipe.				56.90		4	90	61.80
Between Stake No. 86.	9.6 ft.	12"	No. 2. Sewer Pipe.				54.50		4	90	59.40
and Stake No. 87.	9.8 ft.	12"	No. 2. Sewer Pipe.				55.10		4	90	60.00
Between Stake No. 88.	9.8 ft.	12"	No. 2. Sewer Pipe.				53.80		4	90	58.70
and Stake No. 89.	9.7 ft.	12"	No. 2. Sewer Pipe.				52.60		4	90	57.50
Between Stake No. 90.	9.6 ft.	12"	No. 2. Sewer Pipe.				52.30		4	90	57.20
and Stake No. 91.	9.2 ft.	12"	No. 2. Sewer Pipe.				50.50		4	90	55.40
Between Stake No. 92.	8.5 ft.	12"	No. 2. Sewer Pipe.				47.50		4	90	52.40
and Stake No. 93.	8.4 ft.	12"	No. 2. Sewer Pipe.				46.50		4	90	51.40
Between Stake No. 94.	8.6 ft.	12"	No. 2. Sewer Pipe.				47.20		4	90	52.10
and Stake No.				Totals.			\$ 1161.75		\$ 93.10		\$ 1254.85

Total Estimated Cost of Whole Work, \$.....

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. 45, Page No. 6.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yards		(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section		(7) Total Estimated Cost per Section		
					\$	CTS.	\$	CTS.	\$	CTS.	
<i>Between Stake No. 95.</i>	8.6 ft.	12" No. 2. Sewer Pipe.					\$ 46.60	4	90	51	50
<i>and Stake No. 96.</i>	8.2 ft.	12" No. 2. Sewer Pipe.					45.70	4	90	50	60
Between Stake No. 97.	7.8 ft.	12" No. 2. Sewer Pipe.					44.50	4	90	49	40
and Stake No. 98.	7.4 ft.	12" No. 2. Sewer Pipe.					43.60	4	90	48	50
Between Stake No. 99.	7.4 ft.	12" No. 2. Sewer Pipe.					43.36	4	90	48	26
and Stake No. 100.	1.1 ft.	12" No. 2. Sewer Pipe.					43.00	4	90	47	90
Between Stake No. 101.	1.0 ft.	12" No. 2. Sewer Pipe.					43.00	4	90	47	90
and Stake No. 102.	3.5 ft.	12" No. 2. Sewer Pipe.					43.00	4	90	47	90
Between Stake No. 103.	4.0 ft.	2.0 ft. 10.0 ft.		80.07		12	9.60	4	90	14	50
and Stake No. 104.	4.7 ft.	2.0 ft. 11.4 ft.		102.59		12	12.30	4	90	17	20
Between Stake No. 105.	4.8 ft.	2.0 ft. 11.6 ft.		111.37		12	13.36	4	90	18	26
and Stake No. 106.	4.9 ft.	2.0 ft. 11.8 ft.		115.63		12	13.87	4	90	18	77
* Between Stake No. 107.	4.7 ft.	2.0 ft. 11.4 ft.		120.92		12	14.51	4	90	19	41
and Stake No. 107 + 40	4.2 ft.	2.0 ft. 10.4 ft.		42.62		12	5.11	2	00	7	11
<i>Between Stake No. and Stake No.</i>			Totals.	573.20			\$ 421.50	\$ 65	70	\$ 487	21
<i>Between Stake No. and Stake No.</i>											
<i>Between Stake No. and Stake No.</i>											
<i>Between Stake No. and Stake No.</i>											

Total Estimated Cost of Whole Work, \$-----

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. 45

SECTION	(1) DEPTH OF CUT		(2) WIDTH OF CUT AT BOTTOM		(3) WIDTH OF CUT AT TOP		(4) NO. OF CUBIC YARDS TO BE REMOVED		(5) Estimated Cost Per Cubic Yards		(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section		(7) Total Estimated Cost per Section		
	\$	CTS.	\$	CTS.	\$	CTS.	\$	CTS.	\$	CTS.	\$	CTS.	\$	CTS.	
<i>Between Stake No.</i>					B R A N C H		N o .		1.	P a g e N o . 2.					
<i>Between Stake No. 18.</i>															
<i>and Stake No. 19.</i>	3.7	ft.	2.0	ft.	9.4	ft.	75.37		11	\$ 8.28		4	90	13	18
<i>and Stake No. 20.</i>	3.9	ft.	2.0	ft.	9.6	ft.	80.92		11	8.90		4	90	13	80
<i>Between Stake No. 21.</i>	4.0	ft.	2.0	ft.	10.0	ft.	86.70		11	9.53		4	90	14	43
<i>and Stake No. 22.</i>	4.2	ft.	2.0	ft.	10.4	ft.	92.66		11	10.19		4	90	15	09
<i>Between Stake No. 23.</i>	4.3	ft.	2.0	ft.	10.6	ft.	98.78		11	10.86		4	90	15	76
<i>and Stake No. 24.</i>	4.5	ft.	2.0	ft.	11.0	ft.	105.12		11	11.56		4	90	16	46
<i>Between Stake No. 25.</i>	4.7	ft.	2.0	ft.	11.2	ft.	111.66		11	12.28		4	90	17	18
<i>and Stake No. 25 + 51</i>	4.8	ft.	2.0	ft.	11.6	ft.	<u>60.16</u>		11	<u>6.61</u>		4	90	11	51
<i>Between Stake No. and Stake No.</i>			Totals.				711.37			\$ 78.21		\$ 39	20	\$ 117	41
<i>Between Stake No. and Stake No.</i>															
<i>Between Stake No. and Stake No.</i>															
<i>Between Stake No. and Stake No.</i>															
<i>Between Stake No. and Stake No.</i>															
<i>Between Stake No. and Stake No.</i>															

Total Estimated Cost of Whole Work, \$

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County, Ditch No. 45

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yards		(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section		(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
BRANCH NO. 1.										
Between Stake No. 0.	4.0 ft.	2.0 ft.	10.0 ft.			11				
and Stake No. 1.	4.2 ft.	2.0 ft.	10.4 ft.	92.66		11	\$ 10.19		4 90	\$ 15.09
Between Stake No. 2.	4.7 ft.	2.0 ft.	11.2 ft.	104.89		11	11.53		4 90	16.43
and Stake No. 3.	4.4 ft.	2.0 ft.	10.2 ft.	109.19		11	12.00		4 90	16.90
Between Stake No. 4.	4.8 ft.	2.0 ft.	11.6 ft.	111.92		11	12.31		4 90	17.21
and Stake No. 5.	5.0 ft.	2.0 ft.	12.0 ft.	123.70		11	13.60		4 90	18.50
Between Stake No. 6.	5.1 ft.	2.0 ft.	12.2 ft.	131.41		11	14.45		4 90	19.35
and Stake No. 7.	5.3 ft.	2.0 ft.	12.6 ft.	138.66		11	15.25		4 90	20.15
Between Stake No. 8.	5.4 ft.	2.0 ft.	12.8 ft.	146.11		11	16.07		4 90	20.97
and Stake No. 9.	5.6 ft.	2.0 ft.	13.2 ft.	153.77		11	16.91		4 90	21.81
Between Stake No. 10.	5.7 ft.	2.0 ft.	13.4 ft.	160.60		11	17.66		4 90	22.56
and Stake No. 11.	6.0 ft.	2.0 ft.	14.0 ft.	171.18		11	18.82		4 90	23.72
Between Stake No. 12.	5.6 ft.	2.0 ft.	13.2 ft.	167.75		11	18.45		4 90	23.35
and Stake No. 13.	4.2 ft.	2.0 ft.	10.4 ft.	127.33		11	14.00		4 90	18.90
Between Stake No. 14.	3.9 ft.	2.0 ft.	9.8 ft.	91.59		11	10.07		4 90	14.97
and Stake No. 15.	4.1 ft.	2.0 ft.	10.2 ft.	88.15		11	9.69		4 90	14.59
Between Stake No. 16.	3.7 ft.	2.0 ft.	9.4 ft.	84.96		11	9.34		4 90	14.24
and Stake No. 17.	3.4 ft.	2.0 ft.	8.8 ft.	73.07		11	8.03		4 90	12.93
Between Stake No. 18.	3.5 ft.	2.0 ft.	9.0 ft.	69.97		11	7.69		4 90	12.59
and Stake No.	Totals.			2146.11			\$ 236.06		\$ 88 20	\$ 324 26

Total Estimated Cost of Whole Work, \$.....

Exhibit
No. 2

Ditch No. 45
Anoka Co.

Filed March 30, 1907.

Arthur A. Small
Co. Auditor