

Exhibit No. 3:

Ditch No. 47 ----- "Hard"

Anoka County

Filed this 13th day
of June 1907
Arthur H. Russell
County Auditor.

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County, Ditch No. 47.

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | (7) Total Estimated Cost per Section | |
|--------------------------------------------|----------------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|------|------------------------------------------------------------------------------------------------------------------------------------------------|------------|-----------------------------------------------|------|
| | | | | | \$ | CTS. | \$ | CTS. | \$ | CTS. |
| <i>Between Stake No. and Stake No.</i> | | Recapitulation. | | Cu. Yds | | | Auditor, | \$ 100 | 00 | |
| <i>Between Stake No. and Stake No.</i> | Main Line | | | Estimate Cost. | | | Printing, | 30 | 00 | |
| <i>Between Stake No. and Stake No.</i> | Branch No. 1. | | 3162.10 | 399.35 | | | Sheriff, | 75 | 00 | |
| <i>Between Stake No. and Stake No.</i> | Branch No. 2. | | 180.85 | 21.68 | | | Register of Deeds, | 5 | 00 | |
| <i>Between Stake No. and Stake No.</i> | Branch No. 3. | | <u>139.07</u> | <u>16.70</u> | | | Commissioners, | 100 | 00 | |
| <i>Between Stake No. and Stake No.</i> | Total Excavation and Cost. | | 3482.02 | \$ 501.73 | | | Viewers, 4 days, | 60 | 00 | |
| <i>Between Stake No. and Stake No.</i> | Preliminary Expenses, | | | <u>564.15</u> | | | Engineer with Viewers | 20 | 00 | |
| <i>Between Stake No. and Stake No.</i> | Total Cost! | | | \$ 1065.88 | | | Inspecting Finished work, | 60 | 00 | |
| <i>Between Stake No. and Stake No.</i> | | | | | | | Survey, | <u>114</u> | <u>15</u> | |
| <i>Between Stake No. and Stake No.</i> | | | | | | | Total preliminary expense | \$ 564 | 15 | |

Total Estimated Cost of Whole Work, \$

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. --- 47, ----

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | | (7) Total Estimated Cost per Section | |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------|-----------------------------------------------|------|
| | | | | | \$ | CTS. | | \$ | CTS. | \$ | CTS. |
| <p><i>Between Stake No. and Stake No. Between Stake No. and Stake No. Between Stake No. and Stake No. Between Stake No. and Stake No. Between Stake No. and Stake No. Between Stake No. and Stake No. Between Stake No. and Stake No. Between Stake No. and Stake No. Between Stake No. and Stake No.</i></p> | | | | Main Line | | | <p>Between Stations No. 30 and Station 55 the line will follow the present bed of the creek all of the way making a distance of 3200 feet or Thirty Two (32) stations as the bed is so irregular it is estimated that Two (2) Dollars per station will clean the creek which will make</p> | \$ 64.00 | \$139.84 | \$ 203 84 | |

Total Estimated Cost of Whole Work, \$-----

Summary of Branch No. 1. Ditch No. 47 Anoka County.

| | Cubic | Excavation | Preliminary | |
|--------------|---------------|--------------|--------------|---------------|
| | Yds. | Cost. | Cost. | Total. |
| Sheet No. 1. | 677.91 | \$ 81.36 | \$ 78.66 | \$ 160.02 |
| Sheet No. 2. | 727.23 | 89.69 | 83.03 | 172.71 |
| Sheet No. 3. | 989.73 | 129.17 | 83.03 | 212.20 |
| Sheet No. 4. | <u>767.32</u> | <u>99.14</u> | <u>65.55</u> | <u>164.69</u> |
| Totals. | 3162.10 | \$ 399.35 | \$ 310.27 | \$ 709.62 |

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County. Ditch No. 47.

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | | | (7) Total Estimated Cost per Section | |
|-----------------------|---------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|------|------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|------|-----------------------------------------------|----|
| | | | | | \$ | CTS. | \$ | CTS. | \$ | CTS. | | |
| Branch No. 1. | | | | | | | | | | | | |
| Between Stake No. 19. | 2.1 ft. | 2.0 ft. | 6.2 ft. | 33.55 | | 12 | \$ 4.03 | | \$ 4 | 37 | \$ 8 | 40 |
| and Stake No. 20. | 2.1 " | 2.0 " | 6.2 " | 31.89 | | 12 | 3.83 | | 4 | 37 | 8 | 20 |
| Between Stake No. 21. | 2.0 " | 2.0 " | 6.0 " | 30.76 | | 12 | 3.69 | | 4 | 37 | 8 | 06 |
| and Stake No. 22. | 2.2 " | 2.0 " | 6.4 " | 31.89 | | 12 | 3.83 | | 4 | 37 | 8 | 20 |
| Between Stake No. 23. | 2.2 " | 2.0 " | 6.4 " | 34.22 | | 12 | 4.21 | | 4 | 37 | 8 | 48 |
| and Stake No. 24. | 2.3 " | 2.0 " | 6.6 " | 35.43 | | 12 | 4.25 | | 4 | 37 | 8 | 62 |
| Between Stake No. 25. | 2.3 " | 2.0 " | 6.6 " | 36.63 | | 12 | 4.40 | | 4 | 37 | 8 | 77 |
| and Stake No. 26. | 2.6 " | 2.0 " | 7.2 " | 40.39 | | 12 | 4.85 | | 4 | 37 | 9 | 22 |
| Between Stake No. 27. | 2.6 " | 2.0 " | 7.2 " | 44.29 | | 12 | 5.31 | | 4 | 37 | 9 | 68 |
| and Stake No. 28. | 2.4 " | 2.0 " | 6.8 " | 41.67 | | 12 | 5.00 | | 4 | 37 | 9 | 37 |
| Between Stake No. 29. | 2.4 " | 2.0 " | 6.8 " | 39.11 | | 12 | 4.69 | | 4 | 37 | 9 | 06 |
| and Stake No. 30. | 2.3 " | 2.0 " | 6.6 " | 37.87 | | 12 | 4.54 | | 4 | 37 | 8 | 91 |
| Between Stake No. 31. | 2.1 " | 2.0 " | 6.2 " | 34.22 | | 12 | 4.11 | | 4 | 37 | 8 | 48 |
| and Stake No. 32. | 2.1 " | 2.0 " | 6.2 " | 31.89 | | 12 | 3.83 | | 4 | 37 | 8 | 20 |
| Between Stake No. 33. | 2.2 " | 2.0 " | 6.4 " | 33.55 | | 12 | 4.03 | | 4 | 37 | 8 | 40 |
| and Stake No. 34. | 2.2 " | 2.0 " | 6.4 " | 34.22 | | 12 | 4.11 | | 4 | 37 | 8 | 48 |
| Between Stake No. 35. | 2.4 " | 2.0 " | 6.8 " | 36.63 | | 12 | 4.40 | | 4 | 37 | 8 | 77 |
| and Stake No. 36. | 3.4 " | 2.0 " | 8.8 " | 52.63 | | 14 | 7.37 | | 4 | 37 | 11 | 74 |
| Between Stake No. 37. | 3.3 " | 2.0 " | 8.6 " | 66.39 | | 14 | 9.30 | | 4 | 37 | 13 | 67 |
| and Stake No. | Totals. | | | 727.23 | | | \$ 89.68 | | \$ 83 | 03 | \$ 172 | 71 |

Total Estimated Cost of Whole Work, \$

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County Ditch No. 47.

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | | | (7) Total Estimated Cost per Section | |
|-----------------------|---------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|------|------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------|-----------|-----------------------------------------------|-----------|
| | | | | | \$ | CTS. | \$ | CTS. | \$ | CTS. | | |
| | | | | Branch No. 1. | | | | | | | | |
| Between Stake No. 0. | 2.0 ft. | 2.0 ft. | 6.0 ft. | | | | | | | | | |
| and Stake No. 1. | 2.7 " | 2.0 " | 7.4 " | 37.87 | | 12. | \$ 4.54 | | \$ 4 | 37 | \$ 8 | 91 |
| Between Stake No. 2. | 2.1 " | 2.0 " | 6.2 " | 44.16 | | 12 | 5.30 | | 4 | 37 | 9 | 67 |
| and Stake No. 3. | 2.5 " | 2.0 " | 7.0 " | 36.63 | | 12 | 4.40 | | 4 | 37 | 8 | 77 |
| Between Stake No. 4. | 2.4 " | 2.0 " | 6.8 " | 40.39 | | 12 | 4.85 | | 4 | 37 | 9 | 22 |
| and Stake No. 5. | 2.3 " | 2.0 " | 6.6 " | 37.87 | | 12 | 4.54 | | 4 | 37 | 8 | 91 |
| Between Stake No. 6. | 2.5 " | 2.0 " | 7.0 " | 39.11 | | 12 | 4.69 | | 4 | 37 | 9 | 06 |
| and Stake No. 7. | 2.4 " | 2.0 " | 6.8 " | 40.39 | | 12 | 4.85 | | 4 | 37 | 9 | 22 |
| Between Stake No. 8. | 2.4 " | 2.0 " | 6.8 " | 39.11 | | 12 | 4.69 | | 4 | 37 | 9 | 06 |
| and Stake No. 9. | 2.2 " | 2.0 " | 6.4 " | 36.63 | | 12 | 4.40 | | 4 | 37 | 8 | 77 |
| Between Stake No. 10. | 1.9 " | 2.0 " | 5.8 " | 30.76 | | 12 | 3.69 | | 4 | 37 | 8 | 06 |
| and Stake No. 11. | 2.4 " | 2.0 " | 6.8 " | 33.55 | | 12 | 4.03 | | 4 | 37 | 8 | 40 |
| Between Stake No. 12. | 2.4 " | 2.0 " | 6.8 " | 39.11 | | 12 | 4.69 | | 4 | 37 | 9 | 06 |
| and Stake No. 13. | 2.2 " | 2.0 " | 6.4 " | 36.63 | | 12 | 4.40 | | 4 | 37 | 8 | 77 |
| Between Stake No. 14. | 2.4 " | 2.0 " | 6.8 " | 36.63 | | 12 | 4.40 | | 4 | 37 | 8 | 77 |
| and Stake No. 15. | 2.4 " | 2.0 " | 6.8 " | 39.11 | | 12 | 4.69 | | 4 | 37 | 9 | 06 |
| Between Stake No. 16. | 2.4 " | 2.0 " | 6.8 " | 39.11 | | 12 | 4.69 | | 4 | 37 | 9 | 06 |
| and Stake No. 17. | 2.2 " | 2.0 " | 6.4 " | 36.63 | | 12 | 4.40 | | 4 | 37 | 8 | 77 |
| Between Stake No. 18. | 2.2 " | 2.0 " | 6.4 " | 34.22 | | 12 | 4.11 | | 4 | 37 | 8 | 48 |
| and Stake No. | | Totals. | | 677.91 | | | \$ 81.36 | | \$ 78 | 66 | \$ 160 | 02 |

Total Estimated Cost of Whole Work, \$-----

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County. Ditch No. 47.

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | (7) Total Estimated Cost per Section | |
|--------------------------------------------|---------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|----------|------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------------------------------------|------|
| | | | | | \$ | CTS. | \$ | CTS. | \$ | CTS. |
| | | | | Branch No. 1. | | | | | | |
| Between Stake No. 57. and Stake No. 58. | 3.1 ft. | 2.0 ft. | 8.2 ft. | 64.77 | 14 | \$ 9.97 | | \$ 4 37 | \$ 13 44 | |
| Between Stake No. 59. and Stake No. 60. | 3.1 " | 2.0 " | 8.2 " | 58.55 | 14 | 8.20 | | 4 37 | 12 57 | |
| Between Stake No. 61. and Stake No. 62. | 3.6 " | 2.0 " | 9.2 " | 66.39 | 14 | 9.30 | | 4 37 | 13 67 | |
| Between Stake No. 63. and Stake No. 64. | 4.2 " | 2.0 " | 10.4 " | 85.20 | 14 | 11.93 | | 4 37 | 16 30 | |
| Between Stake No. 65. and Stake No. 66. | 3.1 " | 2.0 " | 8.2 " | 76.37 | 14 | 10.69 | | 4 37 | 15 06 | |
| Between Stake No. 67. and Stake No. 68. | 2.9 " | 2.0 " | 7.8 " | 55.56 | 12 | 6.67 | | 4 37 | 11 04 | |
| Between Stake No. 69. and Stake No. 70. | 2.5 " | 2.0 " | 7.0 " | 47.00 | 12 | 5.64 | | 4 37 | 10 01 | |
| Between Stake No. 71. and Stake No. 72. | 2.6 " | 2.0 " | 7.2 " | 42.98 | 12 | 5.16 | | 4 37 | 9 53 | |
| Between Stake No. 73. and Stake No. 74. | 2.6 " | 2.0 " | 7.2 " | 44.29 | 12 | 5.32 | | 4 37 | 9 69 | |
| Between Stake No. 75. and Stake No. 76. | 2.5 " | 2.0 " | 7.0 " | 42.98 | 12 | 5.16 | | 4 37 | 9 53 | |
| Between Stake No. 77. and Stake No. 78. | 3.0 " | 2.0 " | 8.0 " | 48.38 | 12 | 5.81 | | 4 37 | 10 18 | |
| Between Stake No. 79. and Stake No. 80. | 1.8 " | 2.0 " | 5.6 " | 39.11 | 12 | 4.69 | | 4 37 | 9 06 | |
| Between Stake No. 81. and Stake No. 82. | 2.0 " | 2.0 " | 6.0 " | 29.63 | 12 | 3.56 | | 4 37 | 7 93 | |
| Between Stake No. 83. and Stake No. 84. | 2.1 " | 2.0 " | 6.2 " | 31.89 | 12 | 3.83 | | 4 37 | 8 20 | |
| Between Stake No. 85. and Stake No. 86. | 2.3 " | 2.0 " | 6.6 " | 34.22 | 12 | 4.11 | | 4 37 | 8 48 | |
| | | Totals. | | 767.32 | | \$ 99.14 | | \$ 65 55 | \$ 164.69 | |

Total Estimated Cost of Whole Work, \$

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County, Ditch No. 47.

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | | | (7) Total Estimated Cost per Section | |
|-----------------------|---------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|------|------------------------------------------------------------------------------------------------------------------------------------------------|------|-------|------|-----------------------------------------------|----|
| | | | | | \$ | CTS. | \$ | CTS. | \$ | CTS. | | |
| Between Stake No. 38. | 3.1 ft. | 2.0 ft. | 8.2 ft. | 61.62 | | 14 | \$ 8.63 | | \$ 4 | 37 | \$ 13 | 00 |
| and Stake No. 39. | 3.2 " | 2.0 " | 8.4 " | 60.08 | | 14 | 8.41 | | 4 | 37 | 12 | 78 |
| Between Stake No. 40. | 2.8 " | 2.0 " | 7.6 " | 55.56 | | 14 | 7.78 | | 4 | 37 | 12 | 15 |
| and Stake No. 41. | 3.1 " | 2.0 " | 8.2 " | 54.09 | | 14 | 7.57 | | 4 | 37 | 11 | 94 |
| Between Stake No. 42. | 2.6 " | 2.0 " | 7.2 " | 51.19 | | 12 | 6.14 | | 4 | 37 | 10 | 51 |
| and Stake No. 43. | 2.4 " | 2.0 " | 6.8 " | 41.67 | | 12 | 5.00 | | 4 | 37 | 9 | 37 |
| Between Stake No. 44. | 2.4 " | 2.0 " | 6.8 " | 39.11 | | 12 | 4.69 | | 4 | 37 | 9 | 06 |
| and Stake No. 45. | 2.5 " | 2.0 " | 7.0 " | 40.39 | | 12 | 4.85 | | 4 | 37 | 9 | 22 |
| Between Stake No. 46. | 2.7 " | 2.0 " | 7.4 " | 44.29 | | 12 | 5.32 | | 4 | 37 | 9 | 69 |
| and Stake No. 47. | 2.6 " | 2.0 " | 7.2 " | 45.65 | | 12 | 5.48 | | 4 | 37 | 9 | 85 |
| Between Stake No. 48. | 3.0 " | 2.0 " | 8.0 " | 49.77 | | 12 | 5.97 | | 4 | 37 | 10 | 34 |
| and Stake No. 49. | 2.9 " | 2.0 " | 7.8 " | 54.09 | | 12 | 6.49 | | 4 | 37 | 10 | 86 |
| Between Stake No. 50. | 3.2 " | 2.0 " | 8.4 " | 57.00 | | 14 | 7.98 | | 4 | 37 | 12 | 35 |
| and Stake No. 51. | 3.0 " | 2.0 " | 8.0 " | 58.55 | | 14 | 8.20 | | 4 | 37 | 12 | 57 |
| Between Stake No. 52. | 3.1 " | 2.0 " | 8.2 " | 57.00 | | 14 | 7.98 | | 4 | 37 | 12 | 35 |
| and Stake No. 53. | 2.8 " | 2.0 " | 7.6 " | 54.09 | | 12 | 6.49 | | 4 | 37 | 10 | 86 |
| Between Stake No. 54. | 2.8 " | 2.0 " | 7.6 " | 49.77 | | 12 | 5.97 | | 4 | 37 | 10 | 34 |
| and Stake No. 55. | 3.0 " | 2.0 " | 8.0 " | 52.62 | | 14 | 7.37 | | 4 | 37 | 11 | 74 |
| Between Stake No. 56. | 3.5 " | 2.0 " | 9.0 " | 63.19 | | 14 | 8.85 | | 4 | 37 | 13 | 22 |
| and Stake No. | | Totals. | | 989.73 | | | \$ 129.17 | | \$ 83 | 03 | \$ 212 | 20 |

Total Estimated Cost of Whole Work, \$.....

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County, Ditch No. 47.

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | (7) Total Estimated Cost per Section | |
|---------------------------------|---------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|------|------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------------------------------------------|------|
| | | | | | \$ | CTS. | | | \$ | CTS. |
| | | | | | | | | | | |
| Branch No. 2. | | | | | | | | | | |
| <i>Between Stake No. 90.</i> | 2.6 ft. | 2.0 ft. | 7.2 ft. | | | | | | | |
| <i>and Stake No. 1.</i> | 2.7 " | 2.0 " | 7.4 " | 45.64 | | 12 | \$ 5.46 | \$ 4 37 | \$ 9 85 | |
| <i>Between Stake No. 2.</i> | 2.7 " | 2.0 " | 7.4 " | 47.00 | | 12 | 5.64 | 4 37 | 10 01 | |
| <i>and Stake No. 3.</i> | 2.6 " | 2.0 " | 7.2 " | 45.64 | | 12 | 5.48 | 4 37 | 9 85 | |
| <i>Between Stake No. 3 + 90</i> | 2.8 " | 2.0 " | 7.6 " | 42.30 | | 12 | 5.08 | 4 37 | 9 45 | |
| <i>and Stake No.</i> | | Totals. | | 180.85 | | | \$ 21.68 | \$ 17.48 | \$ 39 16 | |
| <i>Between Stake No.</i> | | | | | | | | | | |
| <i>and Stake No.</i> | | | | | | | | | | |
| <i>Between Stake No.</i> | | | | | | | | | | |
| <i>and Stake No.</i> | | | | | | | | | | |
| <i>Between Stake No.</i> | | | | | | | | | | |
| <i>and Stake No.</i> | | | | | | | | | | |
| <i>Between Stake No.</i> | | | | | | | | | | |
| <i>and Stake No.</i> | | | | | | | | | | |
| <i>Between Stake No.</i> | | | | | | | | | | |
| <i>and Stake No.</i> | | | | | | | | | | |

Total Estimated Cost of Whole Work, \$

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Anoka County, Ditch No. 47 ///

| SECTION | (1) DEPTH OF CUT | (2) WIDTH OF CUT AT BOTTOM | (3) WIDTH OF CUT AT TOP | (4) NO. OF CUBIC YARDS TO BE REMOVED | (5) Estimated Cost Per Cubic Yards | | (6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section | | | (7) Total Estimated Cost per Section | |
|------------------------------------------------------|---------------------|----------------------------------|-------------------------------|--------------------------------------------|------------------------------------------|------|------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-----------------------------------------------|-----------|
| | | | | | \$ | CTS. | | \$ | CTS. | \$ | CTS. |
| <i>Between Stake No. and Stake No.</i> | | | | Branch No. 3. | | | | | | | |
| <i>Between Stake No. and Stake No. 0.</i> | 2.3 ft. | 2.0 ft. | 6.6 ft. | | | | | | | | |
| <i>Between Stake No. 1. and Stake No. 2.</i> | 2.4 " | 2.0 " | 6.8 " | 37.87 | | 12 | \$ 4.55 | \$ 4 | 37 | \$ 8 | 92 |
| <i>Between Stake No. 3. and Stake No. 3 + 10</i> | 2.8 " | 2.0 " | 7.6 " | 42.98 | | 12 | 5.16 | 4 | 37 | 9 | 53 |
| | 3.0 " | 2.0 " | 8.0 " | 52.62 | | 12 | 6.32 | 4 | 37 | 10 | 69 |
| | 3.0 | 2.0 " | 8.0 " | <u>5.56</u> | | 12 | <u>.67</u> | <u>4</u> | <u>37</u> | <u>5</u> | <u>04</u> |
| <i>Between Stake No. and Stake No.</i> | | | | 139.03 | | | \$ 16.70 | \$ 17 | 48 | \$ 34 | 18 |
| <i>Between Stake No. and Stake No.</i> | | | | | | | | | | | |
| <i>Between Stake No. and Stake No.</i> | | | | | | | | | | | |
| <i>Between Stake No. and Stake No.</i> | | | | | | | | | | | |
| <i>Between Stake No. and Stake No.</i> | | | | | | | | | | | |
| <i>Between Stake No. and Stake No.</i> | | | | | | | | | | | |

Total Estimated Cost of Whole Work, \$

EXHIBIT 2.

Engineer's Report

IN

Ditch Proceedings.
