

ENGINEER'S REPORT

IN

DITCH PROCEEDINGS.

Filed this 13th day
 of June 1907
M. D. [Signature]
 County Auditor.

Exhibit 2 of Engineer's Report in Ditch Proceedings.

Showing Time and Manner in which same must be done. Ditch No. 47.

SECTION	TIME WITHIN WHICH WORK MUST BE DONE	MANNER IN WHICH WORK MUST BE DONE	MATERIALS USED	COST OF MATERIALS AND WORK
Stake No. TO Stake No.	On the Main Line only that part of the Creek as lies between Station No. 30 and Sta. 55 as now staked out will be worked. And that part will be only cleaned of all willows, brush covered wood etc as is in the bed of the creek, also all sand bars will be removed to such a depth that no riffle will show. The bed will be cleaned between the stations mentioned of all and every material that will in any manner retard the flow of the water in the creek	Main Line.	MATERIALS USED	COST OF MATERIALS AND WORK
Stake No. TO Stake No.	Within Sixty (60) days after signing contract.	The several items are as follows :-	No estimate made because bottom so irregular and amounts small	\$ 64 00
Station 0 tp Station 72. Stake No. TO Stake No.	Within Sixty (60) days after signing Contract.	Ditch to be an open ditch Two (2) feet on the bottom and with a side slope of One (1) to One (1). Berm to be Two (2) feet on both sides of the ditch. Earth to be deposited in piles along the line of the Ditch. For further information see Specifications.	Branch No. 1.	\$ 399 35
Stake No. TO Stake No.	Same as Branch No. 1.	Branch No. 2.	Same as Branch No. 1.	\$ 21 68
Stake No. TO Stake No.	Same as Branch No. 1.	Branch No. 3.	Same as Branch No. 1.	\$ 16 20
Stake No. TO Stake No.	Same as Branch No. 1.	Branch No. 1.	Total Cost.	\$ 501 73