

Estimated Cost of Branch No. 3. of

Ditch No. 49.

Sheets..	Cubic Yards.	Excavation Cost.	Preliminary Cost.	Total Cost.
No. 1.	1742.01	\$ 208.96	\$ 38.00	\$ 246.96
" 2.	<u>838.19</u>	<u>100.54</u>	<u>18.00</u>	<u>118.54</u>
Totals.	2580.020	\$ 309.50	\$ 56.00	\$ 365.50

Filed this 27th day
of September 1908
Arthur Maswell
County Auditor.
By Carrie S. Piper
Deputy

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Branch 3 Ditch No. 49

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yards		(6) Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section		(7) Total Estimated Cost per Section		
					\$	CTS.	\$	CTS.	\$	CTS.	
Between Stake No. 0 and Stake No. 1	4.3	7	10.6								
Between Stake No. 2 and Stake No. 3	4.0		10.0	94.22	12	11.30	2.00	13.30			
Between Stake No. 4 and Stake No. 5	3.8		9.6	85.20	12	10.22	2.00	12.22			
Between Stake No. 6 and Stake No. 7	4.3		10.6	90.44	12	10.85	2.00	12.85			
Between Stake No. 8 and Stake No. 9	4.2		10.4	98.36	12	11.80	2.00	13.80			
Between Stake No. 10 and Stake No. 11	4.2		10.4	96.43	12	11.57	2.00	13.57			
Between Stake No. 12 and Stake No. 13	4.2		10.4	96.43	12	11.57	2.00	13.57			
Between Stake No. 14 and Stake No. 15	5.2		12.4	116.60	12	13.99	2.00	15.99			
Between Stake No. 16 and Stake No. 17	4.4		10.8	120.86	12	14.50	2.00	16.50			
Between Stake No. 18 and Stake No. 19	4.1		10.2	98.37	12	11.80	2.00	13.80			
Between Stake No. 20 and Stake No. 21	3.9		9.8	88.87	12	10.66	2.00	12.66			
Between Stake No. 22 and Stake No. 23	4.0		10.0	87.03	12	10.44	2.00	12.44			
Between Stake No. 24 and Stake No. 25	3.9		9.8	87.03	12	10.44	2.00	12.44			
Between Stake No. 26 and Stake No. 27	3.8		9.6	83.40	12	10.00	2.00	12.00			
Between Stake No. 28 and Stake No. 29	3.9		9.8	83.40	12	10.00	2.00	12.00			
Between Stake No. 30 and Stake No. 31	3.9		9.8	85.20	12	10.22	2.00	12.22			
Between Stake No. 32 and Stake No. 33	3.6		9.2	79.85	12	9.57	2.00	11.57			
Between Stake No. 34 and Stake No. 35	3.8		9.6	78.09	12	9.37	2.00	11.37			
Between Stake No. 36 and Stake No. 37	4.0		10.0	85.20	12	10.22	2.00	12.22			
Between Stake No. 38 and Stake No. 39	3.9		9.8	87.03	12	10.40	2.00	12.44			
				1742.11							
					\$ 208.96						
					Total Estimated Cost of Whole Work,		\$ 38.00		\$ 246.96		

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Branch 3 Ditch No. 49

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)		
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yards		Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work Until Completed With Total Per Section		Total Estimated Cost per Section		
					\$	CTS.		\$	CTS.	\$	CTS.
Between Stake No. 20 and Stake No. 1	4.0	7	10.0	87.03		12	10.44		2.00		12.44
Between Stake No. 2 and Stake No. 3	4.1		10.2	90.44		12	10.85		2.00		12.85
Between Stake No. 3 and Stake No. 4	4.2		10.4	94.22		12	11.30		2.00		13.20
Between Stake No. 4 and Stake No. 5	4.3		10.6	98.37		12	11.80		2.00		13.80
Between Stake No. 5 and Stake No. 6	4.3		10.6	100.32		12	12.03		2.00		14.03
Between Stake No. 6 and Stake No. 7	4.5		11.0	104.27		12	12.51		2.00		14.51
Between Stake No. 7 and Stake No. 8	4.6		11.2	110.36		12	13.24		2.00		15.24
Between Stake No. 8 and Stake No. 9	4.7		11.4	114.51		12	13.74		2.00		15.74
Between Stake No. 9 and Stake No. 10	4.9		11.8	38.67		12	4.63		2.00		6.63
				838.19			\$100.54		\$18.00		\$118.54
Between Stake No. 10 and Stake No. 11											
Between Stake No. 11 and Stake No. 12											
Between Stake No. 12 and Stake No. 13											
Between Stake No. 13 and Stake No. 14											
Between Stake No. 14 and Stake No. 15											
Between Stake No. 15 and Stake No. 16											
Between Stake No. 16 and Stake No. 17											
Between Stake No. 17 and Stake No. 18											

Total Estimated Cost of Whole Work, \$.....