

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Branch No. 5 Ditch No. 53.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)				(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				Total Estimated Cost per Section	
					\$	CTS.			\$	CTS.	\$	CTS.
Between Stake No. 0.	4.0 ft.	4.0 ft.	12.0 ft.									
and Stake No. 1.	4.4 "	4.0 "	12.8 "	127.7		10	\$ 12.77		2 00		\$ 14 77	
Between Stake No. 2.	4.3 "	4.0 "	12.6 "	134.5		10	13.45		2 00		15 45	
and Stake No. 3.	4.1 "	4.0 "	12.4 "	127.4		10	12.74		2 00		14 74	
Between Stake No. 4.	4.2 "	4.0 "	12.4 "	125.2		10	12.52		2 00		14 52	
and Stake No. 5.	4.6 "	4.0 "	13.2 "	137.0		10	13.70		2 00		15 70	
Between Stake No. 6.	4.4 "	4.0 "	12.8 "	141.8		10	14.18		2 00		16 18	
and Stake No. 7.	4.2 "	4.0 "	12.4 "	132.5		10	13.25		2 00		15 25	
Between Stake No. 8.	4.1 "	4.0 "	12.2 "	125.2		10	12.25		2 00		24 52	
and Stake No. 9.	4.0 "	4.0 "	12.0 "	120.7		10	12.07		2 00		14 07	
Between Stake No. 10.	4.2 "	4.0 "	12.4 "	123.1		10	12.31		2 00		14 31	
and Stake No. 11.	4.1 "	4.0 "	12.2 "	125.2		10	12.52		2 00		14 52	
Between Stake No. 12.	3.7 "	4.0 "	11.4 "	114.2		10	11.41		2 00		13 42	
and Stake No. 13.	3.8 "	4.0 "	11.6 "	89.1		10	8.91		2 00		10 91	
Between Stake No. 14.	4.0 "	4.0 "	12.0 "	114.1		10	11.41		2 00		13 41	
and Stake No. 15.	4.1 "	4.0 "	12.2 "	120.1		10	12.01		2 00		14 01	
Between Stake No. 16.	4.0 "	4.0 "	12.0 "	120.1		10	12.01		2 00		14 01	
and Stake No. 17.	5.0 "	4.0 "	14.0 "	142.6		10	14.26		2 00		16 26	
Between Stake No. 18.	4.7 "	4.0 "	13.4 "	159.0		10	15.90		2 00		17 90	
and Stake No. 19.	5.1 "	4.0 "	14.2 "	161.5		10	16.15		2 00		18 15	

2,441.0

\$ 244.10

\$ 38.00

\$ 282.10

*Total Estimated Cost of Whole Work*

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in branch No. 5 Ditch No. 53.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yar		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		(7) Total Estimated Cost per Section	
					\$	CTS.			\$	CTS.
<i>Between Stake No. 20.</i>	5.2 ft.	4.0 ft.	14.4 ft.	174.5		10	\$ 17.45		2 00	\$ 19 45
<i>and Stake No. 21.</i>	5.5 "	4.0 "	15.0 "	185.3		10	18.53		2 00	20 53
<i>Between Stake No. 22.</i>	5.6 "	4.0 "	15.2 "	196.3		10	19.63		2 00	21.63
<i>and Stake No. 23.</i>	5.3 "	4.0 "	14.6 "	190.8		10	19.08		2 00	21 08
<i>Between Stake No. 24.</i>	5.3 "	4.0 "	14.6 "	182.6		10	18.26		2 00	20 26
<i>and Stake No. 25.</i>	4.2 "	4.0 "	12.4 "	155.1		10	15.51		2 00	17 51
<i>Between Stake No. 26.</i>	4.3 "	4.0 "	12.6 "	129.8		10	12.98		2 00	17 98
<i>and Stake No. 27.</i>	4.1 "	4.0 "	12.2 "	127.5		10	12.75		2 00	14 75
<i>Between Stake No. 28.</i>	4.8 "	4.0 "	13.6 "	139.7		10	13.97		2 00	15 97
<i>and Stake No. 29.</i>	5.3 "	4.0 "	14.6 "	169.1		10	16.91		2 00	18 91
<i>Between Stake No. 30.</i>	5.4 "	4.0 "	14.8 "	180.0		10	18.00		2 00	20 00
<i>and Stake No. 31.</i>	5.7 "	4.0 "	15.4 "	196.4		10	19.64		2 00	21 64
<i>Between Stake No. 32.</i>	5.7 "	4.0 "	15.4 "	204.8		10	20.48		2 00	22 48
<i>and Stake No. 33.</i>	5.7 "	4.0 "	15.4 "	204.8		10	20.48		2 00	22 48
<i>Between Stake No. 34.</i>	5.6 "	4.0 "	14.6 "	184.4		10	18.44		2 00	20 44
<i>and Stake No. 35.</i>	5.3 "	4.0 "	15.2 "	190.8		10	19.08		2 00	21 08
<i>Between Stake No. 36.</i>	5.2 "	4.0 "	14.4 "	188.1		10	18.81		2 00	20 81
<i>and Stake No. 37.</i>	5.4 "	4.0 "	14.8 "	182.6		10	18.26		2 00	20 26
<i>Between Stake No. 38.</i>	5.8 "	4.0 "	15.6 "	199.2		10	19.92		2 00	21 92
<i>and Stake No. 39.</i>	6.6 "	4.0 "	17.2 "	234.8		10	23.48		2 00	25 48
				3,616.6			\$ 361.66		\$ 40.00	\$ 401.66

*Total Estimated Cost of Whole Work* .....

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Branch No. 5 Ditch No. 53.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 40.	6.8 ft.	4.0 ft.	17.6 ft.	265.5		10	\$ 26.55		2 00	\$ 28 55
and Stake No. 41.	7.1	4.0 "	18.2 "	282.0		10	28.20		2 00	30 20
Between Stake No. 42.	8.0 "	4.0 "	20.0 "	323.7		10	32.37		2 00	34 37
and Stake No. 43.	7.3 "	4.0 "	18.6 "	330.5		10	33.05		2 00	35 05
Between Stake No. 44.	6.9 "	4.0 "	17.8 "	292.0		10	29.20		2 00	31 20
and Stake No. 45.	7.0 "	4.0 "	18.0 "	281.9 "		10	28.19		2 00	30 19
Between Stake No. 46.	7.0 "	4.0 "	18.0 "	285.2		10	28.52		2 00	30 52
and Stake No. 47.	7.3 "	4.0 "	18.6 "	295.3		10	29.53		2 00	31 53
Between Stake No. 48.	7.3 "	4.0 "	18.6 "	305.5		10	30.55		2 00	32 55
and Stake No. 49.	7.4 "	4.0 "	18.8 "	309.0		10	30.90		2 00	32 90
Between Stake No. 50.	7.4 "	4.0 "	18.8 "	312.4		10	31.24		2 00	33 24
and Stake No. 51.	7.0 "	4.0 "	18.0 "	298.8		10	29.88		2 00	31 88
Between Stake No. 52.	7.0 "	4.0 "	18.0 "	285.2		10	28.52		2 00	30 52
and Stake No. 53.	7.3 "	4.0 "	18.6 "	295.3		10	29.53		2 00	31 53
Between Stake No. 54.	7.3 "	4.0 "	18.6 "	302.1		10	30.21		2 00	32 21
and Stake No. 55.	8.3 "	4.0 "	20.6 "	336.5		10	33.65		2 00	35 65
Between Stake No. 56.	8.0 "	4.0 "	20.0 "	366.8		10	36.68		2 00	38 68
and Stake No. 57.	7.8 "	4.0 "	19.6 "	348.2		10	34.82		2 00	36 82
Between Stake No. 58.	7.9 "	4.0 "	19.8 "	344.5		10	34.45		2 00	36 45
and Stake No. 59.	8.1 "	4.0 "	20.2 "	355.6		10	35.56		2 00	37 56
				6,216.0			\$ 621.60		\$ 40.00	\$ 661.60

Total Estimated Cost of Whole Work

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Lateral to Branch No. 5 enters on the South at 18 + 33 Ditch No. \_\_\_\_\_

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yar		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.		
<i>Between Stake No. 0.</i>	5.0 ft.	4.0 ft.	14.0 ft.									
<i>and Stake No. 1.</i>	5.8 "	4.0 "	15.6 "	177.3		10	\$ 17.73		2 00		\$ 19.73	
<i>Between Stake No. 2.</i>	4.7 "	4.0 "	13.4 "	169.7		10	16.97		2 00		18.97	
<i>and Stake No. 3.</i>	4.7 "	4.0 "	13.4 "	125.7		10	12.57		2 00		14.57	
<i>Between Stake No. 4.</i>	4.7 "	4.0 "	13.4 "	125.7		10	12.57		2 00		14.57	
<i>and Stake No. 5.</i>	4.7 "	4.0 "	13.4 "	125.7		10	12.57		2 00		14.57	
<i>Between Stake No. 6.</i>	4.5 "	4.0 "	13.0 "	146.3		10	14.63		2 00		16.63	
<i>and Stake No. 7.</i>	4.8 "	4.0 "	12.6 "	136.8		10	13.68		2 00		15.68	
<i>Between Stake No. 8.</i>	4.3 "	4.0 "	12.6 "	132.1		10	13.21		2 00		15.21	
<i>and Stake No. 9.</i>	4.5 "	4.0 "	13.0 "	136.8		10	13.68		2 00		15.68	
<i>Between Stake No. 10.</i>	5.4 "	4.0 "	14.8 "	164.8		10	16.48		2 00		18.48	
<i>and Stake No. 11.</i>	4.3 "	4.0 "	12.6 "	160.1		10	16.01		2 00		18.01	
<i>Between Stake No. 12.</i>	4.1 "	4.0 "	12.2 "	127.5		10	12.75		2 00		14.75	
<i>and Stake No. 13.</i>	4.5 "	4.0 "	13.0 "	132.3		10	13.23		2 00		15.23	
<i>Between Stake No. 14.</i>	4.6 "	4.0 "	13.2 "	134.1		10	13.41		2 00		15.41	
<i>and Stake No. 15.</i>	4.8 "	4.0 "	13.6 "	160.0		10	16.00		2 00		19.00	
<i>Between Stake No. 16.</i>	5.3 "	4.0 "	14.6 "	169.5		10	16.95		2 00		18.95	
<i>and Stake No.</i>				2,324.4			\$ 232.44		\$ 32.00		\$ 264.44	
<i>Between Stake No.</i>												
<i>and Stake No.</i>												

*Total Estimated Cost of Whole Work* .....

Lateral # 1 of Branch # 5 of Main Ditch # 53

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Page 1

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Lateral to Br. No. 5 enters at Sta. 17+65 of Br. 5 Ditch No. \_\_\_\_\_

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 0.	4.9 ft.	4.0 ft.	13.8 ft.							
and Stake No. 1.	4.8 "	4.0 "	13.6 "	158.6	10	\$ 15.86		2 00	\$ 17 86	
Between Stake No. 2.	4.5 "	4.0 "	13.0 "	149.1	10	14.91		2 00	16 91	
and Stake No. 3.	4.4 "	4.0 "	12.8 "	139.3	10	13.93		2 00	15 93	
Between Stake No. 4.	4.4 "	4.0 "	12.8 "	133.5	10	13.35		2 00	15 35	
and Stake No. 5.	5.1 "	4.0 "	14.2 "	154.4 <del>155.4</del>	10	15.44		2 00	17 44	
Between Stake No. 6.	4.7 "	4.0 "	13.4 "	161.6	10	16.16		2 00	18 16	
and Stake No. 7.	4.1 "	4.0 "	12.2 "	235.3	10	13.53		2 00	15 53	
Between Stake No. 8.	5.1 "	4.0 "	14.2 "	147.4	10	14.74		2 00	16 74	
and Stake No. 9.	5.1 "	4.0 "	14.2 "	171.9	10	17.19		2 00	19 19	
Between Stake No. 10	5.1 "	4.0 "	14.2 "	171.9	10	17.19		2 00	19 19	
and Stake No. 11.	4.9 "	4.0 "	13.8 "	166.7	10	16.67		2 00	18 67	
Between Stake No. 12.	5.4 "	4.0 "	14.8 "	174.8	10	17.48		2 00	19 48	
and Stake No. 13.	5.9 "	4.0 "	15.8 "	202.1	10	20.21		2 00	22 21	
Between Stake No. 14.	6.2 "	4.0 "	16.4 "	225.3	10	22.53		2 00	24 53	
and Stake No. 15.	7.4 "	4.0 "	18.8 "	273.3	10	27.33		2 00	29 33	
Between Stake No. 16.	4.9 "	4.0 "	13.8 "	237.0	10	23.70		2 00	25 70	
and Stake No. 17.	4.7 "	4.0 "	13.4 "	156.4	10	15.64		2 00	17 64	
Between Stake No. 18.	4.9 "	4.0 "	13.8 "	156.4	10	15.64		2 00	17 64	
and Stake No.				3,115.0		\$ 311.50		\$ 36.00	\$ 347.50	

Total Estimated Cost of Whole Work \_\_\_\_\_

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Lateral to Branch No. 5 enters at Sta. 17 + 65 Br. 5 Ditch No.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 19.	4.9 ft.	4.0 ft.	13.8 ft.	161.5	10		\$ 16.15		2 00	18 15
and Stake No. 20.	5.5 "	4.0 "	15.0 "	177.5	10		17.75		2 00	19 75
Between Stake No. 21.	5.3 "	4.0 "	14.6 "	188.0	10		18.80		2 00	20 80
and Stake No. 22.	5.0 ft.	4.0 "	14.0	99.5	10		9.95		1 00	10 95
Between Stake No. and Stake No.				626.5			\$ 62.65		\$ 7 00	\$ 69 65
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										
Between Stake No. and Stake No.										

Total Estimated Cost of Whole Work