

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Page: 4.

Devine Lateral

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Ditch No. 53.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yard		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 0.	5.6 ft.	4.0 ft.	15.2 ft.					2 00		
and Stake No. 1.	5.9 "	4.0 "	15.8 "	207.7		10	\$ 20.77			\$ 22 77
Between Stake No. 2.	5.4 "	4.0 "	14.8 "	202.1		10	20.21	2 00		22 21
and Stake No. 3.	5.3 "	4.0 "	14.7 "	185.3		10	18.53	2 00		20 53
Between Stake No. 4.	5.4 "	4.0 "	14.8 "	185.3		10	18.53	2 00		20 53
and Stake No. 5.	5.9 "	4.0 "	15.8 "	202.1		10	20.21	2 00		22 21
Between Stake No. 6.	6.7 "	4.0 "	17.4 "	240.9		10	24.09	2 00		26 09
and Stake No. 7.	6.7 "	4.0 "	17.4 "	265.5		10	26.55	2 00		28 55
Between Stake No. 8.	5.9 "	4.0 "	15.8 "	240.9		10	24.09	2 00		26 09
and Stake No. 9.	6.1 "	4.0 "	16.2 "	222.2		10	22.22	2 00		24 22
Between Stake No. 10.	6.1 "	4.0 "	16.2 "	228.2		10	22.82	2 00		24 82
and Stake No. 11.	6.0 "	4.0 "	16.0 "	225.2		10	22.52	2 00		24 52
Between Stake No. 12.	6.0 "	4.0 "	16.0 "	222.2		10	22.22	2 00		24 22
and Stake No. 13.	6.0 "	4.0 "	16.0 "	222.2		10	22.22	2 00		24 22
Between Stake No. 14.	6.2 "	4.0 "	16.4 "	228.2		10	22.82	2 00		24 82
and Stake No. 15.	5.7 "	4.0 "	15.4 "	213.9		10	21.39	2 00		23 39
Between Stake No. 16.	5.8 "	4.0 "	15.6 "	202.1		10	20.21	2 00		22 21
and Stake No. 17.	5.8 "	4.0 "	15.6 "	210.5		10	21.05	2 00		23 05
Between Stake No. 18.	6.1 "	4.0 "	16.2 "	219.3		10	21.93	2 00		23 93
and Stake No. 19.	6.8 "	4.0 "	17.6 "	250.1		10	25.01	2 00		27 01
				4,173.9			\$ 417.9	\$ 38.00		\$ 455.39

Total Estimated Cost of Whole Work.....

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Devine Lateral. Ditch No. 53.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yar		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.		
											\$	CTS.
<i>Between Stake No. 20.</i>	6.1 ft.	4.0 ft.	16.2 ft.	250.1		10	\$ 25.01		2.00		27	01
<i>and Stake No. 21.</i>	7.4 "	4.0 "	18.8 "	270.8		10	27.03		2 00		29	03
<i>Between Stake No. 22.</i>	7.1 "	4.0 "	18.2 "	302.1		10	30.21		2 00		32	21
<i>and Stake No. 23.</i>	7.0 "	4.0 "	18.0 "	288.5		10	28.85		2 00		30	85
<i>Between Stake No. 24.</i>	7.7 "	4.0 "	19.4 "	309.2		10	30.92		2 00		32	92
<i>and Stake No. 25.</i>	7.9 "	4.0 "	19.8 "	341.0		10	34.10		2 00		36	10
<i>Between Stake No. 26.</i>	7.6 "	4.0 "	19.2 "	338.4		10	33.84		2 00		35	84
<i>and Stake No. 27.</i>	7.2 "	4.0 "	18.4 "	313.7		10	31.37		2 00		33	37
<i>Between Stake No. 28.</i>	7.3 "	4.0 "	18.6 "	302.1		10	30.21		2 00		32	21
<i>and Stake No. 29.</i>	8.0 "	4.0 "	20.0 "	330.5		10	33.05		2 00		35	05
<i>Between Stake No. 30.</i>	9.5 "	4.0 "	23.0 "	415.2		10	41.52		2 00		43	52
<i>and Stake No. 31.</i>	9.4 "	4.0 "	22.8 "	470.7		10	47.07		2 00		49	07
<i>Between Stake No. 32.</i>	7.6 "	4.0 "	19.2 "	396.5		10	39.65		2 00		41	65
<i>and Stake No. 33.</i>	7.6 "	4.0 "	19.2 "	326.5		10	32.65		2 00		34	65
<i>Between Stake No. 34.</i>	7.9 "	4.0 "	19.8 "	337.3		10	33.73		2 00		35	73
<i>and Stake No. 46</i>	8.0 "	4.0 "	20.0 "	161.9		10	16.19		1 00		17	19
<i>Between Stake No.</i>				5,154.0			\$ 515.40		\$ 31 00		\$ 546.40	
<i>and Stake No.</i>											546.40	
<i>Between Stake No.</i>												
<i>and Stake No.</i>												

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Peeble's Lateral to Branch No. 2. Ditch No. 11-53-11

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
<i>Between Stake No. 0.</i>	5.1 ft.	4.0 ft.	14.2 ft.							
<i>and Stake No. 1.</i>	6.1 "	4.0 "	16.2 "	200.00		10	\$ 20.00		2 00	\$ 22 00
<i>Between Stake No. 2.</i>	7.0 "	4.0 "	18.0 "	156.6		10	25.66		2 00	27.66
<i>and Stake No. 3.</i>	7.0 "	4.0 "	18.0 "	244.4		10	24.44		2 00	26.44
<i>Between Stake No. 4.</i>	6.0 "	4.0 "	16.0 "	253.7		10	25.37		2 00	27.37
<i>and Stake No. 5.</i>	5.9 "	4.0 "	15.8 "	219.4		10	21.94		2 00	23.94
<i>Between Stake No. 6.</i>	6.3 "	4.0 "	16.6 "	228.3		10	22.83		2 00	24.83
<i>and Stake No. 7.</i>	6.2 "	4.0 "	16.4 "	237.3		10	23.73		2 00	25.73
<i>Between Stake No. 8.</i>	6.4 "	4.0 "	16.8 "	340.3		10	24.03		2 00	26.03
<i>and Stake No. 9.</i>	6.5 "	4.0 "	17.0 "	249.7		10	24.97		2 00	26.97
<i>Between Stake No. 10.</i>	5.3 "	4.0 "	14.6 "	217.7		10	21.77		2 00	23.77
<i>and Stake No. 11.</i>	6.1 "	4.0 "	16.2 "	205.4		10	20.54		2 00	22.54
<i>Between Stake No. 12.</i>	6.4 "	4.0 "	16.8 "	237.3		10	23.73		2 00	25.73
<i>and Stake No. 13.</i>	6.5 "	4.0 "	17.0 "	249.7		10	24.97		2 00	26.97
<i>Between Stake No. 14.</i>	7.7 "	4.0 "	19.4 "	293.2		10	29.82		2 00	31.82
<i>and Stake No. 15.</i>	6.5 "	4.0 "	17.0 "	293.2		10	29.82		2 00	31.82
<i>Between Stake No. 16.</i>	7.0 "	4.0 "	18.0 "	257.9		10	25.79		2 00	27.79
<i>and Stake No. 17.</i>	7.5 "	4.0 "	19.0 "	302.3		10	30.23		2 00	32.23
<i>Between Stake No. 18.</i>	8.2 "	4.0 "	20.4 "	344.9		10	34.49		2 00	36.49
<i>and Stake No. 19.</i>	9.4 "	4.0 "	22.8 "	418.5		10	41.85		2 00	43.85
				4,929.8			\$ 492.98		\$ 38.00	\$ 530.98

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Beebles Lateral to Branch No. 2 Ditch No. 53

SECTION	(1)	(2)	(3)	(4)	(5)		(6)				(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				Total Estimated Cost per Section	
					\$	CTS.					\$	CTS.
<i>Between Stake No. 20.</i>	8.7 ft.	4.0 ft.	21.4 ft.	437.9	10	\$ 43.79					2 00	45 79
<i>and Stake No. 21.</i>	7.1 "	4.0 "	18.2 "	350.6	10	35.06					2 00	37 06
<i>Between Stake No. 22.</i>	7.9 "	4.0 "	17.8 "	285.2	10	28.52					2 00	30 52
<i>and Stake No. 23.</i>	7.2 "	4.0 "	18.4 "	288.6	10	28.86					2 00	30 86
<i>Between Stake No. 24.</i>	7.4 "	4.0 "	18.8 "	308.5	10	30.55					2 00	32 55
<i>and Stake No. 25.</i>	8.1 "	4.0 "	20.2 "	337.7	10	33.77					2 00	35 77
<i>Between Stake No. 26.</i>	7.8 "	4.0 "	19.6 "	352.0	10	35.20					2 00	37 20
<i>and Stake No. 27.</i>	8.0 "	4.0 "	20.0 "	348.2	10	34.82					2 00	36 82
<i>Between Stake No. 28.</i>	8.0 "	4.0 "	20.0 "	355.5	10	35.55					2 00	37 55
<i>and Stake No. 29.</i>	7.5 "	4.0 "	19.0 "	377.7	10	37.77					2 00	39 77
<i>Between Stake No. + 11</i>	7.7 "	4.0 "	19.4 "	40.0	10	4.00						4 00
<i>and Stake No.</i>				3,478.9		\$ 347.89					20 00	\$ 367 89
<i>Between Stake No.</i>												
<i>and Stake No.</i>												
<i>Between Stake No.</i>												
<i>and Stake No.</i>												
<i>Between Stake No.</i>												
<i>and Stake No.</i>												
<i>Between Stake No.</i>												
<i>and Stake No.</i>												

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Branch No. 3, Ditch No. 53

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 0.	6.8 ft.	4.0 ft.	10.6 ft.							
and Stake No. 1.	6.9 "	4.0 "	17.9 "	273.5	10	\$ 27.53		2 00	\$ 29.53	
Between Stake No. 2.	6.0 "	4.0 "	16.0 "	250.5	10	25.05		2 00	27 05	
and Stake No. 3.	6.3 "	4.0 "	16.6 "	231.1	10	23.11		2 00	25 11	
Between Stake No. 4.	6.1 "	4.0 "	16.2 "	234.2	10	23.42		2 00	25 42	
and Stake No. 5.	6.3 "	4.0 "	16.6 "	234.2	10	23.42		2 00	25 42	
Between Stake No. 6.	6.1 "	4.0 "	16.2 "	234.2	10	23.42		2 00	25 42	
and Stake No. 7.	6.1 "	4.0 "	16.2 "	228.2	10	22.82		2 00	24 82	
Between Stake No. 8.	6.4 "	4.0 "	16.8 "	237.3	10	23.73		2 00	25 73	
and Stake No. 9.	6.2 "	4.0 "	16.4 "	240.4	10	24.04		2 00	26 04	
Between Stake No. 10.	6.2 "	4.0 "	16.4 "	234.2	10	23.42		2 00	25 42	
and Stake No. 11.	6.3 "	4.0 "	16.6 "	237.2	10	23.72		2 00	25 72	
Between Stake No. 12.	7.4 "	4.0 "	18.8 "	276.4	10	27.64		2 00	29 64	
and Stake No. 13.	7.7 "	4.0 "	19.4 "	323.0	10	32.30		2 00	34 30	
Between Stake No. 14.	7.4 "	4.0 "	18.8 "	323.0	10	32.30		2 00	34 30	
and Stake No. 15.	7.7 "	4.0 "	19.4 "	323.0	10	32.30		2 00	34 30	
Between Stake No. 16.	7.5 "	4.0 "	19.0 "	326.5	10	32.65		2 00	34 65	
and Stake No. 17.	7.2 "	4.0 "	18.4 "	309.1	10	30.91		2 00	32 91	
Between Stake No. 18.	7.4 "	4.0 "	18.8 "	305.5	10	30.55		2 00	32 55	
and Stake No. 19.	7.6 "	4.0 "	19.6 "	326.6	10	32.66		2 00	34 66	
				5,149.9		\$ 514.99		+ 38.00	\$ 552.99	

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in Branch No. 3 Ditch No. 53.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 20.	7.6 ft.	4.0 ft.	19.2 ft.	334.8		10	\$ 33.48		2 00	\$ 35 48
and Stake No. 21.	7.7 "	4.0 "	19.4 "	331.2		10	33.12		2 00	35 12
Between Stake No. 22.	5.8 "	4.0 "	15.6 "	272.1		10	27.21		2 00	29 21
and Stake No. 23.	5.4 "	4.0 "	14.8 "	199.2		10	19.92		2 00	21 92
Between Stake No. 24.	5.7 "	4.0 "	15.4 "	190.8		10	19.08		2 00	21 08
and Stake No. 25.	5.2 "	4.0 "	14.4 "	185.4		10	18.54		2 00	20 54
Between Stake No. 26 +36	5.1 "	4.0 "	14.2 "	62.8		10	6.28		1 00	7 28
and Stake No.				1,576.3			\$ 157.63		\$ 13 00	\$ 170 63
Between Stake No.										
and Stake No.										
Between Stake No.										
and Stake No.										
Between Stake No.										
and Stake No.										
Between Stake No.										
and Stake No.										
Between Stake No.										
and Stake No.										

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in The Lateral that enters Main Ditch at 32+80 Ditch No.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
<i>Between Stake No. 0.</i>	5.1 ft.	4.0 ft.	14.2 ft.							
<i>and Stake No. 1.</i>	5.2 "	4.0 "	14.4 "	174.5	10	\$ 17.45		00	\$ 19	45
<i>Between Stake No. 2.</i>	5.5 "	4.0 "	15.0 "	185.3	10	18.53		00	20	53
<i>and Stake No. 3.</i>	5.7 "	4.0 "	15.4 "	199.1	10	19.91		00	21	91
<i>Between Stake No. 4.</i>	5.7 "	4.0 "	15.4 "	204.8	10	20.48		00	22	48
<i>and Stake No. 5.</i>	6.1 "	4.0 "	16.2 "	216.4	10	21.64		00	23	64
<i>Between Stake No. 6.</i>	6.6 "	4.0 "	17.2 "	243.6	10	24.36		00	26	36
<i>and Stake No. 7.</i>	7.2 "	4.0 "	18.4 "	279.0	10	27.90		00	29	90
<i>Between Stake No. 8.</i>	6.6 "	4.0 "	17.2 "	279.0	10	27.90		00	29	90
<i>and Stake No. 9.</i>	6.4 "	4.0 "	16.8 "	252.8	10	25.28		00	27	28
<i>Between Stake No. 10.</i>	7.2 "	4.0 "	18.4 "	272.6	10	27.26		00	29	26
<i>and Stake No. 11.</i>	7.8 "	4.0 "	19.6 "	319.8	10	31.98		00	33	98
<i>Between Stake No. 12.</i>	8.2 "	4.0 "	20.4 "	355.8	10	35.58		00	37	58
<i>and Stake No. 13.</i>	8.1 "	4.0 "	20.2 "	366.7	10	36.67		00	38	67
<i>Between Stake No. 79</i>	8.1 "	4.0 "	20.2 "	286.7	10	28.67		00	30	67
<i>and Stake No.</i>				3,636.1		\$ 363.61		00	\$ 391.61	
<i>Between Stake No.</i>										
<i>and Stake No.</i>										
<i>Between Stake No.</i>										
<i>and Stake No.</i>										

Total Estimated Cost of Whole Work