

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Sheet No. 1.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in MAIN Ditch No. 53.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yar		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
							Excavation.			
Between Stake No. 0.	8.1 Ft.	8.0 Ft.	32.3Ft.							
and Stake No. 1.	8.2 "	8.0 "	32.6"	603.9		12	\$ 72.48		2 00	7448
Between Stake No. 2.	8.3 "	8.0 "	32.90"	628.1		12	75.36		2 00	7736
and Stake No. 3.	8.0 "	8.0 "	32.0 "	615.9		12	73.92		2 00	7592
Between Stake No. 4.	8.3 "	8.0 "	32.90"	615.9		12	73.92		2 00	7592
and Stake No. 5.	7.5 "	8.0 "	31.0 "	580.2		12	69.60		2 00	7160
Between Stake No. 6.	7.3 "	8.0 "	29.95"	523.1		12	62.76		2 00	6476
and Stake No. 7.	6.8 "	8.0 "	28.4 "	489.9		12	58.80		2 00	6080
Between Stake No. 8.	6.9 "	8.0 "	28.7 "	467.4		12	56.04		2 00	5804
and Stake No. 9.	7.2 "	8.0 "	29.6 "	489.8		12	58.80		2 00	6080
Between Stake No. 10.	7.0 "	8.0 "	29.0 "	489.8		12	58.80		2 00	6080
and Stake No. 11.	7.0 "	8.0 "	29.0 "	479.2		12	57.48		2 00	5948
Between Stake No. 12.	6.8 "	8.0 "	28.4 "	467.4		12	56.04		2 00	5804
and Stake No. 13.	7.1 "	8.0 "	29.30"	479.2		12	57.48		2 00	5948
Between Stake No. 14.	7.0 "	8.0 "	29.0 "	479.2		12	57.48		2 00	5948
and Stake No. 15.	6.9 "	8.0 "	28.7 "	467.4		12	56.04		2 00	5804
Between Stake No. 16.	6.9 "	8.0 "	28.7 "	467.4		12	56.04		2 00	5804
and Stake No. 17.	7.3 "	8.0 "	29.9 "	489.9		12	58.80		2 00	6080
Between Stake No. 18.	7.0 "	8.0 "	29.0 "	500.9		12	60.12		2 00	6212
and Stake No. 19.	7.2 "	8.0 "	29.6 "	489.9		12	58.80		2 00	6080

9824.5

1178.76

\$ 38.00

\$ 1216.76

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Sheet No. 2.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in M A I N Ditch No. 53 .

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				(7) Total Estimated Cost per Section		
					\$	CTS.		\$	CTS.	\$	CTS.		
<i>Between Stake No. 19.</i>	7.2 ft.	8.0 ft.	29.6 ft.				Excavation						
<i> and Stake No. 20.</i>	8.1 "	8.0 "	32.3 "	556.9		12	\$	66.83		2	00	66	83
<i>Between Stake No. 21.</i>	9.3 "	8.0 "	35.9 "	677.6		12		81.36		2	00	83	76
<i> and Stake No. 22.</i>	8.4 "	8.0 "	33.2 "	703.0		12		84.36		2	00	86	36
<i>Between Stake No. 23.</i>	8.3 "	8.0 "	32.9 "	640.3		12		76.80		2	00	78	80
<i> and Stake No. 24.</i>	8.2 "	8.0 "	32.6 "	628.1		12		75.36		2	00	77	36
<i>Between Stake No. 25.</i>	8.6 "	8.0 "	33.8 "	640.3		12		76.80		2	00	78	80
<i> and Stake No. 26.</i>	9.4 "	8.0 "	36.2 "	716.5		12		85.92		2	00	87	92
<i>Between Stake No. 28.</i>	8.7 "	8.0 "	34.1 "	728.9		12		87.48		2	00	89	48
<i> and Stake No. 28.n</i>	8.7 "	8.0 "	34.1 "	677.6		12		81.36		2	00	83	36
<i>Between Stake No. 29</i>	8.5 "	8.0 "	33.5 "	665.0		12		79.80		2	00	81	80
<i> and Stake No. 30</i>	8.5 "	8.0 "	33.5 "	652.6		12		78.24		2	00	80	24
<i>Between Stake No. 31</i>	8.1 "	8.0 "	32.3 "	628.1		12		75.36		2	00	77	36
<i> and Stake No. 32</i>	8.2 "	8.0 "	32.6 "	603.9		12		72.48		2	00	74	48
<i>Between Stake No. 33.</i>	8.2 "	8.0 "	32.6 "	615.9		12		73.92		2	00	75	92
<i> and Stake No. 34.</i>	8.3 "	8.0 "	32.9 "	628.1		12		75.36		2	00	77	36
<i>Between Stake No. 35.</i>	8.7 "	8.0 "	34.1 "	652.7		12		78.24		2	00	80	24
<i> and Stake No. 36.</i>	8.4 "	8.0 "	33.2 "	652.7		12		78.24		2	00	80	24
<i>Between Stake No. 37.</i>	8.6 "	8.0 "	33.8 "	652.7		12		78.24		2	00	80	24
<i> and Stake No. 38.</i>	9.1 "	8.0 "	35.30"	703.0		12		84.36		2	00	86	36

~~\$1242.50~~
12423.9

\$1490.51 \$38.00 \$1530.51
Total Estimated Cost of Whole Work \$1528.51

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Sheet No. 3.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in MAIN Ditch No. 53.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)		
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section		
					\$	CTS.		\$	CTS.	\$	CTS.
							Excavation.				
Between Stake No. 39	8.5 ft.	8.0 ft.	33.5 ft.	690.3		12	\$ 82.80	2	00	\$ 84	80
and Stake No. 40.	8.3 "	8.0 "	32.9 "	640.3		12	\$ 76.80	2	00	78	80
Between Stake No. 41.	7.9 "	8.0 "	31.7 "	603.9		12	72.48	2	00	74	48
and Stake No. 42.	8.2 "	8.0 "	32.6 "	603.9		12	72.48	2	00	74	48
Between Stake No. 43.	9.0 "	8.0 "	35.0 "	665.0		12	79.80	2	00	81	80
and Stake No. 44.	9.7 "	8.0 "	37.10 "	755.3		12	90.60	2	00	92	60
Between Stake No. 45.	8.7 "	8.0 "	34.1 "	742.1		12	89.04	2	00	91	04
and Stake No. 46.	8.3 "	8.0 "	32.9 "	652.6		12	78.36	2	00	80	36
Between Stake No. 47.	8.5 "	8.0 "	33.5 "	640.3		12	76.80	2	00	78	80
and Stake No. 48.	8.9 "	8.0 "	34.7 "	677.6		12	81.36	2	00	83	36
Between Stake No. 49.	9.6 "	8.0 "	36.8 "	755.3		12	90.60	2	00	92	60
and Stake No. 50.	8.8 "	8.0 "	34.4 "	742.1		12	89.04	2	00	91	04
Between Stake No. 51.	7.9 "	8.0 "	31.7 "	523.1		12	62.76	2	00	64	76
and Stake No. 52.	7.9 "	8.0 "	31.7 "	580.2		12	69.60	2	00	71	60
Between Stake No. 53.	8.2 "	8.0 "	32.6 "	592.0		12	71.04	2	00	73	04
and Stake No. 54.	8.3 "	8.0 "	32.9 "	628.1		12	75.36	2	00	77	36
Between Stake No. 55	8.4 "	8.0 "	33.2	628.1		12	75.36	2	00	77	36
and Stake No. 56	8.3 "	8.0 "	32.9	640.3		12	76.80	2	00	78	80
Between Stake No. 57	8.4 "	8.0 "	33.2	628.1		12	75.36	2	00	77	36
and Stake No. 78	8.4 "	8.0 "	33.2	640.3		12	76.80	2	00	78	80

~~\$1302.90~~
13029.0

\$1563.18 \$40.00 \$1603.18

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Sheet No. 4.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in MAIN Ditch No. 53.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yar		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				(7) Total Estimated Cost per Section	
					\$	CTS.		\$	CTS.	\$	CTS.	
<i>Between Stake No. 59.</i>	8.4 ft.	8.0 ft.	33.2 ft.	640.3		12	\$	76.80	2	00	\$	78 80
<i>and Stake No. 60.</i>	8.6 "	8.0 "	33.8 "	652.6		12		78.36	2	00		80 36
<i>Between Stake No. 61.</i>	8.4 "	8.0 "	33.2 "	652.6		12		78.36	2	00		80 36
<i>and Stake No. 62.</i>	8.1 "	8.0 "	32.3 "	615.9		12		73.92	2	00		75 92
<i>Between Stake No. 63.</i>	8.1 "	8.0 "	32.3 "	603.9		12		72.36	2	00		74 36
<i>and Stake No. 64.</i>	8.8 "	8.0 "	31.4 "	592.0		12		71.04	2	00		73 04
<i>Between Stake No. 65.</i>	8.6 "	8.0 "	33.8 "	615.9		12		73.92	2	00		75 92
<i>and Stake No. 66.</i>	8.1 "	8.0 "	32.3 "	628.1		12		75.36	2	00		77 36
<i>Between Stake No. 67.</i>	8.3 "	8.0 "	32.9 "	615.9		12		73.92	2	00		75 92
<i>and Stake No. 68.</i>	8.4 "	8.0 "	33.2 "	640.3		12		76.80	2	00		78 80
<i>Between Stake No. 69.</i>	8.1 "	8.0 "	32.3 "	615.9		12		73.92	2	00		75 92
<i>and Stake No. 70.</i>	8.0 "	8.0 "	32.0 "	592.0		12		71.04	2	00		73 04
<i>Between Stake No. 71.</i>	8.2 "	8.0 "	32.6 "	603.9		12		72.36	2	00		74 36
<i>and Stake No. 72.</i>	9.3 "	8.0 "	35.90 "	677.6		12		81.36	2	00		83 36
<i>Between Stake No. 73.</i>	8.1 "	8.0 "	32.3 "	677.6		12		81.36	2	00		83 36
<i>and Stake No. 74.</i>	8.2 "	8.0 "	32.6 "	615.9		12		73.92	2	00		75 92
<i>Between Stake No. 75.</i>	9.5 "	8.0 "	36.50 "	703.0		12		84.36	2	00		86 36
<i>and Stake No. 76.</i>	8.6 "	8.0 "	33.8 "	728.9		12		87.48	2	00		89 48
<i>Between Stake No. 77.</i>	8.3 "	8.0 "	32.9 "	652.6		12		78.36	2	00		80 36
<i>and Stake No. 78.</i>	8.8 "	8.0 "	34.4 "	665.0		12		79.80	2	00		81 80
				<u>12789.9</u>								

\$1534.84

\$40.00

\$1574.84

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Sheet No. 5.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in M A I N Ditch No. 53 .

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yar		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				(7) Total Estimated Cost per Section			
					\$	CTS.					\$	CTS.		
								\$	CTS.	\$	CTS.	\$	CTS.	
<i>Between Stake No. 79.</i>	8.9 ft.	8.0 ft.	34.7 ft.	703.0		12	\$	84.36			2	00	86	36
<i>and Stake No. 80.</i>	8.9 "	8.0 "	34.7 "	703.0		12		84.36			2	00	86	36
<i>Between Stake No. 81.</i>	8.8 "	8.0 "	34.4 "	690.3		12		82.83			2	00	84	83
<i>and Stake No. 82.</i>	8.6 "	8.0 "	33.8 "	677.6		12		81.31			2	00	83	31
<i>Between Stake No. 83.</i>	8.7 "	8.0 "	34.1 "	677.6		12		81.31			2	00	83	31
<i>and Stake No. 84.</i>	8.6 "	8.0 "	33.8 "	666.0		12		79.81			2	00	81	81
<i>Between Stake No. 85.</i>	8.5 "	8.0 "	33.5 "	665.0		12		79.81			2	00	81	81
<i>and Stake No. 86.</i>	8.8 "	8.0 "	34.4 "	677.6		12		81.31			2	00	83	31
<i>Between Stake No. 87.</i>	8.6 "	8.0 "	33.8 "	677.6		12		81.31			2	00	83	31
<i>and Stake No. 88.</i>	8.8 "	8.0 "	34.4 "	677.6		12		81.31			2	00	83	31
<i>Between Stake No. 89.</i>	8.9 "	8.0 "	34.7 "	690.3		12		82.83			2	00	85	83
<i>and Stake No. 90.</i>	9.0 "	8.0 "	35.0 "	703.0		12		84.36			2	00	86	36
<i>Between Stake No. 91.</i>	8.0 "	8.0 "	35.0 "	716.5		12		85.98			2	00	87	98
<i>and Stake No. 92.</i>	8.9 "	8.0 "	34.7 "	703.0		12		84.36			2	00	86	36
<i>Between Stake No. 93.</i>	8.9 "	8.0 "	34.7 "	703.0		12		84.36			2	00	86	36
<i>and Stake No. 94.</i>	9.3 "	8.0 "	35.90 "	728.0		12		87.47			2	00	89	47
<i>Between Stake No. 95.</i>	10.3 "	8.0 "	38.9 "	822.3		12		98.68			2	00	100	68
<i>and Stake No. 96.</i>	11.9 "	8.0 "	43.7 "	1012.4		12		121.48			2	00	123	48
<i>Between Stake No. 97.</i>	9.5 "	8.0 "	36.50 "	952.1		12		114.25			2	00	116	25
<i>and Stake No. 98.</i>	9.3 "	8.0 "	35.90 "	768.5		12		92.22			2	00	94	22
				14614.3				\$1753.76			\$40.00		\$1793.71	

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in M. A. I. N. Ditch No. 53.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yar		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section		(7) Total Estimated Cost per Section			
					\$	CTS.	\$	CTS.	\$	CTS.		
Between Stake No. 99.	9.5 ft.	8.0 ft.	36.5 ft.	768.5		12	\$ 92.16		2	00	94	16
and Stake No. 100.	9.6 "	8.0 "	36.8 "	783.1		12	93.96		2	00	95	96
Between Stake No. 101.	9.6 "	8.0 "	36.8 "	795.7		12	95.40		2	00	97	40
and Stake No. 102.	9.2 "	8.0 "	35.6 "	768.5		12	92.16		2	00	94	16
Between Stake No. 103.	9.5 "	8.0 "	36.5 "	755.3		12	90.60 92.16		2	00	92	60
and Stake No. 104.	9.8 "	8.0 "	37.4 "	795.7		12	95.40		2	00	97	40
Between Stake No. 105.	9.2 "	8.0 "	35.6 "	783.1		12	93.96		2	00	95	96
and Stake No. 106.	8.9 "	8.0 "	34.7 "	728.9		12	87.48		2	00	89	48
Between Stake No. 107.	9.5 "	8.0 "	36.50 "	742.1		12	89.04		2	00	91	04
and Stake No. 108.	9.9 "	8.0 "	37.7 "	812.8		12	97.56		2	00	99	56
Between Stake No. 109.	9.8 "	8.0 "	37.40 "	822.3		12	98.64		2	00	100	64
and Stake No. 110.	10.4 "	8.0 "	39.20 "	865.0		12	103.80	Pipe. 24"	2	00	105	80
Between Stake No. 111.	9.1 "	6.0 "	6.0 "	215.5		12	25.86	\$ 100.00	2	00	127	86
and Stake No. 112.	9.1 "	6.0 "	6.0 "	201.1		12	24.13	100.00	2	00	126	13
Between Stake No. 113.	10.3 "	6.0 "	6.0 "	215.5:		12	25.86	100.00	2	00	127	86
and Stake No. 114.	9.8 "	6.0 "	6.0 "	221.1		12	26.53	100.00	2	00	128	53
Between Stake No. 115.	10.4 "	6.0 "	6.0 "	224.4		12	26.93	100.00	2	00	128	93
and Stake No. 116.	9.0 "	6.0 "	6.0 "	217.3		12	26.08	100.00	2	00	128	08
Between Stake No. 117.	9.3 "	6.0 "	6.0 "	203.3		12	24.40	100.00	2	00	126	40
and Stake No. 118.	8.7 "	6.0 "	6.0 "	200.0		12	24.00	100.00	2	00	126	00

11119.2

~~\$800.00~~
\$1333.30 \$800.00 \$40.00 \$2173.30
 Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Sheet No 7.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in MAIN Ditch No. 53.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)				(7)					
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yar		Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				Total Estimated Cost per Section					
					\$	CTS.					\$	CTS.				
							Pipe 24" Diamentor									
Between Stake No 119.	9.0 ft.	6.0 ft.	6.0 ft.	197.0		12	\$	23.64	\$	100.00		2	00	\$	125	64
and Stake No 120.	8.8 "	6.0 "	6.0 "	197.0		12		23.64		100.00		2	00		125	64
Between Stake No 121.	8.1 "	6.0 "	6.0 "	188.0		12		22.56		100.00		2	00		124	56
and Stake No 122.	8.0 "	6.0 "	6.0 "	178.0		12		21.36		100.00		2	00		123	36
Between Stake No 123.	9.4 "	6.0 "	6.0 "	193.0		12		23.16		100.00		2	00		125	16
and Stake No 124.	7.5 "	6.0 "	6.0 "	186.2		12		22.34		100.00		2	00		124	34
Between Stake No 125.	7.3 "	6.0 "	6.0 "	164.5		12		19.74		100.00		2	00		121	74
and Stake No 126.	4.4 "	6.0 "	6.0 "	132.1		12		15.73		100.00		2	00		117	73
Between Stake No 127.	7.4 "	6.0 "	6.0 "	135.1		12		16.21		100.00		2	00		118	21
and Stake No 128.	6.3 "	8.0 "	26.90 "	511.7		12		61.45				2	00		63	45
Between Stake No 129.	6.6 "	8.0 "	27.8 "	416.8		12		50.04				2	00		53	04
and Stake No 130.	6.5 "	8.0 "	27.50 "	425.9		12		51.12				2	00		53	12
Between Stake No 131.	6.5 "	8.0 "	27.50 "	425.9		12		51.12				2	00		53	12
and Stake No 132.	5.3 "	8.0 "	23.9 "	367.3		12		44.18				2	00		46	18
Between Stake No 133.	4.6 "	8.0 "	10.9 "	278.3		12		33.4				2	00		35	40
and Stake No 134.	5.4 "	8.0 "	24.20 "	286.7		12		34.40				2	00		36	40
Between Stake No 135.	5.7 "	8.0 "	25.10 "	329.7		12		39.46				2	00		41	46
and Stake No 136.	5.8 "	8.0 "	25.4 "	359.0		12		43.08				2	00		45	08
Between Stake No 137.	5.9 "	8.0 "	25.7 "	367.3		12		44.08				2	00		46	08
and Stake No 138.	5.9 "	8.0 "	25.7 "	367.3		12		44.08				2	00		46	08
				5705.8				\$684.69		\$900.00		\$40.00		\$1624.69		

Total Estimated Cost of Whole Work

EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.

Sheet No. 8.

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in MAIN, Ditch No. 53.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expenses of Inspecting Work until Completed With Total Per Section				(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No 139.	5.46 ft.	8.0 ft.	24.4 ft.	349.0	12	\$ 48.48			2 00		43 48	
and Stake No 140.	6.1 "	8.0 "	26.3 "	357.4	12	42.84			2 00		44 84	
Between Stake No 141.	6.5 "	8.0 "	27.5 "	406.7	12	48.80			2 00		50 80	
and Stake No 142	5.7 "	8.0 "	25.10 "	387.0	12	46.44			2 00		48 44	
Between Stake No 143.	5.6 "	8.0 "	25.4 "	349.0	12	41.88			2 00		43 88	
and Stake No 144.	6.7 "	8.0 "	28.10 "	387.0	12	46.44	Pipe 24" Dia.		2 00		48 44	
Between Stake No 145.	2.8 "	6.0 "	6.0 "	105.0	12	12.60	100.00		2 00		114 60	
and Stake No 146.	3.0 "	6.0 "	6.0 "	64.2	12	7.70	100.00		2 00		109 70	
Between Stake No 147.	3.4 "	6.0 "	6.0 "	71.2	12	8.56	100.00		2 00		110 56	
and Stake No 148.	2.7 "	6.0 "	6.0 "	68.0	12	8.16	100.00		2 00		110 16	
Between Stake No 149.	5.1 "	8.0 "	23.3 "	199.8	12	23.98			2 00		25 98	
and Stake No 150.	4.7 "	8.0 "	22.1 "	278.3	12	33.40			2 00		35 4	
Between Stake No 151.	4.4 "	8.0 "	21.2 "	245.3	12	29.43			2 00		31 43	
and Stake No 152.	5.1 "	8.0 "	23.3 "	270.0	12	32.40			2 00		34 40	
Between Stake No 153.	4.8 "	8.0 "	22.4 "	278.3	12	33.40			2 00		35 40	
and Stake No 154.	4.2 "	8.0 "	20.6 "	245.3	12	29.43			2 00		31 43	
Between Stake No 155.	3.5 "	8.0 "	18.5 "	200.0	12	24.0			2 00		26 00	
and Stake No 156.	4.1 "	8.0 "	20.3 "	200.0	12	24.0			2 00		26 00	
Between Stake No.				4461.5		\$535.38	\$400.00		36.00		\$971.38	
and Stake No.												

Total Estimated Cost of Whole Work

Tabulated Statement of MAIN Ditch No. 53. Count , Minn.

STATION NUMBER	Depth of Cut in Feet	WIDTH OF CUT IN FEET		Number of Cubic Yards Per Section	ESTIMATED COST		REMARKS
		At Base	At Top		Per Cubic Yd.	Per Section	
157.	3.1ft.	8.0	17.3	178.5 ft.	12	\$21.42	\$2.00 \$ 23.42
158.	2.9 "	8.0	16.7	139.8 "	12	16.78	2.00 18.78
159.	3.7 "	8.0	19.1	158.1 "	12	18.97	2.00 20.97
160.	0.0 "	8.0	8.0	92.9 :	12	11.15	2.00 13.15
				<u>569.3</u>		<u>\$68.32</u>	<u>8.00</u> <u>\$76.32</u>