

Tabulated Statement of Branch No. 6 Ditch No. 53. Count, Minn.

STATION NUMBER	Depth of Cut in Feet	WIDTH OF CUT IN FEET		Number of Cubic Yards Per Section	ESTIMATED COST		REMARKS	
		At Base	At Top		Per Cubic Yd.	Per Section		
0	6.3	4.0	16.6					
1	6.6	4.0	17.2	246.3	12	\$29.56	\$ 31.56	
2	6.4	4.0	16.8	255.5	12	30.30	32.30	
3.	6.5	4.0	17.0	252.5	12	30.30	32.30	
4.	6.5	4.0	17.0	252.5	12	30.30	32.30	
5.	6.7	4.0	17.4	258.9	12	31.07	33.07	
6.	7.0	4.0	18.0	27.83	12	33.39	35.39	
7.	7.1	4.0	18.2	284.9	12	34.18	36.18	
8.	7.0	4.0	18.0	291.6	12	34.99	36.99	
9.	6.8	4.0	17.6	278.3	12	33.40	35.40	
10.	7.1	4.0	18.2	284.9	12	34.18	36.18	
11.	7.9	4.0	19.8	319.1	12	38.29	40.29	
12.	8.0	4.0	20.0	355.1	12	42.61	44.61	
13.	8.7	4.0	21.4	377.3	12	45.28	47.28	
14.	8.6.	4.0	21.2	400.6	12	48.07	50.07	
15.	8.7	4.0	21.4	408.8	12	49.05	51.05	
16.	8.6	4.0	21.2	400.6	12	48.07	50.07	
17.	9.5	4.0	23.0	441.0	12	52.92	54.92	
18.	8.5	4.0	21.0	432.9	12	51.94	53.94	
19.	8.8	4.0	21.6	408.8	12	49.05	51.05	
20.	8.9	4.0	21.8	424.8	12	50.98	52.98	
21.	9.1	4.0	22.2	432.9	12	51.94	53.94	
22.	8.8	4.0	21.6	424.8	12	50.97	52.97	
23.	9.1	4.0	22.2	424.8	12	50.97	52.97	
24.	8.9	4.0	21.8	432.9	12	51.94	53.94	
25.	8.7	4.0	21.4	415.5	12	49.86	51.86	
26.	8.6	4.0	21.2	408.8	12	49.06	51.06	
26 x 11	8.6	4.0	21.2	54.9	12	6.59	8.59	
				<u>9244.3</u>		<u>\$1109.25</u>	<u>\$54.00</u>	<u>\$1163.25</u>