

Handwritten text at the top of the page, possibly a title or reference number, which is mostly illegible due to fading.

EXHIBIT 2.

---

# Engineer's Report

in

## Ditch Proceedings

---

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Ditch No. 56

SECTION	(1)	(2)	(3)	(4)	(5)	(6)	(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yard \$ CTS.		Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section	\$
Between Stake No. 0	3.7	3.0	10.4					
and Stake No. 0+5	4.8	"	12.6	1.5	75			75
Between Stake No. 0+14	5.5	"	14.0	14	210	24ft. of 30" Cor. Iron. pipe	4140	4350
and Stake No. 0+23	4.8	"	12.6	14	210			210
Between Stake No. 1	4.0	"	11.0	105	1575			1575
and Stake No. 2	3.8	"	10.6	100	1500			1500
Between Stake No. 3	3.7	"	10.4	92	1380			1380
and Stake No. 4	3.9	"	10.8	96	1440			1440
Between Stake No. 5	3.8	"	10.6	96	1440			1440
and Stake No. 6	3.8	"	10.6	96	1440			1440
Between Stake No. 7	3.8	"	10.6	96	1440			1440
and Stake No. 8	3.9	"	10.8	100	1500			1500
Between Stake No. 9	3.9	"	10.8	100	1500			1500
and Stake No. 10	4.1	"	11.2	104	1560			1560
Between Stake No. 11	4.2	"	11.4	108	1620			1620
and Stake No. 12	4.0	"	11.0	108	1620			1620
Between Stake No. 13	3.9	"	10.8	100	1500			1500
and Stake No. 14	3.8	"	10.6	96	1440			1440
Between Stake No. 15	4.3	"	11.6	104	1560	Clearing etc.	150	1710
and Stake No. 16	4.3	"	11.6	116	1740			150
				1.650	247.50		4440	\$291.90

Total Estimated Cost of Whole Work, \$.....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in..... Ditch No. 5-6

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) No. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section	(7) Total Estimated Cost per Section		
					\$	CTS.		\$	CTS.	
Between Stake No. 17	3.7	3.0	10.4	104	15	60	Clearing etc.	15	10	
and Stake No. 18	3.9	"	10.8	96	14	40		"	15	90
Between Stake No. 19	3.9	"	10.8	100	15	00	"	15	50	
and Stake No. 20	3.8	"	10.6	96	14	40	"	15	90	
Between Stake No. 21	3.8	"	10.6	96	14	40	"	15	90	
and Stake No. 22	3.7	"	10.4	92	13	80	"	15	30	
Between Stake No. 23	3.7	"	10.4	92	13	80	"	15	30	
and Stake No. 24	3.6	"	10.2	88	13	20	"	15	70	
Between Stake No. 25	3.6	"	10.2	88	13	20	"	15	70	
and Stake No. 26	3.6	"	10.2	88	13	20	"		320	
Between Stake No. 27	3.3	"	9.6	81	12	15	"		1215	
and Stake No. 28	3.3	"	9.6	77	11	55	"		1155	
Between Stake No. 29	3.4	"	9.8	77	11	55	"		1155	
and Stake No. 30	3.7	"	10.4	88	13	20	"		1320	
Between Stake No. 31	3.5	"	10.0	88	13	20	"		1320	
and Stake No. 32	3.5	"	10.0	84	12	60	"		1260	
Between Stake No. 33	3.9	"	10.8	92	13	80	"		1380	
and Stake No. 34	3.5	"	10.0	92	13	80	"		1380	
Between Stake No. 35	3.5	"	10.0	84	12	60	"		1260	
and Stake No. 36	3.5	"	10.0	84	12	60	"		1260	
				1787	268.05				13.50	281.55

Total Estimated Cost of Whole Work, \$.....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Ditch No. 56.

SECTION	(1)	(2)	(3)	(4)	(5)		(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED	Estimated Cost Per Cubic Yard		Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section		Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 37	3.2	8.0	9.4	77	11	55			11	55
and Stake No. 38	3.4	"	9.8	77	11	55			11	55
Between Stake No. 39	3.3	"	9.6	77	11	55			11	55
and Stake No. 40	3.4	"	9.8	77	11	55			11	55
Between Stake No. 41	3.2	"	9.4	77	11	55			11	55
and Stake No. 42	3.2	"	9.4	73	10	95			10	95
Between Stake No. 43	3.3	"	9.6	73	10	95			10	95
and Stake No. 44	3.1	"	9.2	73	10	95			10	95
Between Stake No. 45	3.4	"	9.8	77	11	55			11	55
and Stake No. 46	3.2	"	9.4	77	11	55			11	55
Between Stake No. 47	3.2	"	9.4	73	10	95			10	95
and Stake No. 48	3.2	"	9.4	73	10	95			10	95
Between Stake No. 49	3.2	"	9.4	73	10	95			10	95
and Stake No. 50	3.2	"	9.4	73	10	95			10	95
Between Stake No. 51	3.3	"	9.6	77	11	55			11	55
and Stake No. 52	3.3	"	9.6	77	11	55			11	55
Between Stake No. 53	3.4	"	9.8	81	12	15			12	15
and Stake No. 54	3.4	"	9.8	81	12	15			12	15
Between Stake No. 55	3.3	"	9.6	77	11	55			11	55
and Stake No. 56	3.3	"	9.6	77	11	55			11	55
				2392	358.80				\$ 358.80	

Total Estimated Cost of Whole Work, \$.....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Ditch No. 56.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) No. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section			(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.	
Between Stake No. 57	3.4	3.0	10.0	81	12	15				12	15
and Stake No. 58	3.4	"	9.6	81	12	15				12	15
Between Stake No. 59	3.3	"	9.6	77	11	53				11	53
and Stake No. 60	3.3	"	9.6	77	11	53				11	53
Between Stake No. 61	3.3	"	9.6	77	11	53				11	53
and Stake No. 62	3.3	"	9.6	77	11	53				11	53
Between Stake No. 63	3.3	"	9.8	77	11	53				11	53
and Stake No. 64	3.3	"	9.6	77	11	53				11	53
Between Stake No. 65	3.3	"	9.6	77	11	53				11	53
and Stake No. 66	3.3	"	9.6	77	11	53				11	53
Between Stake No. 67	3.4	"	10.0	81	12	15				12	15
and Stake No. 68	3.5	"	10.0	84	12	60				12	60
Between Stake No. 69	3.5	"	9.8	84	12	60				12	60
and Stake No. 70	3.4	"	9.8	81	12	15				12	15
Between Stake No. 71	3.4	"	9.8	81	12	15				12	15
and Stake No. 72	3.4	"	9.8	81	12	15				12	15
Between Stake No. 73	3.5	"	10.0	84	12	60				12	60
and Stake No. 74	3.4	"	9.8	81	12	15				12	15
Between Stake No. 75	3.4	"	9.8	81	12	15				12	15
and Stake No. 76	3.4	"	9.8	81	12	15				12	15
				1597	239.53					\$ 239.53	

Total Estimated Cost of Whole Work, \$.....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Ditch No. 56

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) No. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section		(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 77	3.4	3.0	9.8	81	12	15			12	15
and Stake No. 78	3.4	"	9.8	81	12	15			12	15
Between Stake No. 79	3.4	"	9.8	81	12	15			12	15
and Stake No. 80	3.3	"	9.6	77	11	53			11	53
Between Stake No. 81	3.2	"	9.4	73	10	95			10	95
and Stake No. 82	3.1	"	9.2	70	10	50			10	50
Between Stake No. 83	3.2	"	9.4	70	10	50			10	50
and Stake No. 84	3.1	"	9.2	70	10	50			10	50
Between Stake No. 85	3.0	"	9.0	67	10	05			10	05
and Stake No. 86	3.0	"	9.0	67	10	05			10	05
Between Stake No. 87	3.0	"	9.0	67	10	05			10	05
and Stake No. 88	3.0	"	9.0	67	10	05			10	05
Between Stake No. 89	2.9	"	8.8	67	10	05			10	05
and Stake No. 90	3.0	"	9.0	67	10	05			10	05
Between Stake No. 91	3.0	"	9.0	67	10	05			10	05
and Stake No. 92	3.0	"	9.0	67	10	05			10	05
Between Stake No. 93	3.0	"	9.0	67	10	05			10	05
and Stake No. 94	2.6	"	9.2	60	9	00			9	00
Between Stake No. 95	2.5	"	8.0	51	7	65			7	65
and Stake No. 96	2.0	"	7.0	42	6	80			6	80
				1359	203.85				\$ 203.85	

Total Estimated Cost of Whole Work, \$.....

## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Ditch No. 56.

SECTION	(1) DEPTH OF CUT	(2) WIDTH OF CUT AT BOTTOM	(3) WIDTH OF CUT AT TOP	(4) NO. OF CUBIC YARDS TO BE REMOVED	(5) Estimated Cost Per Cubic Yard		(6) Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section		(7) Total Estimated Cost per Section	
					\$	CTS.	\$	CTS.	\$	CTS.
Between Stake No. 96+88	2.8	3.0	8.6	44	6	60				660
and Stake No. 97	2.8	"	8.6	7	1	05				105
Between Stake No. 98	1.0	"	5.0	34	5	10				510
and Stake No. 99	1.1	"	5.2	15	2	25				225
Between Stake No. 100	1.0	"	5.0	15	2	25				225
and Stake No. <sup>100 to 120</sup> in Goose Lake				115	17	20				1725
Between Stake No. 120	0.0	14.0								
and Stake No. 121	2.1	"	18.2	61	9	15				915
Between Stake No. 122	2.1	"	18.2	125	18	75				1875
and Stake No. 123	2.1	"	18.2	125	18	75				1875
Between Stake No. 124	2.1	"	18.2	125	18	75				1875
and Stake No. 125	2.1	"	18.2	125	18	75				1875
Between Stake No. 126	2.1	"	18.2	125	18	75				1875
and Stake No. 127	2.3	"	18.6	132	19	80				1980
Between Stake No. 128	2.1	"	18.2	125	18	75				1875
and Stake No. 129	2.0	"	18.0	122	18	30				1830
Between Stake No. 130	2.0	"	18.0	123	18	45				1845
and Stake No. 131	2.0	"	18.0	123	18	45				1845
Between Stake No. 132	1.8	"	17.6	112	16	80				1680
and Stake No. 133	1.9	"	17.8	108	16	20				1620
				1646	246	90				24690

Total Estimated Cost of Whole Work, \$.....

**EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS.**

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in *County* Ditch No. *56*

SECTION	(1)	(2)	(3)	(4)		(5)	(6)		(7)	
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED		Estimated Cost Per Cubic Yard	Character of Other Expenses, Including Preliminary Expenses And Expense of Inspecting Work until Completed With Total Per Section		Total Estimated Cost per Section	
						D \$ 15 CTS.	\$	CTS.	\$	CTS.
Between Stake No. 133	1.9	14.0	17.8	<i>yds deducted</i>		—	—	—	—	—
and Stake No. 134	1.7	"	17.4		106	15.90				15 90
Between Stake No. 135	1.7	"	17.4		99	17.85				14 85
and Stake No. 136	1.8	"	17.6		<del>102</del> 102	15.30				15 30
Between Stake No. 137	1.6	"	17.2		99	14.85				14 85
and Stake No. 138	2.0	"	18.0		105	15.75				15 75
Between Stake No. 139	1.9	"	17.8	14	97	14.55				14 55
and Stake No. 140	2.0	"	18.0	14	97	14.55				14 55
Between Stake No. 141	2.2	"	18.4	16	109	16.35				16 35
and Stake No. 142	2.7	"	19.4	18	132	19.80				19 80
Between Stake No. 143	2.6	"	19.2	20	143	21.45				21 45
and Stake No. 144	2.6	"	19.2	19	141	21.15				21 15
Between Stake No. 145	4.3	"	22.6	26	85	12.95				12 75
and Stake No. 145	2.2	"	18.4	24	80	12.00				12 00
Between Stake No. 146	1.8	"	17.6	15	103	15.45				15 45
and Stake No. 147	1.6	"	17.2	13	84	12.60				12 60
Between Stake No. 148	1.6	"	17.2	12	80	12.00				12 00
and Stake No. 149	1.6	"	17.2	12	80	12.00				12 00
Between Stake No. 150	1.5	"	17.0	11	78	11.70				11 70
and Stake No. 151	1.6	14.0	17.2	11	78	11.70				11 70
						1898	\$ 284.70			284.70

Total Estimated Cost of Whole Work, \$-----



## EXHIBIT 2 OF ENGINEER'S REPORT IN DITCH PROCEEDINGS

Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of Same, in County Ditch No. 56

SECTION	(1)	(2)	(3)	(4)		(5)	(6)		(7)		
	DEPTH OF CUT	WIDTH OF CUT AT BOTTOM	WIDTH OF CUT AT TOP	NO. OF CUBIC YARDS TO BE REMOVED		Estimated Cost Per Cubic Yard \$ 15 CTS.	Character of Other Expenses, Including Preliminary Expenses and Expense of Inspecting Works Until Completed With Total per Section		\$	CTS.	
Between Stake No. 152	1.9	14.0	17.8	13	89	13 35				13 35	
and Stake No. 153	2.3	"	18.6	16	109	16 35				16 35	
Between Stake No. 154	5.9	"	25.8	114	161	24 15				24 15	
and Stake No. +70	10.2	"	34.4	270	194	29 10				29 10	
Between Stake No. +90	7.0	"	28.0	80	64	9 60				9 60	
and Stake No. 155	7.0	"	}	123	60	18 45	34 feet of 48" Cov Iron Pipe		98	20	116 65
Between Stake No. +14	3.0	"									
and Stake No. +50	2.9	"	13.8	7	60	9 00				9 00	
Between Stake No. 156	3.3	"	20.6	9	189	28 35				28 35	
and Stake No. 157	2.8	"	19.6	17	176	26 40				26 40	
Between Stake No. 158	3.1	"	20.2	18	167	25 05				25 05	
and Stake No. 159	3.1	"	20.2	19	177	26 55				26 55	
Between Stake No. 160	2.9	"	19.8	17	172	25 80				25 80	
and Stake No. 161	2.7	"	19.4	15	159	23 85				23 85	
Between Stake No. 162	1.9	"	17.8	12	127	19 05				19 05	
and Stake No. 163	1.9	"	17.8	12	96	14 40				14 40	
Between Stake No. and Stake No.					2063	\$309 45				\$407 65	

Total Estimated Cost of Whole Work, \$.....