

Ditch No 6
EXHIBIT 2.

VIEWERS' REPORT

—IN—

DITCH PROCEEDINGS.

No. 680.—Pioneer Press Co., St. Paul, Minn.

Filed June 5th 1890
W. M. Putnam
County Auditor

72D JOSE
WELBURY
ONE OF

EXHIBIT 2 OF VIEWERS' REPORT IN DITCH PROCEEDINGS.

Showing Time and Manner in which same must be done. Ditch No. 6

SECTION	TIME WITHIN WHICH WORK MUST BE DONE	MANNER IN WHICH WORK MUST BE DONE	MATERIALS USED	COST OF MATERIALS AND WORK
Stake No. <u>0 A</u> TO Stake No. <u>50</u>	June 1, 1891	Ditch to be thrown at least two feet from edge of the ditch		
Stake No. <u>50</u> to Stake No. <u>51</u>	June 1, 1891	at the bridge between these two stakes the bridge must be thoroughly rebuilt in a workmanlike manner using planks 2" thick & at least 14 feet long. The abutments to be built of logs or other material subject to the order of the County Surveyor or the Engineer in Charge	Work on the abutments Plank 14 ft long 2 inches thick 100 feet Board Measure @ \$13 per M	\$3 70 \$1 30
Stake No. <u>51</u> to Stake No. <u>114</u>	June 1, 1891	Ditch to be disposed of as above between Stake No. <u>0 A</u> to Stake No. <u>50</u>		\$5 00
Stake No. <u>114</u> to Stake No. <u>115</u>	June 1, 1891	at the Bridge at this point the same specifications as an above bridge between Stake No. <u>50</u> and Stake No. <u>51</u>	Work on abutments Plank as above 100 feet Board Measure @ \$13 per M	\$3 70 \$1 30 \$5 00
Stake No. <u>115</u> to Stake No. <u>141</u>	December 1, 1890	Ditch to be disposed of as above between Stake No. <u>0 A</u> and Stake No. <u>50</u>		
Stake No. <u>141</u> to Stake No. <u>142</u>	December 1, 1890	Bridge to be constructed according to above specifications between Stake No. <u>50</u> + Stake No. <u>51</u>	Work on abutments Plank 100 feet Board Measure @ \$13 per M	\$3 70 \$1 30 \$5 00
Stake No. <u>142</u> to Stake No. <u>179</u>	December 1, 1890	Ditch to be disposed of as above between Stake No. <u>0 A</u> and Stake No. <u>50</u>		
Stake No. <u>179</u> to Stake No. <u>180</u>	December 1, 1890	Bridge to be constructed according to above specifications between Stake No. <u>141</u> + Stake No. <u>142</u>	Work on abutments 100 ft 2 inch Plank 14 ft long @ \$13 per M	\$3 70 \$1 30 \$5 00
Stake No. <u>180</u> to Stake No. <u>210+11</u>	November 15 1890	Ditch to be disposed of as above between Stake No. <u>0 A</u> + Stake No. <u>50</u> Stakes are on Right Bank of ditch going down stream		
Stake No. <u>182</u> to Stake No. <u>183</u>	November 15 1890	Bridge to be constructed according to above specifications	Work on abutments 100 feet (Board Measure) Plank 14 ft long @ \$13 per M	\$3 70 \$1 30 \$5 00