

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 8

(11)

SECTION	DEPTH OF CUT Feet	WIDTH OF CUT AT BOTTOM Feet	WIDTH OF CUT AT TOP Feet	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. <u>278</u>				3985	
and Stake No. <u>279</u>	3.1	3.0	7.6	50	\$ .08
<u>280</u>	3.2	3.0	7.8	53	\$ .08
<u>281</u>	3.4	3.0	8.1	56	\$ .08
<u>282</u>	3.6	3.0	8.4	60	\$ .08
<u>283</u>	3.4	3.0	8.1	60	\$ .08
<u>284</u>	3.4	3.0	8.1	58	\$ .08
<u>285</u>	3.5	3.0	8.3	60	\$ .08
<u>286</u>	3.3	3.0	8.0	58	\$ .08
<u>287</u>	2.6	3.0	6.9	35	\$ .08
<u>288</u>	2.3	3.0	6.5	12	\$ .08
<u>289</u>	3.1	3.0	7.6	12	\$ .18
<u>290</u>	2.2	3.0	6.3	12	\$ .08
<u>291</u>	2.1	3.0	6.2	10	\$ .08
<u>292</u>	1.6	3.0	5.4	19	\$ .08
<u>293</u>	2.3	3.0	6.5	9	\$ .08
<u>294</u>	1.9	3.0	5.8	0	\$ .08
<u>295</u>	2.0	3.0	6.0	0	\$ .08
<u>296</u>	2.0	3.0	6.0	0	\$ .08
<u>297</u>	2.5	3.0	6.8	5	\$ .08
<u>298</u>	2.5	3.0	6.8	5	\$ .08
<u>299</u>	2.3	3.0	6.5	6	\$ .08
<u>300</u>	2.7	3.0	7.1	14	\$ .08
<u>301</u>	2.8	3.0	7.2	22	\$ .08
<u>302</u>	2.5	3.0	6.8	30	\$ .08
<u>303</u>	2.8	3.0	7.2	27	\$ .08
<u>304</u>	2.7	3.0	7.1	23	\$ .08
<u>305</u>	2.8	3.0	7.2	20	\$ .08
<u>306</u>	3.2	3.0	7.8	30	\$ .08
				4671	
					<i>Totals</i>

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and Cost of same, in Ditch No. 8

(12)

SECTION	DEPTH OF CUT feet	WIDTH OF CUT AT BOTTOM feet	WIDTH OF CUT AT TOP feet	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD
Between Stake No. <u>306</u>				<u>4671</u>	
and Stake No. <u>307</u>	<u>3.0</u>	<u>3.0</u>	<u>7.5</u>	<u>32</u>	<u>\$ .08</u>
<u>308</u>	<u>3.4</u>	<u>3.0</u>	<u>8.1</u>	<u>40</u>	<u>\$ .08</u>
<u>309</u>	<u>3.4</u>	<u>3.0</u>	<u>8.1</u>	<u>40</u>	<u>\$ .08</u>
<u>310</u>	<u>3.3</u>	<u>3.0</u>	<u>8.0</u>	<u>30</u>	<u>\$ .08</u>
<u>311</u>	<u>4.4</u>	<u>3.0</u>	<u>9.6</u>	<u>32</u>	<u>\$ .08</u>
<u>312</u>	<u>3.9</u>	<u>3.0</u>	<u>8.9</u>	<u>50</u>	<u>\$ .08</u>
<u>313</u>	<u>5.2</u>	<u>3.0</u>	<u>11.0</u>	<u>60</u>	<u>\$ .08</u>
<u>314</u>	<u>3.4</u>	<u>3.0</u>	<u>8.1</u>	<u>60</u>	<u>\$ .08</u>
<u>315</u>	<u>3.8</u>	<u>3.0</u>	<u>8.7</u>	<u>36</u>	<u>\$ .08</u>
<u>316</u>	<u>3.6</u>	<u>3.0</u>	<u>8.4</u>	<u>40</u>	<u>\$ .08</u>
<u>317</u>	<u>4.0</u>	<u>3.0</u>	<u>9.0</u>	<u>45</u>	<u>\$ .08</u>
<u>318</u>	<u>3.0</u>	<u>3.0</u>	<u>7.5</u>	<u>31</u>	<u>\$ .08</u>
<u>319</u>	<u>3.6</u>	<u>3.0</u>	<u>8.4</u>	<u>25</u>	<u>\$ .08</u>
<u>320</u>	<u>3.7</u>	<u>3.0</u>	<u>8.6</u>	<u>40</u>	<u>\$ .08</u>
<u>321</u>	<u>3.5</u>	<u>3.0</u>	<u>8.3</u>	<u>40</u>	<u>\$ .08</u>
<u>322</u>	<u>3.4</u>	<u>3.0</u>	<u>8.1</u>	<u>36</u>	<u>\$ .08</u>
<u>323</u>	<u>3.8</u>	<u>3.0</u>	<u>8.7</u>	<u>41</u>	<u>\$ .08</u>
<u>324</u>	<u>3.4</u>	<u>3.0</u>	<u>8.1</u>	<u>43</u>	<u>\$ .08</u>
<u>325</u>	<u>3.9</u>	<u>3.0</u>	<u>8.9</u>	<u>42</u>	<u>\$ .08</u>
<u>326</u>	<u>4.1</u>	<u>3.0</u>	<u>9.2</u>	<u>46</u>	<u>\$ .08</u>
<u>327</u>	<u>4.1</u>	<u>3.0</u>	<u>8.7</u>	<u>40</u>	<u>\$ .08</u>
<u>328</u>	<u>3.8</u>	<u>3.0</u>	<u>7.8</u>	<u>41</u>	<u>\$ .08</u>
<u>329</u>	<u>3.2</u>	<u>3.0</u>	<u>8.6</u>	<u>45</u>	<u>\$ .08</u>
<u>330</u>	<u>3.7</u>	<u>3.0</u>	<u>8.1</u>	<u>45</u>	<u>\$ .08</u>
<u>331</u>	<u>3.4</u>	<u>3.0</u>	<u>7.8</u>	<u>40</u>	<u>\$ .08</u>
<u>332</u>	<u>3.2</u>	<u>3.0</u>	<u>7.2</u>	<u>33</u>	<u>\$ .08</u>
<u>333</u>	<u>2.8</u>	<u>3.0</u>	<u>10.4</u>	<u>25</u>	<u>\$ .08</u>
<u>334</u>	<u>4.9</u>	<u>3.0</u>	<u>8.6</u>	<u>41</u>	<u>\$ .08</u>
				<u>5780</u>	
					<i>Totals</i>

EXHIBIT 1 OF VIEWERS' REPORT IN DITCH PROCEEDINGS, Showing Estimated Depth of Cut, Width, No. of Cubic Yards Removed and  
 (13) Cost of same, in Ditch No. 8

SECTION	DEPTH OF CUT feet	WIDTH OF CUT AT BOTTOM feet	WIDTH OF CUT AT TOP feet	NO. OF CUBIC YARDS REMOVED	ESTIMATED COST PER CUBIC YARD	
Between Stake No. 334				5780		
and Stake No. 335	3.7	3.0	8.6	55	\$ .08	
336	3.6	3.0	8.4	50	\$ .08	
337	3.8	3.0	8.7	43	\$ .08	
338	3.6	3.0	8.4	40	\$ .08	
339	3.4	3.0	8.1	41	\$ .08	
340	3.6	3.0	8.4	41	\$ .08	
341	3.4	3.0	8.4	39	\$ .08	Private ditch ends at sta 341
342	2.8	3.0	7.2	40	\$ .08	
343	3.3	3.0	8.0	52	\$ .08	
344	3.0	3.0	7.5	64	\$ .08	
345	3.0	3.0	7.5	52	\$ .08	
346	3.5	3.0	8.3	67	\$ .08	
347	2.3	3.0	6.5	53	\$ .08	
348	2.4	3.0	6.6	24	\$ .08	
349	2.7	3.0	7.1	22	\$ .08	
350	2.8	3.0	7.2	48	\$ .08	
351	3.6	3.0	8.4	64	\$ .08	
351+06	0.0	3.0		4		
				6579		
				6179 cu. yds @ \$ .08 =		\$ 494.16
				402 " " " @ \$ .10 =		\$ 40.20
				6579		Totals \$ 534.36

