

HISTORY OF GOVERNMENT CORNER

Page No. 115

County of Anoka

State of Minnesota

East 1/4 Corner of Sec. 33 Township 32 Range 24

CORNER HISTORY:

June 1957 - Cartwright and Olson indicate that corner is a 1-1/2" X 2' iron pipe down 1' on north edge of road. Established ties to monument.

July 29, 1960 - Found iron pipe down 0.3' and updated ties.

April 17, 1962 - Found 1" iron pipe and updated ties due to road construction.

June 12, 1964 - Replaced iron pipe with a cast iron monument set depth of monument in type of surface. Updated ties.

August 20, 1964 - Found cast iron monument and updated ties.

July 23, 1968 - Found cast iron monument and updated ties.

July 7, 1972 - Found cast iron monument and updated ties.

February 26, 1976 - Set construction ties (P.K. nails 100' east and west of corner) prior to road construction.

December 30, 1977 - Set cast iron monument flush with the surface after road construction using construction ties. Updated ties.

July 27, 1978 - Found cast iron monument and updated ties.

September 26, 1978 - Raised cast iron monument and updated ties.

June 7, 1979 - Found cast iron monument and updated ties.

August 2, 1988 - Found cast iron monument and updated ties.

July 19, 1993 - Found cast iron monument and updated ties.

May 4, 1999 - Set construction ties and removed cast iron monument prior to road construction.

October 25, 1999 - Set cast iron monument after road construction using construction ties. Updated ties.

July 19, 2000 - Found cast iron monument and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods. Updated ties.

November 4, 2010 - Found cast iron monument flush with the surface and updated ties.