

HISTORY OF GOVERNMENT CORNER

Page No. 33

County of Anoka

State of Minnesota

West 1/4 Corner of Sec. 11 Township 32 Range 24

CORNER HISTORY:

January 3, 1962 - Set 12' X 1 1/2" iron pipe in swamp using area resurvey. Top 3'± is above ground with 6" painted red and white bands. No features available to establish ties.

Summer 1968 - Area too wet to access corner.

Summer 1972 - Area too wet to access corner.

March 21, 1983 - Found 1 1/2" red and white iron pipe bent over.

April 12, 1983 - Replaced bent 1 1/2" red and white iron pipe with a new red and white iron pipe using area resurvey. Also set steel witness posts with punchmarks and signs attached to be used as ties.

December 3, 1984 - Found red and white iron pipe and updated ties.

July 23, 1987 - Set construction ties using 1/2" iron pipes with signs and posts set near iron pipes prior to road construction.

May 24, 1988 - Set cast iron monument flush with surface after road construction using construction ties. Also set P.K. nails 2.00' north and east of monument and updated ties.

July 15, 1993 - Found cast iron monument and updated ties.

October 1, 1993 - Found cast iron monument and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods. Updated ties.

January 28, 2011 - Found cast iron monument broken.

February 7, 2011 - Verified position of broken cast iron monument by Static GPS methods.

February 15, 2011 - Replaced broken cast iron monument with a new cast iron monument and updated ties.

June 8, 2012 - Found cast iron monument missing.

August 15, 2012 - Reset position of missing cast iron monument with a P.K. nail using VRS methods and verified position by Static GPS methods.

August 27, 2012 - Replaced P.K. nail with a new cast iron monument and verified that ties were accurate.