

HISTORY OF GOVERNMENT CORNER

Page No. 6

County of Anoka

State of Minnesota

North 1/4 Corner of Sec. 4 Township 32 Range 24

CORNER HISTORY:

September 27, 1961 - Set 1/2" iron pipe in centerline of County Road No. 58 using government proration on a straight line between the Northwest corner and the Northeast corner of Section 4 and established ties to monument.

August 13, 1964 - Found 1/2" iron pipe and updated ties.

July 5, 1968 - Replaced 1/2" iron pipe with a cast iron monument and set P.K. nails 2.00' North and East. Updated ties.

June 20, 1972 - Found cast iron monument and updated ties.

May 24, 1976 - Found cast iron monument and updated ties.

May 29, 1979 - Found cast iron monument and updated ties.

June 23, 1982 - Found cast iron monument and updated ties.

May 30, 1985 - Found cast iron monument and updated ties.

July 29, 1988 - Found cast iron monument and updated ties.

July 14, 1993 - Found cast iron monument and updated ties.

May 11, 1999 - Set construction ties and removed cast iron monument prior to road construction.

May 11, 1999 - Set cast iron monument flush with surface after road construction using construction ties. Updated ties.

July 25, 2000 - Found cast iron monument and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods. Updated ties.

January 4, 2011 - Found cast iron monument flush with the road surface and updated ties.