

HISTORY OF GOVERNMENT CORNER

Page No. 86

County of Anoka

State of Minnesota

Southeast Corner of Sec. 20 Township 32 Range 24

CORNER HISTORY:

July 1, 1963 - Found 8" square granite monument set down 0.7'. Set railroad spike above monument and flush with the surface. Also set P.K. nails 3.00' northeast and northwest of monument. Established ties to monument.

August 25, 1964 - Found railroad spike and updated ties.

July 22, 1968 - Found railroad spike and updated ties.

July 5, 1972 - Found railroad spike and updated ties.

August 6, 1980 - Lowered granite monument 4'± prior to road construction.

October 1, 1980 - Set cast iron monument above granite monument and flush with the surface after road construction. Updated ties.

June 25, 1982 - Found cast iron monument and updated ties.

May 28, 1985 - Found cast iron monument and updated ties.

August 16, 1988 - Found cast iron monument and updated ties.

July 19, 1993 - Found cast iron monument and updated ties.

April 16, 1999 - Found cast iron monument and updated ties.

October 12, 2000 - Found cast iron monument and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods.

April 15, 2004 - Set construction ties and removed cast iron monument prior to road construction.

August 16, 2005 - Found that cast iron monument needs replacing.

September 7, 2005 - Replaced cast iron monument and updated ties.

October 13, 2010 - Found cast iron monument flush with the surface and updated ties.