

HISTORY OF GOVERNMENT CORNER

Page No. 94

County of Anoka

State of Minnesota

Witness Corner of Sec. 29 Township 32 Range 24
(Witness corners to W 1/4 Sec. 29)

CORNER HISTORY:

November 15, 1962 - Found 1" iron pipe down 1' in south rut of east-west trail across field. Set 3/4" iron pipe above 1" iron pipe and flush with trail. Also set steel snow fence post 1'± south of iron pipe. Established ties to monument.

November 12, 1964 - Replaced 1" iron pipe with a cast iron monument set flush with the surface. No ties available in the area. Set steel fence posts 0.5' east and west of monument.

July 19, 1972 - Found cast iron monument down 0.2'± and updated ties. Set steel fence post 1.5' north of monument.

June 9, 1976 - Found cast iron monument and updated ties.

June 11, 1979 - Found cast iron monument and updated ties.

June 21, 1982 - Found cast iron monument and updated ties.

August 11, 1988 - Found cast iron monument and updated ties.

September 22, 1992 and November 30, 1992 - Set cast iron monuments as Witness corners to the West Quarter corner of Section 29 using area resurvey. Position of W1/4 corner falls in house. Witness corners are north and south of W¹/₄ corner. Set sign and post on south side of southerly monument and established ties to monuments.

July 30, 1993 - Found cast iron monument Witness corners and updated ties.

January 14, 2011 - Found cast iron monument Witness corners and updated ties. North Witness corner is 4'± south of centerline of 145th Avenue NW and south Witness corner is down 0.5'± and in backyard of House No. 3984.