

HISTORY OF GOVERNMENT CORNER

Page No. 10

County of Anoka

State of Minnesota

North 1/4 Corner of Sec. 5 Township 31 Range 24

CORNER HISTORY:

August 9, 1955 - C.E. Coulter found granite monument down 1.0' in centerline of Round Lake Blvd. Set iron pipe flush with surface and established ties to monument.

November 1959 - N.C. Hoiium found granite monument down 1.5' and updated ties.

August 2, 1960 - Found iron pipe down 0.3' over granite monument and updated ties.

September 14, 1964 - Found iron pipe and updated ties.

July 14, 1966 - Found iron pipe and updated ties.

July 23, 1970 - Replaced iron pipe, down 0.2', over granite monument, down 1'±, with a shortened cast iron monument set flush with surface on top of granite monument and updated ties. Set P.K. nails 2.00' North and East.

July 5, 1974 - Found cast iron monument and updated ties.

June 16, 1977 - Found cast iron monument and updated ties. Set P.K.nails North and East.

September 21, 1979 - Found cast iron monument and updated ties. Monument is 3.5'± east of centerline.

June 25, 1980 - Found cast iron monument and updated ties.

June 16, 1986 - Found cast iron monument and updated ties.

April 17, 1990 - Set construction ties and prior to road construction.

May 18, 1994 - Set cast iron monument flush with surface on top of granite monument after road construction using construction ties. Monument is next to concrete curb. Updated ties.

August 8, 1994 - Found cast iron monument and updated ties.

November 16, 2000 - Found cast iron monument and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods. Updated ties.

March 25, 2010 - Found cast iron monument and updated ties.