

# HISTORY OF GOVERNMENT CORNER

Page No. 53

County of Anoka

State of Minnesota

## South 1/4 Corner of Sec. 9 Township 31 Range 24

### **CORNER HISTORY:**

May 20, 1944 - H.A. Cartwright found concrete monument down 1.0'±. Established ties to monument.

October 7, 1958 - Harry S. Johnson found concrete monument and updated ties.

July 15, 1960 - Found concrete monument down 1.0'± with a railroad spike on the south side and an iron pipe on center of monument flush with the surface. Updated ties.

June 4, 1964 - Found iron pipe on top of concrete monument and updated ties.

August 21, 1964 - Set cast iron monument on top of concrete monument in centerline-centerline of new road and updated ties.

July 13, 1966 - Found cast iron monument and updated ties.

July 24, 1970 - Found cast iron monument and concrete monument missing. Reset position of corner with a cast iron monument set flush with the surface using ties. Set P.K. nails 2.00' north and east and updated ties.

July 2, 1974 - Found cast iron monument and raised it to the surface. Updated ties.

June 21, 1977 - Found cast iron monument and raised it to the surface. Set P.K. nails north and east and updated ties.

July 2, 1980 - Replaced broken cast iron monument with a new cast iron monument set flush with the surface. Updated ties.

July 18, 1983 - Found cast iron monument and updated ties.

June 13, 1986 - Found cast iron monument and updated ties.

August 12, 1994 - Found cast iron monument and updated ties.

August 29, 1995 - Found cast iron monument and raised it to the surface. Updated ties.

August 23, 2001 - Found cast iron monument and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods. Updated ties.

March 24, 2010 - Found cast iron monument flush with the surface and updated ties.