

# HISTORY OF GOVERNMENT CORNER

Page No. 83

County of Anoka

State of Minnesota

## South 1/4 Corner of Sec. 22 Township 31 Range 24

### **CORNER HISTORY:**

**November 7, 1944** - H.A. Cartwright found concrete monument. Established ties to monument.

**July 26, 1960** - Found iron pipe flush with the surface over the center of concrete monument down 12" with an iron pipe on north side flush with monument. Updated ties.

**June 4, 1964** - Found iron pipe and concrete monument. Updated ties.

**August 21, 1967** - Found iron pipe and concrete monument. Updated ties.

**July 31, 1970** - Corner located at 3/8" hole drilled in manhole cover with P.K. nails set 2.00' north and west.

**July 16, 1974** - Found location of corner on manhole cover and updated ties.

**July 3, 1980** - Found location of corner on manhole cover and updated ties.

**June 17, 1986** - Found location of corner on manhole cover and updated ties.

**August 15, 1994** - Found location of corner on manhole cover and updated ties.

**September 10, 1997** - Set construction ties prior to road construction.

**October 10, 1997** - Reset position of corner on manhole cover after construction and set P.K. nails south and west. Updated ties.

**August 23, 2001** - Reset position of corner on manhole cover and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods. Updated ties.

**January 31, 2011** - Reset position of corner on manhole cover and updated ties.