

HISTORY OF GOVERNMENT CORNER

Page No. 96

County of Anoka

State of Minnesota

Southeast Corner of Sec. 36 Township 31 Range 24

CORNER HISTORY:

March 20, 1943 - H.A. Cartwright found 4"x8" limestone monument up 16". Established ties to monument.

July 1, 1960 - Found 4"x8" limestone monument up 16" and updated ties.

October 31, 1962 - Replaced broken limestone monument with a 1"x7' iron pipe set up 3' and updated ties. Top 4' of iron pipe is painted with 6" red and white bands.

November 17, 1965 - Replaced 1"x7' iron pipe (bent and moved by road construction) with a cast iron monument set flush with the surface. Updated ties.

July 11, 1966 - Found cast iron monument and updated ties.

August 19, 1969 - Replaced solid cast iron monument with an extendible cast iron monument set flush with the surface. Set P.K. nails 2.00' north and east of monument. Updated ties.

May 10, 1973 - Checked all ties including construction ties and removed cast iron monument prior to construction.

July 19, 1974 - Found cast iron monument (date reset unknown) and updated ties.

October 12, 1981 - Set construction tie prior to road construction.

May 23, 1982 - Set cast iron monument flush with surface after road construction using construction ties. Set P.K. nails 2.00' north and east of monument. Updated ties.

June 13, 1986 - Found cast iron monument and updated ties.

August 27, 1990 - Found cast iron monument and updated ties.

December 9, 1993 - Replaced cast iron monument with a new cast iron monument. Updated ties.

August 15, 1994 - Found cast iron monument and updated ties.

July 29, 1999 - Found cast iron monument and established NAD 1983 (1996 Adjustment) Anoka County Project Coordinates by Static GPS methods. Updated ties.

October 21, 2010 - Replaced cast iron monument with a new cast iron monument after construction. Updated ties.